



## 556-2024B ADDENDUM 10

### ST. JAMES CIVIC CENTER FACILITY EXPANSION

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: November 19, 2024  
BY: Janelle Fillion, LM-ESP  
TELEPHONE NO. 204 942-0681

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

#### **PART B – BIDDING PROCEDURES**

Revise: B1.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, November 28, 2024.

#### **NMS SPECIFICATIONS**

##### **08 14 16 Flush Wood Doors**

Revise: 2.5.3 to read: Glazed openings: Finished with glazing stops, both sides.

Revise 2.7.3 to read: Glazing stops: Flush wood stained to match high pressure laminate, mitered corners. Stop depth to include a 6mm overhang, and thickness to include a 6mm overlap at glazing opening edge.

#### **CLARIFICATION**

Q1: On drawing E4.2 the data rack detail shows multiple lines between the new wall cabinet and the existing data cabinet but there is no description of what they represent. Could you please confirm the backbone cable requirements?

A1: One (1) CAT3 to existing bix field. Install within minimum 1-1/4" conduit

Two (2) CAT6A copper backbone to existing MDC. Install within minimum 1-1/4" conduit.

CAT3 cable from new data rack to existing bix field to be a 25 pair CAT3 cable.