



THE CITY OF WINNIPEG

TENDER

TENDER NO. 1025-2025

OLYMPIC PARK AND GATEWAY COMMUNITY CENTRE SHELTERS & PATHWAYS

TABLE OF CONTENTS

PART A - BID SUBMISSION

Form A: Bid/Proposal

Form B: Prices

PART B - BIDDING PROCEDURES

B1. Contract Title	1
B2. Submission Deadline	1
B3. Site Investigation	1
B4. Enquiries	1
B5. Confidentiality	1
B6. Addenda	2
B7. Substitutes	2
B8. Bid Components	3
B9. Bid	3
B10. Prices	4
B11. Disclosure	4
B12. Conflict of Interest and Good Faith	4
B13. Qualification	6
B14. Opening of Bids and Release of Information	7
B15. Irrevocable Bid	7
B16. Withdrawal of Bids	7
B17. Evaluation of Bids	7
B18. Award of Contract	8

PART C - GENERAL CONDITIONS

C0. General Conditions	1
------------------------	---

PART D - SUPPLEMENTAL CONDITIONS

General

D1. General Conditions	1
D2. Scope of Work	1
D3. Site Investigation Due Diligence and Risk	1
D4. Definitions	1
D5. Contract Administrator	2
D6. Contractor's Supervisor	2

Submissions

D7. Authority to Carry on Business	2
D8. Safe Work Plan	2
D9. Insurance	2
D10. Contract Security	3
D11. Subcontractor List	4
D12. Detailed Work Schedule	5
D13. Park Access Restrictions	5

Schedule of Work

D14. Commencement	5
D15. Substantial Performance	6
D16. Total Performance	6
D17. Liquidated Damages	6
D18. Scheduled Maintenance	7

Control of Work

D19. Job Meetings	7
D20. Prime Contractor – The Workplace Safety and Health Act (Manitoba)	7
D21. The Workplace Safety and Health Act (Manitoba) – Qualifications	7

Warranty

D22. Warranty	7
---------------	---

Indemnity

D23. Indemnity	8
Form J: Subcontractor List	9

PART E - SPECIFICATIONS

General

E1. Applicable Specifications and Drawings	1
E2. Hazardous Materials	2
E3. Existing Services and Utilities	2
E4. Access To Site	2
E5. Permits, Notices, Licenses, Certificates, Laws and Rules	2
E6. Damage to Existing Structures, Trees and Property	2
E7. Pedestrian Safety And Traffic Management	3
E8. Protection of the Survey Infrastructure	3
E9. Site Enclosures	4
E10. Site Restoration	4

Site Development

E11. Stakes and Marks	4
E12. Tree Removal	4
E13. Removals	5
E14. Excavation and Grading	6
E15. Asphalt Pavement	7
E16. Shade Structure	10
E17. Chain Link Fencing	11
E18. Site Furnishings	12
E19. Cast-in-place concrete foundations	14
E20. Topsoil and Sod	15

PART B - BIDDING PROCEDURES

B1. CONTRACT TITLE

B1.1 Olympic Park and Gateway Community Centre Shelters & Pathways

B2. SUBMISSION DEADLINE

B2.1 The Submission Deadline is 4:00pm Winnipeg time, February 13, 2026.

B2.2 The Contract Administrator or the Manager of Purchasing may extend the Submission Deadline by issuing an addendum at any time prior to the time and date specified in B2.1.

B3. SITE INVESTIGATION

B3.1 Further to C3.1, the Bidder may view the Site without making an appointment.

B3.2 The Bidder is responsible for inspecting the Site, the nature of the Work to be done and all conditions that might affect their Bid or their performance of the Work, and shall assume all risk for conditions existing or arising in the course of the Work which have been or could have been determined through such inspection.

B4. ENQUIRIES

B4.1 All enquiries shall be directed to the Contract Administrator identified in D5.1.

B4.2 If the Bidder finds errors, discrepancies or omissions in the Tender, or is unsure of the meaning or intent of any provision therein, the Bidder shall notify the Contract Administrator of the error, discrepancy or omission, or request a clarification as to the meaning or intent of the provision at least five (5) Business Days prior to the Submission Deadline.

B4.3 Responses to enquiries which, in the sole judgment of the Contract Administrator, require a correction to or a clarification of the Tender will be provided by the Contract Administrator to all Bidders by issuing an addendum.

B4.4 Responses to enquiries which, in the sole judgment of the Contract Administrator, do not require a correction to or a clarification of the Tender will be provided by the Contract Administrator only to the Bidder who made the enquiry.

B4.5 The Bidder shall not be entitled to rely on any response or interpretation received pursuant to B4 unless that response or interpretation is provided by the Contract Administrator in writing.

B4.6 Any enquiries concerning submitting through MERX should be addressed to:
MERX Customer Support
Phone: 1-800-964-6379
Email: merx@merx.com

B5. CONFIDENTIALITY

B5.1 Information provided to a Bidder by the City or acquired by a Bidder by way of further enquiries or through investigation is confidential. Such information shall not be used or disclosed in any way without the prior written authorization of the Contract Administrator. The use and disclosure of the confidential information shall not apply to information which:

- (a) was known to the Bidder before receipt hereof; or
- (b) becomes publicly known other than through the Bidder; or
- (c) is disclosed pursuant to the requirements of a governmental authority or judicial order.

B5.2 The Bidder shall not make any statement of fact or opinion regarding any aspect of the Tender to the media or any member of the public without the prior written authorization of the Contract Administrator.

B6. ADDENDA

B6.1 The Contract Administrator may, at any time prior to the Submission Deadline, issue addenda correcting errors, discrepancies or omissions in the Tender, or clarifying the meaning or intent of any provision therein.

B6.2 The Contract Administrator will issue each addendum at least two (2) Business Days prior to the Submission Deadline, or provide at least two (2) Business Days by extending the Submission Deadline.

B6.3 Addenda will be available on the MERX website at www.merx.com.

B6.4 The Bidder is responsible for ensuring that they have received all addenda and is advised to check the MERX website for addenda regularly and shortly before the Submission Deadline, as may be amended by addendum.

B6.5 The Bidder shall acknowledge receipt of each addendum in Paragraph 10 of Form A: Bid/Proposal. Failure to acknowledge receipt of an addendum may render a Bid non-responsive.

B6.6 Notwithstanding B4, enquiries related to an Addendum may be directed to the Contract Administrator indicated in D5.

B7. SUBSTITUTES

B7.1 The Work is based on the Plant, Materials and methods specified in the Tender.

B7.2 Substitutions shall not be allowed unless application has been made to and prior approval has been granted by the Contract Administrator in writing.

B7.3 Requests for approval of a substitute will not be considered unless received in writing by the Contract Administrator at least five (5) Business Days prior to the Submission Deadline.

B7.4 The Bidder shall ensure that any and all requests for approval of a substitute:

- (a) provide sufficient information and details to enable the Contract Administrator to determine the acceptability of the Plant, Material or method as either an approved equal or alternative;
- (b) identify any and all changes required in the applicable Work, and all changes to any other Work, which would become necessary to accommodate the substitute;
- (c) identify any anticipated cost or time savings that may be associated with the substitute;
- (d) certify that, in the case of a request for approval as an approved equal, the substitute will fully perform the functions called for by the general design, be of equal or superior substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance; and
- (e) certify that, in the case of a request for approval as an approved alternative, the substitute will adequately perform the functions called for by the general design, be similar in substance to that specified, is suited to the same use and capable of performing the same function as that specified and can be incorporated into the Work, strictly in accordance with the proposed work schedule and the dates specified in the Supplemental Conditions for Substantial Performance and Total Performance.

- B7.5 The Contract Administrator, after assessing the request for approval of a substitute, may in their sole discretion grant approval for the use of a substitute as an “approved equal” or as an “approved alternative”, or may refuse to grant approval of the substitute.
- B7.6 The Contract Administrator will provide a response in writing, at least two (2) Business Days prior to the Submission Deadline, to the Bidder who requested approval of the substitute.
- B7.6.1 The Contract Administrator will issue an Addendum, disclosing the approved materials, equipment, methods and products to all potential Bidders. The Bidder requesting and obtaining the approval of a substitute shall be responsible for disseminating information regarding the approval to any person or persons they wish to inform.
- B7.7 If the Contract Administrator approves a substitute as an “approved equal”, any Bidder may use the approved equal in place of the specified item.
- B7.8 If the Contract Administrator approves a substitute as an “approved alternative”, any Bidder bidding that approved alternative may base their Total Bid Price upon the specified item but may also indicate an alternative price based upon the approved alternative. Such alternatives will be evaluated in accordance with B17.
- B7.9 No later claim by the Contractor for an addition to the Total Bid Price because of any other changes in the Work necessitated by the use of an approved equal or an approved alternative will be considered.

B8. BID COMPONENTS

- B8.1 The Bid shall consist of the following components:
- (a) Form A: Bid/Proposal; and
 - (b) Form B: Prices.
- B8.2 All components of the Bid shall be fully completed or provided, and submitted by the Bidder no later than the Submission Deadline, with all required entries made clearly and completely.
- B8.3 The Bid shall be submitted electronically through MERX at www.merx.com.
- B8.3.1 Bids will **only** be accepted electronically through MERX.
- B8.4 Bidders are advised that inclusion of terms and conditions inconsistent with the Tender document, including the General Conditions, will be evaluated in accordance with B17.1(a).

B9. BID

- B9.1 The Bidder shall complete Form A: Bid/Proposal, making all required entries.
- B9.2 Paragraph 2 of Form A: Bid/Proposal shall be completed in accordance with the following requirements:
- (a) if the Bidder is a sole proprietor carrying on business in their own name, their name shall be inserted;
 - (b) if the Bidder is a partnership, the full name of the partnership shall be inserted;
 - (c) if the Bidder is a corporation, the full name of the corporation shall be inserted;
 - (d) if the Bidder is carrying on business under a name other than their own, the business name and the name of every partner or corporation who is the owner of such business name shall be inserted.
- B9.2.1 If a Bid is submitted jointly by two or more persons, each and all such persons shall identify themselves in accordance with B9.2.
- B9.3 In Paragraph 3 of Form A: Bid/Proposal, the Bidder shall identify a contact person who is authorized to represent the Bidder for purposes of the Bid.

- B9.4 Paragraph 13 of Form A: Bid/Proposal shall be signed in accordance with the following requirements:
- (a) if the Bidder is a sole proprietor carrying on business in their own name, it shall be signed by the Bidder;
 - (b) if the Bidder is a partnership, it shall be signed by the partner or partners who have authority to sign for the partnership;
 - (c) if the Bidder is a corporation, it shall be signed by their duly authorized officer or officers;
 - (d) if the Bidder is carrying on business under a name other than their own, it shall be signed by the registered owner of the business name, or by the registered owner's authorized officials if the owner is a partnership or a corporation.
- B9.4.1 The name and official capacity of all individuals signing Form A: Bid/Proposal should be entered below such signatures.
- B9.4.2 All signatures shall be original.
- B9.5 If a Bid is submitted jointly by two or more persons, the word "Bidder" shall mean each and all such persons, and the undertakings, covenants and obligations of such joint Bidders in the Bid and the Contract, when awarded, shall be both joint and several.

B10. PRICES

- B10.1 The Bidder shall state a price in Canadian funds for each item of the Work identified on Form B: Prices.
- B10.1.1 Prices stated on Form B: Prices shall not include any costs which may be incurred by the Contractor with respect to any applicable funding agreement obligations as outlined in C24. Any such costs shall be determined in accordance with C24.
- B10.2 The quantities listed on Form B: Prices are to be considered approximate only. The City will use said quantities for the purpose of comparing Bids.
- B10.3 The quantities for which payment will be made to the Contractor are to be determined by the Work actually performed and completed by the Contractor, to be measured as specified in the applicable Specifications.
- B10.4 Payments to Non-Resident Contractors are subject to Non-Resident Withholding Tax pursuant to the Income Tax Act (Canada).
- B10.5 The Bidder shall enter the Total Bid Price from Form B: Prices into the Total Bid Price field in MERX.
- B10.5.1 Bidders are advised that the calculation indicated in B17.4 prevail over the Total Bid Price entered in MERX.

B11. DISCLOSURE

- B11.1 Various Persons provided information or services with respect to this Work. In the City's opinion, this relationship or association does not create a conflict of interest because of this full disclosure. Where applicable, additional material available as a result of contact with these Persons is listed below.
- B11.2 The Persons are:
- (a) N/A

B12. CONFLICT OF INTEREST AND GOOD FAITH

- B12.1 Further to C3.3, Bidders, by responding to this Tender, declare that no Conflict of Interest currently exists, or is reasonably expected to exist in the future.

- B12.2 Conflict of Interest means any situation or circumstance where a Bidder or employee of the Bidder proposed for the Work has:
- (a) other commitments;
 - (b) relationships;
 - (c) financial interests; or
 - (d) involvement in ongoing litigation;
- that could or would be seen to:
- (i) exercise an improper influence over the objective, unbiased and impartial exercise of the independent judgment of the City with respect to the evaluation of Bids or award of the Contract; or
 - (ii) compromise, impair or be incompatible with the effective performance of a Bidder's obligations under the Contract.
- (e) has contractual or other obligations to the City that could or would be seen to have been compromised or impaired as a result of their participation in the Tender process or the Work; or
 - (f) has knowledge of confidential information (other than confidential information disclosed by the City in the normal course of the Tender process) of strategic and/or material relevance to the Tender process or to the Work that is not available to other bidders and that could or would be seen to give that Bidder an unfair competitive advantage.
- B12.3 In connection with their Bid, each entity identified in B12.2 shall:
- (a) avoid any perceived, potential or actual Conflict of Interest in relation to the procurement process and the Work;
 - (b) upon discovering any perceived, potential or actual Conflict of Interest at any time during the Tender process, promptly disclose a detailed description of the Conflict of Interest to the City in a written statement to the Contract Administrator; and
 - (c) provide the City with the proposed means to avoid or mitigate, to the greatest extent practicable, any perceived, potential or actual Conflict of Interest and shall submit any additional information to the City that the City considers necessary to properly assess the perceived, potential or actual Conflict of Interest.
- B12.4 Without limiting B12.3, the City may, in their sole discretion, waive any and all perceived, potential or actual Conflicts of Interest. The City's waiver may be based upon such terms and conditions as the City, in their sole discretion, requires to satisfy itself that the Conflict of Interest has been appropriately avoided or mitigated, including requiring the Bidder to put into place such policies, procedures, measures and other safeguards as may be required by and be acceptable to the City, in their sole discretion, to avoid or mitigate the impact of such Conflict of Interest.
- B12.5 Without limiting B12.3, and in addition to all contractual or other rights or rights at law or in equity or legislation that may be available to the City, the City may, in their sole discretion:
- (a) disqualify a Bidder that fails to disclose a perceived, potential or actual Conflict of Interest of the Bidder or any of their employees proposed for the Work;
 - (b) require the removal or replacement of any employees proposed for the Work that has a perceived, actual or potential Conflict of Interest that the City, in their sole discretion, determines cannot be avoided or mitigated;
 - (c) disqualify a Bidder or employees proposed for the Work that fails to comply with any requirements prescribed by the City pursuant to B12.4 to avoid or mitigate a Conflict of Interest; and
 - (d) disqualify a Bidder if the Bidder, or one of their employees proposed for the Work, has a perceived, potential or actual Conflict of Interest that, in the City's sole discretion, cannot be avoided or mitigated, or otherwise resolved.

B12.6 The final determination of whether a perceived, potential or actual Conflict of Interest exists shall be made by the City, in their sole discretion.

B13. QUALIFICATION

B13.1 The Bidder shall:

- (a) undertake to be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba; and
- (b) be financially capable of carrying out the terms of the Contract; and
- (c) have all the necessary experience, capital, organization, and equipment to perform the Work in strict accordance with the terms and provisions of the Contract.

B13.2 The Bidder and any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:

- (a) be responsible and not be suspended, debarred or in default of any obligations to the City. A list of suspended or debarred individuals and companies is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Purchasing Division website at <https://www.winnipeg.ca/matmgt/Templates/files/debar.pdf>

B13.3 The Bidder and/or any proposed Subcontractor (for the portion of the Work proposed to be subcontracted to them) shall:

- (a) have successfully carried out work similar in nature, scope and value to the Work; and
- (b) be fully capable of performing the Work required to be in strict accordance with the terms and provisions of the Contract;
- (c) have a written workplace safety and health program if required pursuant to The Workplace Safety and Health Act (Manitoba); and
- (d) have completed the Accessible Customer Service online training required by the Accessibility for Manitobans Act (AMA) (see B13.5 and C6.19).

B13.4 Further to B13.3(c), the Bidder shall, within five (5) Business Days of a request by the Contract Administrator, provide proof satisfactory to the Contract Administrator that the Bidder/Subcontractor has a workplace safety and health program meeting the requirements of The Workplace Safety and Health Act (Manitoba), by providing:

- (a) Written confirmation of a safety and health certification meeting SAFE Work Manitoba's SAFE Work Certified Standard (e.g., COR™ and SECOR™) or
 - (i) a copy of their valid Manitoba COR certificate and Letter of Good Standing (or Manitoba equivalency) as issued under the Certificate of Recognition (COR) Program administered by the Construction Safety Association of Manitoba or by the Manitoba Heavy Construction Association's WORKSAFELY™ COR™ Program; or
 - (ii) a copy of their valid Manitoba SECOR™ certificate and Letter of Good Standing (or Manitoba equivalency) as issued under the Small Employer Certificate of Recognition Program (SECOR™) administered by the Construction Safety Association of Manitoba or by the Manitoba Heavy Construction Association's WORKSAFELY™ COR™ Program; or
- (b) a report or letter to that effect from an independent reviewer acceptable to the City. A list of acceptable reviewers and the review template are available at <http://www.winnipeg.ca/matmgt/Safety/default.stm>.

B13.5 Further to B13.3(d), the Bidder acknowledges that they and all Subcontractors have obtained training required by the Accessibility for Manitobans Act (AMA) available at <https://accessibilityymb.ca/resources-events-and-training/online-training.html> for anyone that may have any interaction with the public on behalf of the City of Winnipeg.

B13.6 The Bidder shall submit, within three (3) Business Days of a request by the Contract Administrator, proof satisfactory to the Contract Administrator of the qualifications of the Bidder and of any proposed Subcontractor.

B13.7 The Bidder shall provide, on the request of the Contract Administrator, full access to any of the Bidder's equipment and facilities to confirm, to the Contract Administrator's satisfaction, that the Bidder's equipment and facilities are adequate to perform the Work.

B14. OPENING OF BIDS AND RELEASE OF INFORMATION

B14.1 Bids will not be opened publicly.

B14.2 Following the submission deadline, the names of the Bidders and their Total Bid Prices (unevaluated, and pending review and verification of conformance with requirements) will be available on the MERX website at www.merx.com.

B14.3 After award of Contract, the name(s) of the successful Bidder(s) and their Contract amount(s) will be available on the MERX website at www.merx.com.

B14.4 The Bidder is advised that any information contained in any Bid may be released if required by The Freedom of Information and Protection of Privacy Act (Manitoba), by other authorities having jurisdiction, or by law or by City policy or procedures (which may include access by members of City Council).

B14.4.1 To the extent permitted, the City shall treat as confidential information, those aspects of a Bid Submission identified by the Bidder as such in accordance with and by reference to Part 2, Section 17 or Section 18 or Section 26 of The Freedom of Information and Protection of Privacy Act (Manitoba), as amended.

B15. IRREVOCABLE BID

B15.1 The Bid(s) submitted by the Bidder shall be irrevocable for the time period specified in Paragraph 11 of Form A: Bid/Proposal.

B15.2 The acceptance by the City of any Bid shall not release the Bids of the next two lowest evaluated responsive Bidders and these Bidders shall be bound by their Bids on such Work for the time period specified in Paragraph 11 of Form A: Bid/Proposal.

B16. WITHDRAWAL OF BIDS

B16.1 A Bidder may withdraw their Bid without penalty prior to the Submission Deadline.

B17. EVALUATION OF BIDS

B17.1 Award of the Contract shall be based on the following bid evaluation criteria:

- (a) compliance by the Bidder with the requirements of the Tender or acceptable deviation therefrom (pass/fail);
- (b) qualifications of the Bidder and the Subcontractors, if any, pursuant to B13 (pass/fail);
- (c) Total Bid Price; and
- (d) economic analysis of any approved alternative pursuant to B7.

B17.2 Further to B17.1(a), the Award Authority may reject a Bid as being non-responsive if the Bid is incomplete, obscure or conditional, or contains additions, deletions, alterations or other irregularities. The Award Authority may reject all or any part of any Bid, or waive technical requirements or minor informalities or irregularities, if the interests of the City so require.

- B17.3 Further to B17.1(b), the Award Authority shall reject any Bid submitted by a Bidder who does not demonstrate, in their Bid or in other information required to be submitted, that they are qualified.
- B17.4 Further to B17.1(c), the Total Bid Price shall be the sum of the quantities multiplied by the unit prices for each item shown on Form B: Prices.
- B17.4.1 Further to B17.1(a), in the event that a unit price is not provided on Form B: Prices, the City may determine the unit price by dividing the Amount (extended price) by the approximate quantity, for the purposes of evaluation and payment.
- B17.4.2 Where MRST is shown on Form B as a separate line item, if that Line item is not completed, the MRST shall be considered to be included in the Total Bid Price.
- B17.4.3 Bidders are advised that the calculation indicated in B17.4 will prevail over the Total Bid Price entered in MERX.

B18. AWARD OF CONTRACT

- B18.1 The City will give notice of the award of the Contract or will give notice that no award will be made.
- B18.2 The City will have no obligation to award a Contract to a Bidder, even though one or all of the Bidders are determined to be qualified, and the Bids are determined to be responsive.
- B18.2.1 Without limiting the generality of B18.2, the City will have no obligation to award a Contract where:
- (a) the prices exceed the available City funds for the Work;
 - (b) the prices are materially in excess of the prices received for similar work in the past;
 - (c) the prices are materially in excess of the City's cost to perform the Work, or a significant portion thereof, with their own forces;
 - (d) only one Bid is received; or
 - (e) in the judgment of the Award Authority, the interests of the City would best be served by not awarding a Contract.
- B18.3 If funding for the Work is provided to the City of Winnipeg by the Government of Manitoba and/or the Government of Canada, Bidders are advised that the terms of C24 shall immediately take effect upon confirmation of such funding, regardless of when funding is confirmed.
- B18.4 Where an award of Contract is made by the City, the award shall be made to the qualified Bidder submitting the lowest evaluated responsive Bid, in accordance with B17.
- B18.5 Further to Paragraph 7 of Form A: Bid/Proposal and C4, the City may issue a purchase order to the successful Bidder in lieu of the execution of a Contract.
- B18.5.1 The Contract Documents, as defined in C1.1(p), in their entirety shall be deemed to be incorporated in and to form a part of the purchase order notwithstanding that they are not necessarily attached to or accompany said purchase order.
- B18.6 Following the award of contract, a Bidder will be provided with information related to the evaluation of their Bid upon written request to the Contract Administrator.

PART C - GENERAL CONDITIONS

C0. GENERAL CONDITIONS

- C0.1 The *General Conditions for Construction* (Revision 2025-11-01) are applicable to the Work of the Contract.
- C0.1.1 The *General Conditions for Construction* are available on the Information Connection page at The City of Winnipeg, Corporate Finance, Purchasing Division website at http://www.winnipeg.ca/matmgt/gen_cond.stm
- C0.2 A reference in the Tender to a section, clause or subclause with the prefix “**C**” designates a section, clause or subclause in the *General Conditions for Construction*.

PART D - SUPPLEMENTAL CONDITIONS

GENERAL

D1. GENERAL CONDITIONS

D1.1 In addition to the *General Conditions for Construction*, these Supplemental Conditions are applicable to the Work of the Contract.

D2. SCOPE OF WORK

D2.1 The major components of the Work are as follows:

- (a) Rough grading;
- (b) Supply and install asphalt pathways and pads;
- (c) Supply and install topcoat of asphalt on existing granular path;
- (d) Supply and install topsoil and sod;
- (e) Supply and install site furniture;
- (f) Secure Development Permit exemptions;
- (g) Secure all permits related to the shade shelter installation; and
- (h) Supply and install shade shelters.

D3. SITE INVESTIGATION DUE DILIGENCE AND RISK

D3.1 Notwithstanding C3.1, the Contractor acknowledges that the site investigation reports and other site information included in this Tender have been provided to it and may be relied upon by the Contractor to the extent that the Contractor uses Good Industry Practice in interpreting such report(s) and site information and carries out the Work in accordance with Good Industry Practice based upon such report(s) and the information contained in them and such other site information. In the event that a site condition related to:

- (a) the location of any utility which can be determined from the records or other information available at the offices of any public authority or person, including a municipal corporation and any board or commission thereof, having jurisdiction or control over the utility;
- (b) the Site conditions, including but not limited to subsurface hazardous materials or other concealed physical conditions;
- (c) the location, nature, quality or quantity of the materials to be removed or to be employed in the performance of the Work;
- (d) the nature, quality or quantity of the Plant needed to perform the Work;
- (e) all matters concerning access to the Site, power supplies, location of existing services, utilities or materials necessary for the completion of the Work; and
- (f) all other matters which could in any way affect the performance of the Work;

that could not have been “properly inferable”, “readily apparent” and readily discoverable” using Good Industry Practice by the Contractor, results in additional Work which is a direct result of this newly discovered site condition, such additional Work will be considered by the City under Changes in Work.

D4. DEFINITIONS

D4.1 When used in this Tender:

- (a) “**CW**” means current City of Winnipeg Standard Construction Specification;
- (b) “**SCD**” means current City of Winnipeg Parks Planning Standard Construction Detail;

(c) “SD” means means current City of Winnipeg Standard Construction Detail.

D5. CONTRACT ADMINISTRATOR

D5.1 The Contract Administrator is:
Tayler Bishop
Landscape Architect
Telephone No. 204-451-4608
Email Address tbishop@winnipeg.ca

D5.2 At the pre-construction meeting, the Contract Administrator will identify additional personnel representing the Contract Administrator and their respective roles and responsibilities for the Work.

D6. CONTRACTOR'S SUPERVISOR

D6.1 At the pre-construction meeting, the Contractor shall identify their designated supervisor and any additional personnel representing the Contractor and their respective roles and responsibilities for the Work.

SUBMISSIONS

D7. AUTHORITY TO CARRY ON BUSINESS

D7.1 The Contractor shall be in good standing under The Corporations Act (Manitoba), or properly registered under The Business Names Registration Act (Manitoba), or otherwise properly registered, licensed or permitted by law to carry on business in Manitoba, or if the Contractor does not carry on business in Manitoba, in the jurisdiction where the Contractor does carry on business, throughout the term of the Contract, and shall provide the Contract Administrator with evidence thereof upon request.

D8. SAFE WORK PLAN

D8.1 The Contractor shall provide the Contract Administrator with a Safe Work Plan at least five (5) Business Days prior to the commencement of any Work on the Site.

D8.2 The Safe Work Plan should be prepared and submitted in the format shown in the City's template which is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Purchasing Division website at <http://www.winnipeg.ca/matmgt/Safety/default.stm>

D8.3 Notwithstanding B13.4 at any time during the term of the Contract, the City may, at their sole discretion and acting reasonably, require an updated COR Certificate or Annual Letter of good Standing. A Contractor, who fails to provide a satisfactory COR Certificate or Annual Letter of good Standing, will not be permitted to continue to perform any Work.

D9. INSURANCE

D9.1 The Contractor shall provide and maintain the insurance coverage:

- (a) commercial general liability insurance, in the amount of at least two million dollars (\$2,000,000.00) inclusive, with The City of Winnipeg added as an additional insured, with a cross-liability clause, contractual liability, unlicensed motor vehicle liability (contractor's equipment), non-owned automobile liability and products and completed operations endorsement, to remain in place at all times during the performance of the Work and throughout the Warranty period;
- (b) if applicable, Automobile Liability Insurance covering all motor vehicles, owned and operated and used or to be used by the Contractor directly or indirectly in the performance

of the Work. The Limit of Liability shall not be less than \$2,000,000 inclusive for loss or damage including personal injuries and death resulting from any one accident or occurrence;

- (c) all risks installation floater, carrying adequate limits to cover all machinery, equipment, supplies and/or materials intended to enter into and form part of any installation; and
- (d) all risks course of construction insurance in the amount of one hundred percent (100%) of the total Contract Price, written in the name of the Contractor and The City of Winnipeg, at all times during the performance of the Work and until the date of Total Performance.

D9.2 Deductibles shall be borne by the Contractor.

D9.3 All policies shall be taken out with insurers licensed to carry on business in the Province of Manitoba.

D9.4 The Contractor shall provide:

- (a) The certificate of insurance, in a form satisfactory to the Supervisor of Insurance, to:

The City of Winnipeg
Risk Management
Insurance Section
185 King Street, 3rd Floor
Winnipeg, MB R3B 1J1

- (b) The Contract Administrator with a copy of the certificate of insurance.

At least two (2) Business Days of notification of the award of the Contract and prior to the commencement of any Work on the Site.

D9.5 The Contractor shall not cancel, materially alter, or cause each policy to lapse without providing at least thirty (30) Calendar Days prior written notice to the Supervisor of Insurance.

D10. CONTRACT SECURITY

D10.1 If the Contract Price exceeds twenty-five thousand dollars (\$25,000.00), the Contractor shall provide and maintain contract security until the expiration of the warranty period in the form of:

- (a) a performance bond of a company registered to conduct the business of a surety in Manitoba, in the amount of fifty percent (50%) of the Contract Price; and
- (b) labour and material payment bond of a company registered to conduct the business of a surety in Manitoba, in an amount equal to fifty percent (50%) of the Contract Price.
- (c) an irrevocable standby letter of credit issued by a bank or other financial institution registered to conduct business in Manitoba and drawn on a branch located in Winnipeg, in the amount of fifty percent (50%) of the Contract Price; or
- (d) a certified cheque or draft payable to "The City of Winnipeg", drawn on a bank or other financial institution registered to conduct business in Manitoba, in the amount of fifty percent (50%) of the Contract Price.

D10.1.1 Bonds are available at:

- (a) Performance Bond <https://www.winnipeg.ca/media/4928/>
 - i. Performance Bond – Schedule A - Form of Notice
<https://www.winnipeg.ca/media/4831/>
 - ii. Performance Bond – Schedule B – Surety's Acknowledgement
<https://www.winnipeg.ca/media/4832/>
 - iii. Performance Bond – Schedule C – Surety's Position
<https://www.winnipeg.ca/media/4833/>

- (b) Labour & Material Payment Bond <https://www.winnipeg.ca/media/4930/>
 - i. L&M Bond – Schedule A – Notice of Claim
<https://www.winnipeg.ca/media/4834/>
 - ii. L&M Bond – Schedule B – Acknowledgement of a Notice
<https://www.winnipeg.ca/media/4835/>
 - iii. L&M Bond – Schedule C – Surety's Position
<https://www.winnipeg.ca/media/4836/>
- (c) Irrevocable Standby Letter of Credit <https://www.winnipeg.ca/media/4931/>

D10.1.2 Where the contract security is a performance bond, it may be submitted in hard copy or digital format. If submitted in digital format the contract security must meet the following criteria:

- (a) the version submitted by the Contractor must have valid digital signatures and seals.
- (b) the version submitted by the Contractor must be verifiable by the City with respect to the totality and wholeness of the bond form, including: the content; all digital signatures and digital seals; with the surety company, or an approved verification service provider of the surety company.
- (c) the version submitted must be viewable, printable and storable in standard electronic file formats compatible with the City, and in a single file. Allowable formats include pdf.
- (d) the verification may be conducted by the City immediately or at any time during the life of the bond and at the discretion of the City with no requirement for passwords or fees.
- (e) the results of the verification must provide a clear, immediate and printable indication of pass or fail regarding D10.1.2(b).

D10.1.3 Digital bonds failing the verification process will not be considered to be valid and may be determined to be an event of default in accordance with C18.1. If a digital bond fails the verification process, the Contractor may provide a replacement bond (in hard copy or digital format) within seven (7) Calendar Days of the City's request or within such greater period of time as the City in their discretion, exercised reasonably, allows.

D10.1.4 Digital bonds passing the verification process will be treated as original and authentic.

D10.1.5 Where the contract security is in the form of a certified cheque or draft, it will be deposited by the City. The City will not pay any interest on certified cheques or drafts furnished as contract security.

D10.2 The Contractor shall provide the Contract Administrator identified in D5 with the required contract security within seven (7) Calendar Days of notification of the award of the Contract by way of Purchase Order or an award letter and prior to the commencement of any Work on the Site.

D10.3 Where the Contract Security is provided in accordance with D10.1(a) and D10.1(b), the Contractor shall, as soon as practicable after entering into a contract with a Subcontractor:

- (a) give the Subcontractor written notice of the existence of the labour and material payment bond in D10.1(b); and
- (b) post a notice of the bond and/or a copy of that bond in a conspicuous location at the Site of the Work.

D11. SUBCONTRACTOR LIST

D11.1 The Contractor shall provide the Contract Administrator with a complete list of the Subcontractors whom the Contractor proposes to engage (Form J: Subcontractor List) at least two (2) Business Days prior to the commencement of any Work on the Site.

D12. DETAILED WORK SCHEDULE

D12.1 The Contractor shall provide the Contract Administrator with a detailed work schedule at least two (2) Business Days prior to the commencement of any Work on the Site but in no event later than the date specified in C4.1 for the return of the executed Contract Documents, if applicable.

D12.2 The detailed work schedules shall consist of the following:

- (a) Final drawing submissions for the shade shelter;
- (b) Development Permit Exemption;
- (c) Permitting for shade shelter structures;
- (d) Ordering of shade shelter structures;
- (e) Tree removal (Gateway Community Centre);
- (f) Rough grading (Olympic Park);
- (g) Layout of shelter foundations;
- (h) Installation of shelter foundations;
- (i) Supply and install shade shelters;
- (j) Supply and install asphalt pathways and pads;
- (k) Supply and install of site furniture;
- (l) Supply and install topsoil and sod; and
- (m) Expected completion;

all acceptable to the Contract Administrator.

D12.2.1 Schedule shall conform to stated dates in D14.5.

D12.3 Other milestone dates appropriate to this Project should also be included to make the Contract Administrator aware of.

D13. PARK ACCESS RESTRICTIONS

D13.1 The Contractor shall ensure that the construction site is secured and that the public does not gain access to the work areas using adequate and applicable signage, fencing and barricades to the satisfaction of the Contract Administrator.

D13.2 At a minimum, the Contractor shall review the site conditions on a daily basis to ensure that all features related to Park Access Restrictions are in place. The site review is intended to correct deficiencies as a result of unforeseen events such as wind, traffic, or the general public. Deficiencies that are direct result of the Contractors actions must be corrected immediately.

D13.3 Upon request from the Contract Administrator, the Contractor shall provide records demonstrating that the site has been maintained as per D13.1.

D13.4 Park access to and securement of the Site as required by the Contractor shall be provided and maintained by the Contractor at his/her own expense and approved by the Contract Administrator.

SCHEDULE OF WORK

D14. COMMENCEMENT

D14.1 The Contractor shall not commence any Work until they are in receipt of a Purchase Order from the Award Authority authorizing the commencement of the Work.

D14.2 The Contractor shall not commence any Work on the Site until:

- (a) the Contract Administrator has confirmed receipt and approval of:
 - (i) evidence of authority to carry on business specified in D7;
 - (ii) evidence of the workers compensation coverage specified in C6.17;
 - (iii) the Safe Work Plan specified in D8;
 - (iv) evidence of the insurance specified in D9;
 - (v) the contract security specified in D9;
 - (vi) the Subcontractor list specified in D11;
 - (vii) the detailed work schedule specified in D12;
 - (viii) the direct deposit application form specified in C12.20.

- D14.3 The Contractor has attended a pre-construction meeting with the Contract Administrator, or the Contract Administrator has waived the requirement for a pre-construction meeting.
- D14.4 After Contract award and before Work commences on Site, Contractor must provide all necessary permits and stamped structural engineer drawings to Contract Administrator as E16.2.2.
- D14.5 The Contractor shall not commence the Work on the Site before May 15, 2026 unless otherwise agreed upon with the Contract Administrator.
- D14.5.1 The Contractor shall not commence the Work at Olympic Park before May 15, 2026 unless otherwise agreed upon with the Contract Administrator.
- D14.5.2 The Contractor shall not commence the Work at Gateway Community Centre before September 14, 2026 unless otherwise agreed upon with the Contract Administrator.

D15. SUBSTANTIAL PERFORMANCE

- D15.1 The Contractor shall achieve Substantial Performance within twenty (20) consecutive Working Days of the commencement of the Work as specified in D14.
- D15.2 When the Contractor considers the Work to be substantially performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Substantial Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be reinspected.
- D15.3 The date on which the Work has been certified by the Contract Administrator as being substantially performed to the requirements of the Contract through the issue of a certificate of Substantial Performance is the date on which Substantial Performance has been achieved.

D16. TOTAL PERFORMANCE

- D16.1 The Contractor shall achieve Total Performance within twenty-five (25) consecutive Working Days of the commencement of the Work as specified in D14.
- D16.2 When the Contractor or the Contract Administrator considers the Work to be totally performed, the Contractor shall arrange, attend and assist in the inspection of the Work with the Contract Administrator for purposes of verifying Total Performance. Any defects or deficiencies in the Work noted during that inspection shall be remedied by the Contractor at the earliest possible instance and the Contract Administrator notified so that the Work can be reinspected.
- D16.3 The date on which the Work has been certified by the Contract Administrator as being totally performed to the requirements of the Contract through the issue of a certificate of Total Performance is the date on which Total Performance has been achieved.

D17. LIQUIDATED DAMAGES

- D17.1 If the Contractor fails to achieve Substantial Performance in accordance with the Contract by the day fixed herein for Substantial Performance, the Contractor shall pay the City five hundred

dollars (\$500) per Working Day for each and every Working Day following the day fixed herein for Substantial Performance during which such failure continues.

D17.2 The amount specified for liquidated damages in D17.1 is based on a genuine pre-estimate of the City's damages in the event that the Contractor does not achieve Substantial Performance by the day fixed herein for same.

D17.3 The City may reduce any payment to the Contractor by the amount of any liquidated damages assessed.

D18. SCHEDULED MAINTENANCE

D18.1 The Contractor shall perform the following scheduled maintenance in the manner and within the time periods required by the Specifications:

(a) Soil and sod as specified in E20.

D18.2 Determination of Substantial Performance and Total Performance shall be exclusive of scheduled maintenance identified herein. All scheduled maintenance shall be completed prior to the expiration of the warranty period. Where the scheduled maintenance cannot be completed during the warranty period, the warranty period shall be extended for such period of time as it takes the Contractor to complete the scheduled maintenance.

CONTROL OF WORK

D19. JOB MEETINGS

D19.1 **Regular job meetings will be held at the Site.** These meetings shall be attended by a minimum of one representative of the Contract Administrator, one representative of the City and one representative of the Contractor. Each representative shall be a responsible person capable of expressing the position of the Contract Administrator, the City and the Contractor respectively on any matter discussed at the meeting including the Work schedule and the need to make any revisions to the Work schedule. The progress of the Work will be reviewed at each of these meetings.

D19.2 The Contract Administrator reserves the right to cancel any job meeting or call additional job meetings whenever they deem it necessary.

D20. PRIME CONTRACTOR – THE WORKPLACE SAFETY AND HEALTH ACT (MANITOBA)

D20.1 Further to C6.27, the Contractor shall be the Prime Contractor and shall serve as, and have the duties of the Prime Contractor in accordance with The Workplace Safety and Health Act (Manitoba).

D21. THE WORKPLACE SAFETY AND HEALTH ACT (MANITOBA) – QUALIFICATIONS

D21.1 Further to B13.4, the Contractor/Subcontractor must, throughout the term of the Contract, have a Workplace Safety and Health Program meeting the requirements of The Workplace Safety and Health Act (Manitoba). At any time during the term of the Contract, the City may, at their sole discretion and acting reasonably, require updated proof of compliance, as set out in B13.4.

WARRANTY

D22. WARRANTY

D22.1 Warranty is as stated in C13.

INDEMNITY

D23. INDEMNITY

D23.1 Indemnity shall be as stated in C17.

PART E - SPECIFICATIONS

GENERAL

E1. APPLICABLE SPECIFICATIONS AND DRAWINGS

- E1.1 These Specifications shall apply to the Work.
- E1.2 *The City of Winnipeg Standard Construction Specifications* in their entirety, whether or not specifically listed on Form B: Prices, shall apply to the Work.
- E1.2.1 *The City of Winnipeg Standard Construction Specifications* is available on the Information Connection page at The City of Winnipeg, Corporate Finance, Purchasing Division website at <http://www.winnipeg.ca/matmgt/Spec/Default.stm>
- E1.2.2 The version in effect three (3) Business Days before the Submission Deadline shall apply.
- E1.2.3 Further to C2.4(d), Specifications included in the Tender shall govern over *The City of Winnipeg Standard Construction Specifications*.
- E1.3 Bidders are reminded that requests for approval of substitutes as an approved equal or an approved alternative shall be made in accordance with B7. In every instance where a brand name or design specification is used, the City will also consider approved equals and/or approved alternatives in accordance with B7.
- E1.4 The following are applicable to the Work:

Specification No.	Specification Title
CW-1110	General Instructions
CW-1130	Site Requirements
CW 2160	Concrete Underground Structures and Works
CW-3110	Sub-Grade, Sub-Base and Base Course Construction
CW-3130	Supply & Installation of Geotextile Fabrics
CW-3170	Earthwork and Grading
CW-3410	Asphaltic Concrete Pavement Works
CW-3510	Sodding
CW-3540	Topsoil and Finished Grading for Establishment of Turf Areas

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
G.18-S1	Existing Conditions and Removals
G.18-S2	Materials and Grading Plan
G.18-S3	Layout Plan
O.19-D1	Existing Conditions and Removals
O.19-D2	Materials and Grading Plan
O.19-D3	Layout Plan
SCD-119	Waste Receptacle Side Opening Metal Slant Type
SCD-122	Tache Style Metal Frame Picnic Table
SCD-122A	Tache Style Accessible Metal Frame Picnic Table
SCD-121E	Tache Bench Composite with Arms Surface Mount
SCD-648	Park Pathway Asphalt
SD-243	Sodding Details

E2. HAZARDOUS MATERIALS

- E2.1 If asbestos or other hazardous materials are encountered during the Work of the Contract, the Contractor shall stop all work and notify the Contract Administrator immediately. Removal of hazardous materials shall be dealt with by the City and the Contractor shall await further instruction by the Contract Administrator.

E3. EXISTING SERVICES AND UTILITIES

- E3.1 No responsibility will be assumed by the City for correctness or completeness of the Drawings, when provided, with respect to the existing utilities, pipes or other objects either underground or on the surface; the City shall not be liable for the incorrectness and inadequacy thereof. It shall be the responsibility of the Contractor to determine the location of all such utilities, pipes and other objects and to make good any damage done to them.

E4. ACCESS TO SITE

- E4.1 Access to the Site as required by the Contractor shall be provided and maintained by the Contractor at his/her own expense and approved by the Contract Administrator.
- E4.2 The Contractor's operations shall be limited to the minimum area necessary for undertaking the Work and he/she shall be responsible for all damage resulting from his/her Work on private property.

E5. PERMITS, NOTICES, LICENSES, CERTIFICATES, LAWS AND RULES

- E5.1 Further to C6.12, the Contractor shall give all necessary notices, obtain all necessary permits and pay all fees in order that the Work may be carried out. The Contractor shall submit all plans required by any inspection authority and obtain approval of same before proceeding with the Work, and pay any cost attached to the inspection of such plans.
- E5.2 The Contractor shall comply with all laws, ordinances, rules and regulations that would relate to the Work.
- E5.3 All notices, consents, approvals, statements, authorizations, documents or other communications to the City shall be submitted to the Contract Administrator.
- E5.4 All Work shall be performed in compliance with the Manitoba Workplace Health and Safety Act.
- E5.5 All Work shall be performed in compliance with the Manitoba Workplace Health and Safety Fall Protection guidelines.
- E5.6 The Contractor and Sub-contractors must be fully aware of all Work involving hazardous materials. All Work must be performed in compliance with the Manitoba Department of Labour Workplace Health and Safety Guidelines and all other applicable codes. The Contractor is responsible for the immediate notification to the Contract Administrator of his/her encountering of suspected hazardous material during their course of Work.

E6. DAMAGE TO EXISTING STRUCTURES, TREES AND PROPERTY

- E6.1 All necessary precautions shall be exercised by the Contractor so as not to remove, disturb, or damage any existing trees, shrubs, sod, pavements, streets, roads, boulevards, poles, hydrants, water pipes, gas pipes, electrical wires, cables, conduits, sewers or other existing facilities and equipment at the Site of the Work. For all damage incurred in the performance of the Work (either directly or indirectly), the Contractor shall either replace and repair such damage, whichever may be deemed necessary in the opinion of, and acceptable to City of Winnipeg Contract Administrator, and the cost of which shall be borne entirely by the Contractor. The Contractor shall also indemnify and save harmless the City from all claims made directly or indirectly against it in respect to any such damage.

- E6.2 The Contractor shall take the following precautionary steps to prevent damage from construction activities to existing park trees within the limits of the construction area:
- (a) The Contractor shall not stockpile materials and soil or park vehicles and equipment within 2 metres of trees.
 - (b) Trees identified to be at risk by the Contract Administrator are to be strapped with 25x100x2400 wood planks, or suitable protection as approved by the Contract Administrator.
 - (c) Excavation shall be performed in a manner that minimizes damage to the existing root systems. Where possible, excavation shall be carried out such that the edge of the excavation shall be a minimum of 1.5 times the diameter (measured in inches), with the outcome read in feet, from the closest edge of the trunk. Where roots must be cut to facilitate excavation, they shall be pruned neatly at the face of excavation.
 - (d) Operation of equipment within the drip line of the trees shall be kept to a minimum required to perform the Work required. Equipment shall not be parked, repaired, refuelled; construction materials shall not be stored, and earth materials shall not be stockpiled within the drip lines of trees. The drip line of a tree shall be considered to be the ground surface directly beneath the tips of its outermost branches. The Contractor shall ensure that the operations do not cause flooding or sediment deposition on areas where trees are located.
- E6.3 All damage to existing trees caused by the Contractor's activities shall be repaired to the requirements and satisfaction of the Contract Administrator and the City Forester or their designate.
- E6.4 No separate measurement or payment will be made for the protection of trees.

E7. PEDESTRIAN SAFETY AND TRAFFIC MANAGEMENT

- E7.1 Further to CW 1130, the Contractor shall take such measures as are necessary to ensure safe and convenient pedestrian ingress and egress is maintained to private properties while they are working near them. Any damage caused by the negligence of the Contractor or their Sub-Contractors to the adjacent Works or properties, shall be promptly repaired by him at their own expense, to the satisfaction of the Contract Administrator.
- E7.2 Ambulance/ Emergency vehicle access must be maintained at all times.

E8. PROTECTION OF THE SURVEY INFRASTRUCTURE

- E8.1 Notwithstanding clause 4 "Persons and municipalities to protect Outline Monuments"; under [The Surveys Act](#), of Manitoba, the Contractor shall be responsible to protect the Survey Infrastructure from damage as a result of the Work.
- E8.2 Further to C6.26 (g), at least 72 hours prior to the commencement of the On-Site Work the Contractor shall contact the City of Winnipeg, Geomatics Services Branch at 204-918-1360 (8:00 am to 4:00 pm Monday to Friday, excluding holidays) to obtain underground clearance. Geomatics Services will locate and mark all known outline survey monuments and geodetic control monuments and confirm the physical condition of those monuments upon completion of construction, at no cost to the Contractor.
- E8.3 Where a survey post, bar or control monument lies in the line of the proposed Work and must be disturbed, the Contractor shall provide the Contract Administrator with 48 hours' notice to permit referencing for future replacement, at no cost to the Contractor. Failure to provide the specified notice shall result in the Contractor paying for all costs associated with replacing or relocating the disturbed outline survey monuments and geodetic control monuments. Survey monuments and geodetic control monuments at or adjacent to the Site, not in the line of the proposed construction that are damaged or disturbed by the Contractor shall be replaced or relocated by the City or their agent and all associated costs shall be paid for by the Contractor.

- E8.4 An approximate estimate of the cost to restore a legal survey monument is \$1,000 per bar and \$3,000 per control monument. Contractors shall ensure their landscaping and other subcontractors are aware of this clearance procedure and the potential restoration costs. Where possible, amounts owed to the City in accordance with the above will be deducted from payments to be made by the City to the Contractor.

E9. SITE ENCLOSURES

- E9.1 Temporary Site enclosures shall be erected and maintained as required for the duration of the construction period.
- E9.2 Site enclosures shall be considered incidental to the Contract Work.
- E9.3 Site enclosures shall be sturdy, steel construction fencing.
(a) Snow fencing will not be accepted.
- E9.4 Contractor to securely lock construction fencing at the end of each Working Day.
- E9.5 Contractor shall install minimum one (1) construction safety sign per enclosure.

E10. SITE RESTORATION

- E10.1 Total Performance of the Work shall not be attained until the Contractor has cleaned up the Site and has removed all tools, equipment, waste, debris and surplus foundation earth to the satisfaction of the Contract Administrator. Unless otherwise specified, the Contractor shall restore all areas of the Site beyond the established limit of Work, which have been disturbed by the Contractor's operations to as good as or better than the original condition to the satisfaction of the Contract Administrator. The Contractor shall pay all costs associated with this Work.

SITE DEVELOPMENT

E11. STAKES AND MARKS

- E11.1 The Contractor is responsible for the identification and staking of the property lines and the establishment of the layout of all Work. Key grade stakes shall be identified at the pre-construction meeting.
- E11.2 The Contract Administrator shall be advised of the staking of the layout and site grades at least twenty-four (24) hours in advance in order that the layout and site grades may be inspected and adjusted as required prior to construction.
- E11.3 The Contractor is responsible for the establishment and maintenance of the fixed benchmark, layout and grade stakes throughout the construction process.
- E11.4 The Contractor shall determine the meaning and correctness of the stakes and marks before starting the Work. If an error is suspected in the Drawings, Specifications or directions of the Contract Administrator, Work will be discontinued until the error is rectified. No claim will be made due to alleged inaccuracies in the stakes and marks and for delay in the Work to rectify an error.

E12. TREE REMOVAL

- E12.1 General Description
- E12.1.1 This Specification shall cover the removal of existing trees as shown on the drawings.
- E12.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour,

equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

E12.2 Construction methods

E12.2.1 Tree removal

- (a) The Contractor shall remove trees designated for removal to min. 600mm below proposed grade with use of a stump grinder. The Contractor shall load and haul all waste materials from the site and dispose of these materials at dumps located by the Contractor and approved by the Contract Administrator.
- (b) Holes and depressions left by removals are to be filled with clean fill, as per CW 3170, where areas to be sodded with minimum 75mm mm of topsoil layer then sod per E20. Removals shall include removal of any foundation or footings to one metre below proposed grade.

E12.3 Method of Measurement

E12.3.1 Method of Measurement shall be as follows:

- (a) Removals shall be measured on a per unit basis for:
 - i. "Tree Removal" on Form B: Prices.
- (b) No separate measurement shall be made for filling holes and depressions with fill material as this Work is incidental to the Work herein.

E12.4 Basis of Payment

E12.4.1 Basis of Payment shall be as follows:

- (a) Removals will be paid for at the Contract Unit Prices on Form B: Prices. The amount to be paid for shall be the total number of units, measured as specified herein, which price shall be for full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.
- (b) No additional payment shall be made for filling holes and depressions with fill material as this Work is incidental to the Work herein.

E13. REMOVALS

E13.1 This Specification shall cover the removal of bollards (2), as indicated on the Drawings and identified by the Contract Administrator.

E13.2 The Work to be done by the Contractor under this specification shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies and all other things necessary for and incidental to satisfactory performance and completion of all Work as shown on the drawings as herein specified.

E13.3 Construction Methods

E13.3.1 Remove and reinstall existing bollards as identified by the Contract Administrator.

E13.3.2 At the discretion of the Contract Administrator, some or all of the removed items may be salvaged by the City of Winnipeg.

E13.3.3 Voids from chain link fencing posts shall be filled and sufficiently compacted with clean fill.

E13.3.4 The Contractor shall load and haul all waste materials from the Site and dispose of these materials at dumps located by the Contractor and approved by the Contract Administrator.

E13.4 Method of Measurement and Basis of Payment

E13.4.1 Method of Measurement shall be measured on as follows:

- (a) Removals shall be measured on a lump sum basis for:

- i. "Remove and Reinstall Two Bollards" on Form B: Prices.
- (b) No separate measurement shall be made for filling footing holes with fill material as this work is incidental herein.

E13.4.2 Basis of Payment shall be as follows:

- (a) Removals will be paid for at the Contract Lump Sum Prices. The amount to be paid for shall be the total number of a Lump Sum, as indicated on Form B: Prices. The price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.
- (b) No separate payment shall be made for filling footing holes with fill material as this work is incidental herein.

E14. EXCAVATION AND GRADING

E14.1.1 Grading

- (a) Site grading shall be as per the Drawings and are to match existing grades.
- (b) The design grade shall be considered to be straight grade between finished design elevations shown. Changes in grade where it meets existing sod shall be gently contoured to allow for ease of grass mowing operations.
- (c) Contractor to ensure site grading does not create tripping hazards and no areas of standing water remain.
- (d) If necessary, the Contractor shall import clean fill to achieve grades as per the Drawings.
- (e) Backfill shall be placed in a dry, thawed condition and shall be maintained free of moisture or frost.
- (f) In fill areas where the difference between the existing ground elevation and the new finished design elevation is less than 300 mm, the Contractor shall scarify the existing ground to a minimum depth of 50 mm prior to placement of any fill.
- (g) In areas where new grades are greater than 75 mm than existing grades, clean fill shall be used to achieve finished subgrade levels. Clean fill can be used from On-Site grading operations. If additional clean fill is required, it must be hauled in from Off-Site.

E14.1.2 Finish Grading

- (a) Following earthmoving, rough grading and compaction, the Work areas shall be finish graded to provide a maximum deviation of 50 mm in 10 meters from the design grade with no low areas that hold water. The finished surface of all disturbed areas shall be dragged and smoothed in such a manner that there are no loose soil particles greater than 50 mm.
- (b) All surplus fill material shall be removed and legally disposed off-site.
- (c) Do not disturb adjacent items designated to remain in place.

E14.2 Method of Measurement and Basis of Payment

E14.2.1 Method of Measurement shall be as follows:

- (a) Excavation and grading will be measured at the Contract Unit Price per unit for:
 - i. "Rough Grading" on Form B: Prices.
- (b) If required by the Contract Administrator, no measurement will be made for retaining services relating to survey of layout and establishing grades as these items are incidental to the Work herein.
- (c) No separate measurement will be made for excavation and grading for the following items as these items are incidental to the Work herein:

- i. Asphalt Pathways and Pad;
- ii. Sod; or
- iii. Import of clean fill to achieve rough grading elevations, and earthwork and site finish grading elevations.

E14.2.2 Basis of Payment shall be as follows:

- (a) Excavation and grading will be paid for at the Contract Unit Price per unit for:
 - i. "Rough Grading".
- (b) If required by the Contract Administrator, no additional payment will be made for retaining services relating to survey of layout and establishing grades as these items are incidental to the Work herein.
- (c) No additional payment will be made for excavation and grading for the following items as these items are incidental to the Work herein:
 - i. Asphalt Pathways and Pad;
 - ii. Sod; or
 - iii. Import of clean fill to achieve rough grading elevations, and earthwork and site finish grading elevations.

E15. ASPHALT PAVEMENT

E15.1 General Description

E15.1.1 This Specification shall cover:

- (a) The supply and installation of **new** asphalt path including all excavation, compaction, geotextile, sub-base and base construction, asphaltic paving, and repair of existing sod to ensure a smooth transition to the pathway.
- (b) Removal.

E15.1.2 This Specification shall supplement CW 3110, CW 3130 CW 3170 and 3410 and shall cover the supply and installation of the asphalt pathway.

E15.1.3 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

E15.1.4 The use of recycled concrete as a base material will not be permitted.

E15.2 General Instructions

E15.2.1 Quality Control

- (a) Testing and Approval of Materials
 - i. Material testing may be required as per this Specification and as direct by the Contract Administrator.
- (b) The Contractor shall not proceed with asphalt installation until test results on the crushed limestone base have been reviewed and approval to proceed is granted by the Contract Administrator.
- (c) The Contract Administrator will conduct a survey of the operation to verify installation of specified layer thickness.
- (d) Non-conformity with the specified test requirements or compacted layer thickness will constitute sufficient grounds for rejection of the Work.

E15.2.2 Submittals

- i. Material samples may be required, at the discretion of the Contract Administrator, for materials supplied under this Specification.

E15.3 Materials

(a) Geotextile Fabric

- (i) The separation/ reinforcement non-woven geotextile fabric shall conform to the Products Approved as listed in City of Winnipeg Specification for Approved Products for Surface Works.

- ◆ https://www.winnipeg.ca/finance/findata/matmgt/std_const_spec/current/Docs/Approved_Products_Surface_Works.pdf

(b) Materials - Limestone Materials Only

- (i) 150 mm layer of 50 mm (2") down crushed limestone.
- (ii) 75 mm layer of 20 mm (3/4") down crushed limestone.
- (iii) Sub-base and Base course shall be Granular C as per current CW 3110, the Drawings, SCD-648 and this specification.
- (iv) Notwithstanding current CW 3110 Section 1.2 Clause 1.2.7, Granular A, Granular B, and recycled aggregates or materials will not be accepted.
- (v) Sub-base and Base Course Material Grading Requirements:

CANADIAN METRIC SIEVE SIZE	Percent of Total Dry Weight Passing Each Sieve		
	6 mm (1.4") Topping Material	20 mm (3/4") Base Course	50 mm (2") Base Course
50 000	--	--	100%
25 000	--	--	--
20 000	--	100%	--
10 000	100%	--	--
5 000	65% - 100%	40% - 70%	25% - 60%
2 500	40% - 75%	25% - 60%	--
1 250	35% - 65%	--	--
630	19% - 36%	--	--
315	14% - 28%	8% - 25%	--
160	12% - 24%	--	--
80	10% - 25%	6% - 17%	4% - 15%

(c) Asphaltic Concrete

- (i) Asphaltic Concrete shall be Type 1A as specified and to a compacted thickness of 75mm (3") as shown on the Drawings.

E15.4 Construction Methods

E15.4.1 Excavation

- (a) This specification shall be done in accordance with E11, CW 3170, CW 3110, and as per SCD-648 as indicated on the Drawings.
- (b) Excavation shall be understood to include all removal of existing insitu material necessary to achieve finished grade and as indicated on the Drawings.
- (c) The Contractor shall survey and stake out the proposed asphalt pathway prior to the start of construction as shown on the construction drawings. Layout shall be checked and confirmed with Contract Administrator prior to construction.
- (d) In locations where existing tree root systems intersect with the pavement area, excavation shall be done carefully so as not to damage or sever any roots of the trees.
- (e) If any pavement exists at the limits of the designated area of removal, these shall be saw cut for the full depth of the pavement prior to the demolition and removal operations. All costs in connection with saw cutting are incidental and shall be included in the unit price bid for excavation.
- (f) All excavated material shall be removed, hauled, and legally disposed of off-site to the satisfaction of the Contract Administrator.

E15.5 Sub-Grade Compaction

- (a) Sub grade compaction shall be done in accordance with CW 3110.
- (b) Sub-grade shall be free of any fibrous organics, softened and disturbed soil. The prepared sub-grade shall be proof rolled with a heavy sheep's foot roller (minimum 25 passes) and inspected by the Contract Administrator to detect for any soft spots prior to the placement of overlying granular fills.

E15.6 Geotextile Fabric

- (a) Separation/ Reinforcement geotextile fabric shall be installed as outlined in Section 3.1 of CW 3110.

E15.7 Crushed Limestone Sub-base and Base Course Material

- (a) Crushed limestone sub-base material shall be supplied and installed in accordance with CW 3110 and shall be placed and compacted as specified to a finished thickness as shown on the Drawings.

E15.8 Asphaltic Pavement

- (a) Asphaltic Pavement for the pathway shall be supplied and installed in accordance with City of Winnipeg Standard Construction Specification CW 3410 "Asphaltic Concrete Pavement Works".

E15.9 Crack Sealing

- (a) As a Warranty requirement, the Contractor shall rout and seal any and all cracks which may appear in the pathway and court approach area during the one-year warranty period. Crack sealing shall conform to the requirements of City of Winnipeg Standard Construction CW 3250.
- (b) No separate payment will be made for this item as it is considered a warranty issue and shall fall under GC.13- Warranty.

E15.10 Quality Control for Hard Surfaced Areas

- (a) Further to Section 10, Quality Control, of CW 3110 and CW 3410, the Contractor shall obtain a qualified independent testing lab to conduct tests on materials to determine the acceptability of the sub-grade, sub-base, base course and asphaltic concrete as placed by the Contractor in accordance with the requirements of this Specification.
- (b) The Contractor shall not proceed with asphalt installation until test results have been reviewed and approval to proceed is granted by the Contract Administrator.
- (c) The Contract Administrator will conduct a survey of the operation to verify installation of specified layer thickness.
- (d) Non-conformity with the specified test requirements or compacted layer thickness will constitute sufficient grounds for rejection of the Work.

E15.11 Method of Measurement and Basis of Payment

E15.11.1 Asphalt pathway works shall be measured on a square metre basis for:

- (a) "Supply and Install Asphalt Paving and Seating Area," and
- (b) "Supply and Install Asphalt Overlay over Existing Granular Path" on Form B: Prices.

E15.11.2 Measurement shall be of the actual area covered by Asphalt. Price shall be payment in full for supplying materials and for performing all operations listed below:

- (a) Excavate in-situ material to accommodate the pavement structure including base and subbase. Disposal of excess material.
- (b) Scraping and removing top layer of granular surface for asphalt overlay in areas indicated in the Drawings.
- (c) Supply and installation of geotextile.

- (d) Supply and placement of crushed limestone subbase course.
- (e) Supply and placement of crushed limestone base course.
- (f) Supply and placement of asphaltic concrete.

E15.11.3 Basis of Payment shall be as follows:

- (a) Asphalt pathway works will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for:
 - i. "Supply and Install Asphalt Paving and Seating Area," and
 - ii. "Supply and Install Asphalt Overlay over Existing Granular Path" on Form B: Prices including excavation and grading, importation of clean clay fill if required, material testing, sub-grade compaction, non-woven geotextile, sub-base course and base course crushed limestone, asphalt pavement as per SCD-648, supplying all labour equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

E16. SHADE STRUCTURE

E16.1 General Description

- (a) This specification shall cover the supply and installation of two (2) shade structures.

E16.2 Shade Structure

- (a) The shade structure shall be either:
 - (i) **Poligon 24' x 24' Carnival Square, Hip Roof Shelter** by Poligon with no ornamentation. Complete with 4 columns & min 7.5' height. Model SQR-24MR
 - ◆ Playgrounds R Us: Matther Lacroix
 - ◆ 250 Transport Rd
 - ◆ Box 7, GRP 582, R.R. #5
 - ◆ Winnipeg, MB
 - ◆ 204-632-7000
 - (ii) **ICON. 24' x 24' Two Tier Clerestory Design Square Hip Roof Shelter** by ICON Shelter Systems Inc. Complete with 4 columns & min 7.5' height. Model sQ24M2C-P4
 - ◆ Shelter to come with base covers for Optional Base Connection: Column Type B, Surface Mount with Covers.
 - ◆ Park N Play Design: Dave Jones
 - ◆ #20, 10 Wrangler Place S.E
 - ◆ Rockey View County, MB T1X 0L7
 - ◆ 204-209-0916
 - (iii) **Coverworx Recreational Architecture Steelworx 24' x 24' Square Shelter with Vented Top** by Coverworxs Recreation Architecture. Complete with 4 columns & min, 7.5' height. Model # SQVT-24SW
 - ◆ Colcat Enterprices: Murray Lord
 - ◆ 631 Jubilee Ave.
 - ◆ Winnipeg, Manitoba, R3L 1P5
 - ◆ 204-979-7972
 - (iv) **Cedar Forest Products 24' x 24' Square 2 Tier Hip Roof Shelter** by Cedar Forest Products. Complete with 4 columns & min. 7.5' height. Model # RHS-2424-2T
 - ◆ Parkworks: Jenny Harry

- ◆ 12824 141 Street NW
- ◆ Edmonton AB, T5L 4N8 780-453-6903 ext 406 or 888-890-6257 ext 406

(v) Or approved substitute as per B7.

E16.2.1 Foundation

- (a) Shade Structure foundation shall be CIP concrete piles, **OR** steel auger screw piles complete with a concrete pile cap OR steel auger screw piles complete with metal pile mounting cap. This specification shall amend and supplement the City of Winnipeg Specification CW3310.
- i. Structural drawings must be supplied and stamped by a professional engineer licensed to practice in the Province of Manitoba.

E16.2.2 Permits

- (a) The Contractor shall be responsible to obtain **all necessary permits AND Development Permit Exemption Declaration** for the supply and installation of the Shade Structure, including a Building Permit, and Occupancy Permit, from the City of Winnipeg. A copy of the Permits shall be given to the Contract Administrator before Work on site occurs.
- i. Development Permit Exemption Form can be found at the following link:
<https://legacy.winnipeg.ca/ppd/documents/permits/exemptions/Declaration-Form-for-Development-Permit-Exemption.pdf>

E16.2.3 Shop Drawings

- (a) Contractor to provide shop drawings of both the structure and the foundation that are stamped by a professional engineer registered in the Province of Manitoba.

E16.2.4 Colours

- (a) Post, frame and roof colours shall be selected from Manufacturer's list of standard colours by the Contract Administrator after award of the contract and prior to ordering.

E16.2.5 Installation

- (a) Structure and foundation to be installed in accordance with Shop Drawings and manufacturer's recommendations.

E16.2.6 Method of Measurement and Basis of Payment

- (a) Shade Structure will be measured on a lump sum basis for:
- i. "Supply and Install 24' x 24' Shade Structure Including Piles and All Permits" on Form B: Prices.
- (b) No separate measurement shall be made for production of engineer stamped drawings as that is incidental to the Work herein.

E16.2.7 Bases of Payment shall be as follows:

- (a) Shade Structure will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

E17. CHAIN LINK FENCING

E17.1 Description

- E17.1.1 The Work to be done by the Contractor under this specification shall include the furnishing of all superintendence, overhead labour, materials, equipment, tools, supplies and all other things necessary for and incidental to the satisfactory performance and completion of all Work as shown on the Drawings and as hereinafter specified, including, but not necessarily confined to the following:

- (a) Removal and reinstallation of existing chain link fencing to allow for construction vehicle access.

E17.1.2 This specification supplements and amends C.W. 3550 - Chain Link Fencing.

E17.2 Materials

E17.2.1 All materials, supplied under this specification shall be of a type approved by the Contract Administrator, and shall be subject to inspection and testing by the Contract Administrator.

E17.2.2 Chain link fencing as specified in CW 3550 and on Drawings.

E17.2.3 All fencing to have knuckled top and bottom fabric.

E17.3 Construction Methods

E17.3.1 As per CW 3550 and the Drawings.

E17.4 Method of Measurement and Basis of Payment

E17.4.1 Method of Measurement shall be as follows:

- (a) Chain link vehicle access gate will be measured on a lump sum basis for the following items:
 - i. "Remove & Reinstall Chain Link Fencing for Construction Vehicle Access" on Form B: Prices.

E17.4.2 Basis of Payment shall be as follows:

- (a) Chain link fencing and gate will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

E18. SITE FURNISHINGS

E18.1 General Description

E18.1.1 This Specification shall cover the **supply and installation** of site furnishings as per the Drawings.

E18.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

E18.2 Materials

E18.2.1 All materials supplied under this specification shall be of a type approved by the Contract Administrator, and subject to inspection and testing by the Contract Administrator.

E18.2.2 All site furnishings shall be as per the Drawings.

E18.2.3 Ordering

- (a) To order City of Winnipeg site furnishings email: pwd-cps-orderdesk@winnipeg.ca

E18.2.4 City of Winnipeg Site Furnishings:

- (a) Tache Style Wheelchair Metal Frame Picnic Table as per **SCD-122A** x 2
 - i. Product Number: per SCD-122 – **Cost: \$1,804.00 plus taxes**
 - ii. Finish:
 - iii. Wood Finish: Latex Paint, Colour: Cedar
 - iv. Metal: Galvanized

- v. **One table to be modified to 8' length, Confirm with order desk before pickup**
- (b) Tache Style Standard Metal Frame Picnic Table x 4
 - i. Product Number: per SCD-122 – **Cost: \$1,768.00 plus taxes**
 - ii. Finish:
 - iii. Wood Finish: Latex Paint, Colour: Cedar
 - iv. Metal: Galvanized
 - v. **One table to be modified to 8' length, Confirm with order desk before pickup**
- (c) Tache Bench Composite **surface mount** with arms per **SCD-121E** x 7
 - i. Product Number: 52501071GLV – **Cost: \$1,501.00 each plus taxes**
 - ii. Finish:
 - iii. Wood Finish: Latex Paint, Colour: Cedar
 - iv. Metal: Galvanized
 - v. Mounting: In-ground
- (d) Waste Receptacle Side Opening Metal Slat Type per SCD-119 x 1
 - i. Product Numbers:
 - ii. Metal Slat Waste Receptacle: 52501063GLV **Cost \$506.00 + Tax**
 - iii. Wire Basket: 52501058GLV – **Cost \$231.00 + Tax**
 - iv. Finish: Galvanized
 - v. Mounting: in-ground

E18.3 Construction Methods

E18.3.1 All Work is to be located and installed in accordance with the Drawings, and associated SCDs and/or Manufacturer's written instructions and specifications, using approved non-rusting, tamper resistant fasteners to ensure solid, durable, finished work suitable for the purpose intended. Fasteners and assembly hardware shall be incidental to the Work.

- (a) All furnishings and fixtures to be installed plumb and true to correct elevations and location, as directed by the Contract Administrator. The Contractor shall confirm proposed locations of all site furnishings with Contract Administrator prior to installation.
- (b) All furnishings and fixtures to be carefully handled so that no parts will be bent, broken or otherwise damaged. Hammering is prohibited.
- (c) Damaged Site Furnishings will not be accepted.

E18.4 Method of Measurement and Basis of Payment

E18.4.1 Method of Measurement shall be as follows:

- (a) Supply and installation of Site Furnishings will be measured at the Contract Unit Price per unit for:
 - i. "Supply and Install Standard Picnic Tables";
 - ii. "Supply and Install Accessible Picnic Table";
 - iii. "Supply and Install Tache Benches"; and
 - iv. "Supply and Install Waste Receptacles" on Form B: Prices.
- (b) Price shall be payment in full for supplying all materials and for performing all operations herein described and all other items incidental to the Work included in this Specification.
- (c) No measurement will be made for concrete pads as this item is incidental to the Work herein.

E18.4.2 Basis of Payment shall be as follows:

- (a) Site Furnishings will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. The price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

E19. CAST-IN-PLACE CONCRETE FOUNDATIONS

E19.1 General Description

E19.1.1 This Specification shall supplement CW 2160 and cover the supply and installation of cast-in-place concrete foundations for Site Furnishings.

- (a) All underground cast-in-place concrete foundations for Site Furnishings are to be installed as per the associated SCD Drawing and CW 2160 to ensure stability and prevent frost heaving.
- (b) All other cast-in-place concrete foundations are to be installed as per the Structural drawings supplied and stamped by a professional engineer licensed to practice in the Province of Manitoba.

E19.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

E19.2 General Instructions

E19.2.1 Quality Control

- (a) Testing and Approval of Materials
 - i. Material testing may be required as per this Specification and as directed by the Contract Administrator.

E19.3 Materials

E19.3.1 All materials as per CW 2160.

- (a) Concrete
 - i. Maximum Size of aggregate: 20 mm, nominal;
 - ii. Compression Strength: 28 day compressive strength of 32 Mpa;
 - iii. Slump/Flow: 80 +/- 20mm;
 - iv. Sulphate resistant, Type HS/HSL Cement;
 - v. Maximum water/cement ratio: 0.45; and
 - vi. Air Content: 4-7%.

E19.4 Construction Methods

E19.4.1 Construction Methods as per CW 2160.

- (a) If concrete testing is required, do not place concrete until material testing is performed and reviewed by Contract Administrator.
- (b) All concrete foundations for site furnishings as per the Drawings.

E19.4.2 Cold Weather Concreting

- (a) Cold weather concreting shall be as per Section 3.9 of CW 2160 and CSA A23.1.
 - i. All material and equipment needed for adequate protection and curing shall be on hand and ready to use before concrete placement is started.
 - ii. Before concrete is placed all ice, snow, and frost shall be removed from formwork and all surfaces against which concrete will be placed.
 - iii. Temperatures of adjacent surfaces shall be raised to and maintained at 5° C minimum, prior to and during concreting.

- iv. Calcium chloride or other de-icing salts shall not be used as a de-icing agent in the forms.
- v. Heating equipment and enclosures shall be per CW 2160 and CSA A23.1.

E19.5 Method of Measurement and Basis of Payment

E19.5.1 Method of Measurement shall be as follows:

- (a) No separate measurement for Cast-in-Place Concrete Foundations shall be made for Site Furnishings, as Foundations are incidental to the Works therein.
- (b) If required by the Contract Administrator, no measurement will be made for material testing as this item is incidental to the Work herein.

E19.5.2 Basis of Payment shall be as follows:

- (a) No additional payment for Cast-in-Place Concrete Foundations shall be made for Site Furnishings, as Foundations are incidental to the Works therein.
- (b) If required by the Contract Administrator, no payment will be made for material testing as this item is incidental to the Work herein.

E20. TOPSOIL AND SOD

E20.1 General Description

E20.1.1 This Specification shall amend and supplement CW 3510, CW 3520, and CW 3540 and cover the supply and installation of topsoil and sod.

- (a) The Contractor shall install mineral sod and a minimum 75 mm compacted thickness of topsoil, as required.

E20.1.2 The Work to be completed by the Contractor under this Specification shall include the supply of all materials, and the furnishings of all superintendence, overhead, labour, equipment, tools, and all other things necessary for and incidental to the satisfactory completion of all the Work shown on the Drawings and specified herein.

E20.2 General Instructions

E20.2.1 Quality Control

- (a) Testing and Approval of Materials
 - i. Material testing may be required as per this Specification and as directed by the Contract Administrator.

E20.3 Materials and Construction Methods

E20.3.1 Topsoil shall be as per CW 3540.

E20.3.2 Sod shall be as per CW 3510.

- (a) The Contractor shall install sod in locations as shown on Drawings to cover areas indicated on Drawings.
- (b) Any areas damaged beyond the areas indicated on the Drawings shall be the responsibility of the Contractor to restore through use of topsoil and sod, unless otherwise approved by the Contract Administrator.
- (c) Areas to be sodded are to be laid out on Site and approved by the Contract Administrator before commencing Work. Work outside the limit approved by the Contract Administrator will not be measured and will not be paid for under this section but considered incidental to the Work.

E20.3.3 Incidental items include, but are not limited to; topsoil and sod placed at the edge of new paving and site restoration.

- E20.3.4 Where new sod will meet existing, employ a vertical shearing operation, such as using a sharp spade or edger, along the outside edges of the excavation to create a clean and definite line for the new sod to abut flush to.
- E20.3.5 Restoration shall be achieved using topsoil and sod unless otherwise directed by the Contract Administrator.
- E20.4 Maintenance Period
- E20.4.1 Thirty (30) day maintenance period on sod will commence at Total Performance and acceptance.
- E20.4.2 Termination of maintenance period for sod per Section 9.10 of CW 3510.
- E20.5 Method of Measurement and Basis of Payment
- E20.5.1 Method of Measurement shall be as follows:
- (a) Topsoil and Sodding will be measured on a per square metre basis for:
 - i. "Supply and Install Topsoil and Sod" on Form B: Prices.
- E20.5.2 Basis of Payment shall be as follows:
- (a) Topsoil and Sod will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.