

## **APPENDIX 'A' - GEOTECHNICAL REPORT**

### **GEOTECHNICAL REPORTS FOR:**

Riverton Avenue from Stadacona Street to Allan Street – Asphalt Pavement Reconstruction  
Simpson Avenue from London Street to Louelda Street – Asphalt Pavement Reconstruction

### **PAVEMENT CORES FOR:**

Allan Street from Thames Avenue to Nairn Avenue – Concrete Pavement Rehabilitation  
Dunrobin Avenue from Henderson Highway to Roch Street – Concrete Pavement Rehabilitation  
Hershey Street from Kimberly Avenue to End– Concrete Pavement Rehabilitation

The geotechnical report is provided to aid in the Contractor's evaluation of the existing pavement structure and/or soil conditions. The information presented is considered accurate at the locations shown on the Drawings and at the time of drilling. However, variations in pavement structure and/or soil conditions may exist between test holes and fluctuations in groundwater levels can be expected seasonally and may occur as a result of construction activities. The nature and extent of variations may not become evident until construction commences.



Stantec Consulting Ltd.  
199 Henlow Bay  
Winnipeg MB R3Y 1G4

---

February 25, 2025

Project/File: 123317463-4

Geoff Kerr  
City of Winnipeg  
1155 Pacific Avenue  
Winnipeg, Manitoba R3E 3P1

Good day Geoff,

**Reference: 2025 Local Street Renewal Program (Contract 4) - Geotechnical Investigation**

Stantec Consulting Ltd. (Stantec) was retained to undertake a factual geotechnical investigation for the 2025 Local Street Renewal Program (Contract 4) in Winnipeg, Manitoba. Use of this report is subject to the Statement of General Conditions provided in Appendix A.

The coring and drilling program was conducted from January 7 to January 29, 2025. A total of 18 locations were investigated with pavement coring and/or subsurface geotechnical drilling. Pavement coring was performed by Stantec's geotechnical field technologist, and drilling services were provided by Maple Leaf Drilling Ltd. under the supervision of Stantec's technologist. A Borehole Location Plan is provided in Appendix B.

## **1. Pavement Coring**

A total of 18 pavement core samples were recovered to determine the in-place pavement thickness. In addition, 9 concrete core samples were tested to assess the in-place compressive strength of the concrete. One (1) concrete compressive strength test was cancelled due to the core sample being inadequate for testing (crumbly/fractured condition). The existing pavement thicknesses are summarized in Table 1 below, and the core photographs are provided in Appendix C.

## **2. Geotechnical Drilling**

A total of 8 boreholes were investigated by geotechnical drilling. The boreholes were terminated at a depth of 2.0 m below the pavement, which resulted in borehole depths ranging from 2.0 to 2.2 m. Soil samples were obtained directly from the auger flights at depths of 0.6 m, 0.9 m, 1.2 m, 1.6 m, and 2.0 m from the bottom of the existing pavement. The testholes were examined for evidence of sloughing and groundwater seepage upon completion of drilling.

Reference: 2025 Local Street Renewal Program (Contract 4) - Geotechnical Investigation

The borehole records are provided in Appendix D. The soil classification used in the borehole records is as per ASTM D2487 – *Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)*.

### 3. Existing Pavement Thicknesses

The existing pavement thicknesses are provided in the following table:

**Table 1 – Existing Pavement Thicknesses**

| Borehole No. | Street       | Asphalt Thickness (mm) | Concrete Thickness (mm) | Total Pavement Thickness (mm) |
|--------------|--------------|------------------------|-------------------------|-------------------------------|
| 234          | Riverton Ave | 30                     | 0                       | 30                            |
| 235          | Riverton Ave | 85                     | 0                       | 85                            |
| 236          | Riverton Ave | 30                     | 0                       | 30                            |
| 237          | Simpson Ave  | 30                     | 200                     | 230                           |
| 238          | Simpson Ave  | 30                     | 145                     | 175                           |
| 239          | Simpson Ave  | 30                     | 140                     | 170                           |
| 240          | Simpson Ave  | 25                     | 135                     | 160                           |
| 241          | Simpson Ave  | 30                     | 170                     | 200                           |
| 242          | Allan St     | 0                      | 190                     | 190                           |
| 243          | Allan St     | 0                      | 150                     | 150                           |
| 244          | Allan St     | 0                      | 225                     | 225                           |
| 245          | Allan St     | 0                      | 150                     | 150                           |
| 246          | Dunrobin Ave | 0                      | 160                     | 160                           |
| 247          | Dunrobin Ave | 0                      | 150                     | 150                           |
| 248          | Dunrobin Ave | 0                      | 165                     | 165                           |
| 249          | Dunrobin Ave | 0                      | 150                     | 150                           |
| 250          | Hershey St   | 0                      | 135                     | 135                           |
| 251          | Hershey St   | 0                      | 150                     | 150                           |

### 4. Laboratory Testing

Laboratory determination of moisture content (ASTM D2216) was conducted on all soil samples. The results are provided on the attached borehole records.

In addition, the following laboratory tests were conducted on select samples:

Reference: 2025 Local Street Renewal Program (Contract 4) - Geotechnical Investigation

- ASTM D4318 - *Liquid Limit, Plastic Limit, and Plasticity Index of Soils*
- ASTM D7928 - *Particle-Size Distribution of Fine-Grained Soils Using The Sedimentation Analysis*
- ASTM D698 - *Laboratory Compaction Characteristics of Soil Using Standard Effort*
- ASTM D1883 - *California Bearing Ratio (CBR) of Laboratory-Compacted Soils*
- CSA A23.2-14C – *Obtaining and testing drilled cores for compressive strength testing*

The CBR tests were performed on test specimens compacted to 95% of the maximum dry density under soaked conditions.

Prior to compressive strength testing, the concrete core samples were conditioned in water at room temperature for 48 hours.

The laboratory test reports are provided in Appendix E.

## 5. Closure

Please contact the undersigned if you have any questions regarding this report.

Regards,

**Stantec Consulting Ltd.**



**Guillaume Beauce** P.Eng.  
Senior Associate  
Geotechnical Engineer, Materials Testing Services  
Phone: 204-928-7618  
Mobile: 204-898-8290  
guillaume.beauce@stantec.com



**Jason Thompson** C.E.T.  
Principal – Manager, Materials Testing Services  
Manitoba & Northwestern Ontario Operations  
Phone: 204-928-4004  
Mobile: 204-898-8290  
jason.thompson@stantec.com

Attachment: Appendix A – Statement of General Conditions  
Appendix B – Borehole Location Plan  
Appendix C – Core Photographs  
Appendix D – Borehole Records  
Appendix E – Laboratory Test Reports

- Atterberg Limits Test Reports
- Particle-Size Analysis Reports
- Standard Proctor Test Reports
- CBR Test Reports
- Concrete Compressive Strength Test Results

## **Appendix A**

### Statement of General Conditions

## STATEMENT OF GENERAL CONDITIONS

**USE OF THIS REPORT:** This report has been prepared for the sole benefit of the Client or its agent and may not be used by any third party without the express written consent of Stantec and the Client. Any use which a third party makes of this report is the responsibility of such third party.

**BASIS OF THE REPORT:** The information, opinions, and/or recommendations made in this report are in accordance with Stantec's present understanding of the site-specific project as described by the Client. The applicability of these is restricted to the site conditions encountered at the time of the investigation or study. If the proposed site-specific project differs or is modified from what is described in this report or if the site conditions are altered, this report is no longer valid unless Stantec is requested by the Client to review and revise the report to reflect the differing or modified project specifics and/or the altered site conditions.

**STANDARD OF CARE:** Preparation of this report, and all associated work, was carried out in accordance with the normally accepted standard of care in the state or province of execution for the specific professional service provided to the Client. No other warranty is made.

**INTERPRETATION OF SITE CONDITIONS:** Soil, rock, or other material descriptions, and statements regarding their condition, made in this report are based on site conditions encountered by Stantec at the time of the work and at the specific testing and/or sampling locations. Classifications and statements of condition have been made in accordance with normally accepted practices which are judgmental in nature; no specific description should be considered exact, but rather reflective of the anticipated material behavior. Extrapolation of in situ conditions can only be made to some limited extent beyond the sampling or test points. The extent depends on variability of the soil, rock, and groundwater conditions as influenced by geological processes, construction activity, and site use.




**VARYING OR UNEXPECTED CONDITIONS:** Should any site or subsurface conditions be encountered that are different from those described in this report or encountered at the test locations, Stantec must be notified immediately to assess if the varying or unexpected conditions are substantial and if reassessments of the report conclusions or recommendations are required. Stantec will not be responsible to any party for damages incurred as a result of failing to notify Stantec that differing site or sub-surface conditions are present upon becoming aware of such conditions.

**PLANNING, DESIGN, OR CONSTRUCTION:** Development or design plans and specifications should be reviewed by Stantec, sufficiently ahead of initiating the next project stage (property acquisition, tender, construction, etc.), to confirm that this report completely addresses the elaborated project specifics and that the contents of this report have been properly interpreted. Specialty quality assurance services (field observations and testing) during construction are a necessary part of the evaluation of sub-subsurface conditions and site preparation works. Site work relating to the recommendations included in this report should only be carried out in the presence of a qualified geotechnical engineer; Stantec cannot be responsible for site work carried out without being present.



## **Appendix B**

### Borehole Location Plan






SEWER — BORE HOLE ● WATER MAIN/WATERLINE —  
 MANHOLE ○ CATCH BASIN □

NOTE: DRILL 2.0m BOREHOLE AS PER SITE INVESTIGATION SPECIFICATION F3.4

DATE: 11/14/2024  
 DRAWING NO.: 1 of 3  
 DRAWN BY: J.W.  
 SCALE: NTS

2025 LOCAL STREET RENEWAL PROGRAM CORING DRAWING - CONTRACT 4  
 RIVERTON AV FROM ALLEN ST TO STADACONA ST - RECONSTRUCTION  
 SIMPSON AV FROM LONDON ST TO LOUELDA ST - RECONSTRUCTION








NOTE: DRILL PAVEMENT CORES AS PER SITE INVESTIGATION SPECIFICATION F3.5

DATE: 11/13/2024  
 DRAWING NO.: 2 of 3  
 DRAWN BY: J.W.  
 SCALE: NTS

2025 LOCAL STREET RENEWAL PROGRAM CORING DRAWING - **CONTRACT 4**  
**ALLAN ST FROM THAMES AV TO TWEED AV - MINOR REHABILITATION**  
**RIVERTON AV FROM STADACONA ST TO ALLAN ST - RECONSTRUCTION**



|   |   |                     |                        |  |
|---|---|---------------------|------------------------|--|
| SEWER — PAVEMENT CORES ●<br>MANHOLE ○ CATCH BASIN □ | NOTE: DRILL PAVEMENT CORES AS PER<br>SITE INVESTIGATION SPECIFICATION<br>F3.5 | DATE:<br>11/13/2024 | DRAWING NO.:<br>3 of 3 | <b>2025 LOCAL STREET RENEWAL PROGRAM CORING DRAWING - CONTRACT 4</b><br><br><b>HERSEY ST FROM KIMBERLY AV TO END -<br/>         REHABILITATION</b><br><b>DUNROBIN AV FROM HENDERSON HWY TO ROCH ST -<br/>         REHABILITATION</b> |
|   |   | DRAWN BY:<br>J.W.   | SCALE:<br>NTS          |  |

## **Appendix C**

### Core Photographs



Figure 1 – Core Sample No. 234 – Riverton Ave



Figure 2 – Core Sample No. 235 – Riverton Ave



Figure 3 – Core Sample No. 236 - Riverton Ave



Figure 4 – Core Sample No. 237 – Simpson Ave



Figure 5 – Core Sample No. 238 – Simpson Ave



Figure 6 – Core Sample No. 239 – Simpson Ave



Figure 7 – Core Sample No. 240 – Simpson Ave



Figure 8 – Core Sample No. 241 – Simpson Ave



Figure 9 – Core Sample No. 242 – Allan St



Figure 10 – Core Sample No. 243 – Allan St



Figure 11 – Core Sample No. 244 – Allan St

**Core Photograph Not Available**

Figure 12 – Core Sample No. 245 – Allan St



Figure 43 – Core Sample No. 246 – Dunrobin Ave



Figure 14 – Core Sample No. 247 – Dunrobin Ave



Figure 15 – Core Sample No. 248 – Dunrobin Ave



Figure 16 – Core Sample No. 249 – Dunrobin Ave



Figure 17 – Core Sample No. 250 – Hershey St



Figure 18 – Core Sample No. 251 – Hershey St



## **Appendix D**

### Borehole Records


CLIENT: City of Winnipeg  
 PROJECT: 2025 Local Street Renewal Program (Contract 4)  
 LOCATION: Riverton Ave  
 DATE BORED: January 09 2025

PROJECT NO.: 123317463-4  
 BH ELEVATION: N/A  
 DATUM: N/A

WATER LEVEL: N/A

| DEPTH (m) | ELEVATION (m) | SOIL DESCRIPTION (USCS)   | STRATA PLOT | SAMPLES |        |                        |                  | OTHER TESTS / REMARKS | UNDRAINED SHEAR STRENGTH, Cu (kPa) |         |         |         | BACKFILL | ELEVATION (m) |
|-----------|---------------|---|-------------|---------|--------|------------------------|------------------|-----------------------|------------------------------------|---------|---------|---------|----------|---------------|
|           |               |   |             | TYPE    | NUMBER | RECOVERY (mm) or TCR % | N-VALUE or RQD % |                       | 50 kPa                             | 100 kPa | 150 kPa | 200 kPa |          |               |
| 0         |               | Firm black <b>FAT CLAY (CH)</b><br>- some silt  |             |         |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               | - black to brown and some silt below 0.5 m  |             |         |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   |             | BS      |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |                       |                                    |         |         |         |          |               |
| 1         |               | Soft tan <b>SILT (ML)</b><br>- some sand, trace clay  |             |         |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   | AS          |         |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   | AS          |         |        |                        |                  |                       |                                    |         |         |         |          |               |
| 2         |               | <b>End of Borehole</b><br>• Borehole terminated at a depth of 2.0 m.<br>• No groundwater seepage or soil sloughing was observed during or upon completion of drilling.<br>• Borehole backfilled in accordance with the City of Winnipeg Street Cuts Manual. |             |         |        |                        |                  |                       |                                    |         |         |         |          |               |

Sieve/Hydro at 0.6 m  
 G S M C  
 0% 2% 17% 82%



BACKFILL SYMBOL: ASPHALT    GROUT    CONCRETE  
 BENTONITE    DRILL CUTTINGS    SAND    SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.    Logged By: RB  
 Drilling Method: 125 mm SSA    Reviewed By: GB  
 Completion Depth: 2 m    Page 1 of 1

CLIENT: City of Winnipeg  
 PROJECT: 2025 Local Street Renewal Program (Contract 4)  
 LOCATION: Riverton Ave  
 DATE BORED: January 09 2025

PROJECT NO.: 123317463-4  
 BH ELEVATION: N/A  
 DATUM: N/A  
 WATER LEVEL: N/A

| DEPTH (m) | ELEVATION (m) | SOIL DESCRIPTION (USCS)   | STRATA PLOT | SAMPLES |        |                        |                  | OTHER TESTS / REMARKS                         | UNDRAINED SHEAR STRENGTH, Cu (kPa) |  |         |         |                                  |  |  |  | BACKFILL | ELEVATION (m) |  |  |  |
|-----------|---------------|---|-------------|---------|--------|------------------------|------------------|---|------------------------------------|--|---------|---------|----------------------------------|--|--|--|----------|---------------|--|--|--|
|           |               |   |             | TYPE    | NUMBER | RECOVERY (mm) or TCR % | N-VALUE or RQD % |   | 50 kPa                             | 100 kPa  | 150 kPa | 200 kPa | WATER CONTENT & ATTERBERG LIMITS |  |  |  |          |               |  |  |  |
|           |               |   |             |         |        |                        |                  |   |                                    | ▲ LABORATORY TEST      ◆ FIELD VANE TEST<br>★ POCKET PENETROMETER    □ POCKET SHEAR VANE |         |         |                                  |  |  |  |          |               |  |  |  |
|           |               |   |             |         |        |                        |                  |   |                                    | SPT (N-value) BLOWS/0.3m<br>10    20    30    40    50    60    70    80                 |         |         |                                  |  |  |  |          |               |  |  |  |
| 0         |               | ASPHALT   |             |         |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
|           |               | Firm brown FAT CLAY (CH)  |             |         |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
|           |               | Soft tan FAT CLAY (CH)  |             |         |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
| 1         |               | Soft tan SILT (ML)<br>- some sand   |             | BS      |        |                        |                  | Sieve/Hydro at 0.7 m<br>G 0% S 1% M 35% C 63% |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
|           |               |   |             | AS      |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
|           |               |   |             | AS      |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
|           |               |   |             | AS      |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
|           |               |   |             | AS      |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
| 2         |               | Firm brown FAT CLAY (CH)<br>- some silt, trace sand   |             | AS      |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |
| 3         |               | <b>End of Borehole</b><br>• Borehole terminated at a depth of 2.1 m.<br>• No groundwater seepage or soil sloughing was observed during or upon completion of drilling.<br>• Borehole backfilled in accordance with the City of Winnipeg Street Cuts Manual. |             |         |        |                        |                  |   |                                    |  |         |         |                                  |  |  |  |          |               |  |  |  |


BACKFILL SYMBOL: ASPHALT    GROUT    CONCRETE  
 BENTONITE    DRILL CUTTINGS    SAND    SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.      Logged By: RB  
 Drilling Method: 125 mm SSA      Reviewed By: GB  
 Completion Depth: 2.1 m      Page 1 of 1

CLIENT: City of Winnipeg  
 PROJECT: 2025 Local Street Renewal Program (Contract 4)  
 LOCATION: Riverton Ave  
 DATE BORED: January 09 2025

PROJECT NO.: 123317463-4  
 BH ELEVATION: N/A  
 DATUM: N/A  
 WATER LEVEL: N/A

| DEPTH (m) | ELEVATION (m) | SOIL DESCRIPTION (USCS)   | STRATA PLOT | SAMPLES |        |                        |                  | OTHER TESTS / REMARKS                         | UNDRAINED SHEAR STRENGTH, Cu (kPa) |         |         |         | BACKFILL | ELEVATION (m) |
|-----------|---------------|---|-------------|---------|--------|------------------------|------------------|---|------------------------------------|---------|---------|---------|----------|---------------|
|           |               |   |             | TYPE    | NUMBER | RECOVERY (mm) or TCR % | N-VALUE or RQD % |   | 50 kPa                             | 100 kPa | 150 kPa | 200 kPa |          |               |
| 0         |               | ASPHALT<br>FILL: granular base  |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               | Firm black to grey FAT CLAY (CH)  |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | BS      |        |                        |                  | Sieve/Hydro at 0.6 m<br>G 0% S 2% M 35% C 63% |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
| 1         |               | Soft tan SILT (ML)<br>- some sand   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
| 2         |               | <b>End of Borehole</b><br>• Borehole terminated at a depth of 2.0 m.<br>• No groundwater seepage or soil sloughing was observed during or upon completion of drilling.<br>• Borehole backfilled in accordance with the City of Winnipeg Street Cuts Manual. |             |         |        |                        |                  |   |                                    |         |         |         |          |               |



BACKFILL SYMBOL: ASPHALT    GROUT    CONCRETE  
 BENTONITE    DRILL CUTTINGS    SAND    SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.    Logged By: RB  
 Drilling Method: 125 mm SSA    Reviewed By: GB  
 Completion Depth: 2 m    Page 1 of 1

CLIENT: City of Winnipeg  
 PROJECT: 2025 Local Street Renewal Program (Contract 4)  
 LOCATION: Simpson Ave  
 DATE BORED: January 09 2025

PROJECT NO.: 123317463-4  
 BH ELEVATION: N/A  
 DATUM: N/A  
 WATER LEVEL: N/A

| DEPTH (m) | ELEVATION (m) | SOIL DESCRIPTION (USCS)   | STRATA PLOT | SAMPLES |        |                        |                  | OTHER TESTS / REMARKS                         | UNDRAINED SHEAR STRENGTH, Cu (kPa) |         |         |         | BACKFILL | ELEVATION (m) |
|-----------|---------------|---|-------------|---------|--------|------------------------|------------------|---|------------------------------------|---------|---------|---------|----------|---------------|
|           |               |   |             | TYPE    | NUMBER | RECOVERY (mm) or TCR % | N-VALUE or RQD % |   | 50 kPa                             | 100 kPa | 150 kPa | 200 kPa |          |               |
| 0         |               | ASPHALT<br>FILL: granular base  |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               | CONCRETE<br>FILL: granular base, 19 mm  |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               | Firm brown FAT CLAY (CH)  |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | BS      |        |                        |                  | Sieve/Hydro at 0.8 m<br>G 0% S 0% M 27% C 73% |                                    |         |         |         |          |               |
| 1         |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               | Soft tan LEAN CLAY (CL)   |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               | Firm brown FAT CLAY (CH)<br>- some silt, trace sand   |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
| 2         |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
| 3         |               | <b>End of Borehole</b><br>• Borehole terminated at a depth of 2.2 m.<br>• No groundwater seepage or soil sloughing was observed during or upon completion of drilling.<br>• Borehole backfilled in accordance with the City of Winnipeg Street Cuts Manual. |             |         |        |                        |                  |   |                                    |         |         |         |          |               |

BACKFILL SYMBOL ASPHALT GROUT CONCRETE  
 BENTONITE DRILL CUTTINGS SAND SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.      Logged By: RB  
 Drilling Method: 125 mm SSA      Reviewed By: GB  
 Completion Depth: 2.2 m      Page 1 of 1

CLIENT: City of Winnipeg  
 PROJECT: 2025 Local Street Renewal Program (Contract 4)  
 LOCATION: Simpson Ave  
 DATE BORED: January 09 2025

PROJECT NO.: 123317463-4  
 BH ELEVATION: N/A  
 DATUM: N/A  
 WATER LEVEL: N/A

| DEPTH (m) | ELEVATION (m) | SOIL DESCRIPTION (USCS)   | STRATA PLOT | SAMPLES |        |                        |                  | OTHER TESTS / REMARKS                         | UNDRAINED SHEAR STRENGTH, Cu (kPa) |         |         |         | BACKFILL | ELEVATION (m) |
|-----------|---------------|---|-------------|---------|--------|------------------------|------------------|---|------------------------------------|---------|---------|---------|----------|---------------|
|           |               |   |             | TYPE    | NUMBER | RECOVERY (mm) or TCR % | N-VALUE or RQD % |   | 50 kPa                             | 100 kPa | 150 kPa | 200 kPa |          |               |
| 0         |               | ASPHALT<br>CONCRETE   |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               | FILL: granular base, 19 mm<br>Firm brown <b>FAT CLAY (CH)</b><br>- trace silt   |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               | Soft tan <b>LEAN CLAY (CL)</b>  |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
| 1         |               | Firm brown <b>FAT CLAY (CH)</b><br>- some silt, trace sand  |             |         |        |                        |                  | Sieve/Hydro at 0.8 m<br>G 0% S 2% M 69% C 30% |                                    |         |         |         |          |               |
| 2         |               |   |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
| 3         |               | <b>End of Borehole</b><br>• Borehole terminated at a depth of 2.2 m.<br>• No groundwater seepage or soil sloughing was observed during or upon completion of drilling.<br>• Borehole backfilled in accordance with the City of Winnipeg Street Cuts Manual. |             |         |        |                        |                  |   |                                    |         |         |         |          |               |

BACKFILL SYMBOL: ASPHALT    GROUT    CONCRETE  
 BENTONITE    DRILL CUTTINGS    SAND    SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.    Logged By: RB  
 Drilling Method: 125 mm SSA    Reviewed By: GB  
 Completion Depth: 2.2 m    Page 1 of 1

Printed Feb 24 2025 09:19:00 SOIL 123317463-4.GPJ 2/24/25

CLIENT: City of Winnipeg  
 PROJECT: 2025 Local Street Renewal Program (Contract 4)  
 LOCATION: Simpson Ave  
 DATE BORED: January 09 2025

PROJECT NO.: 123317463-4  
 BH ELEVATION: N/A  
 DATUM: N/A  
 WATER LEVEL: N/A

| DEPTH (m) | ELEVATION (m) | SOIL DESCRIPTION (USCS)   | STRATA PLOT | SAMPLES |        |                        |                  | OTHER TESTS / REMARKS                         | UNDRAINED SHEAR STRENGTH, Cu (kPa) |         |         |         | BACKFILL | ELEVATION (m) |
|-----------|---------------|---|-------------|---------|--------|------------------------|------------------|---|------------------------------------|---------|---------|---------|----------|---------------|
|           |               |   |             | TYPE    | NUMBER | RECOVERY (mm) or TCR % | N-VALUE or RQD % |   | 50 kPa                             | 100 kPa | 150 kPa | 200 kPa |          |               |
| 0         |               | ASPHALT<br>CONCRETE   |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               | FILL: granular base, 19 mm<br>Soft tan LEAN CLAY (CL)   |             |         |        |                        |                  |   |                                    |         |         |         |          |               |
| 1         |               | Firm brown FAT CLAY (CH)<br>- trace silt  |             | BS      |        |                        |                  | Sieve/Hydro at 0.8 m<br>G 0% S 6% M 79% C 16% |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
| 2         |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |   |                                    |         |         |         |          |               |
| 3         |               | <b>End of Borehole</b><br>• Borehole terminated at a depth of 2.2 m.<br>• No groundwater seepage or soil sloughing was observed during or upon completion of drilling.<br>• Borehole backfilled in accordance with the City of Winnipeg Street Cuts Manual. |             |         |        |                        |                  |   |                                    |         |         |         |          |               |

BACKFILL SYMBOL ASPHALT GROUT CONCRETE  
 BENTONITE DRILL CUTTINGS SAND SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.      Logged By: RB  
 Drilling Method: 125 mm SSA      Reviewed By: GB  
 Completion Depth: 2.2 m      Page 1 of 1

CLIENT: City of Winnipeg  
 PROJECT: 2025 Local Street Renewal Program (Contract 4)  
 LOCATION: Simpson Ave  
 DATE BORED: January 09 2025

PROJECT NO.: 123317463-4  
 BH ELEVATION: N/A  
 DATUM: N/A  
 WATER LEVEL: N/A

| DEPTH (m) | ELEVATION (m) | SOIL DESCRIPTION (USCS)   | STRATA PLOT                      | SAMPLES |        |                        |                  | OTHER TESTS / REMARKS                                  | UNDRAINED SHEAR STRENGTH, Cu (kPa) |  |         |         |                                  |  |  |  | BACKFILL | ELEVATION (m) |  |
|-----------|---------------|---|----------------------------------|---------|--------|------------------------|------------------|--|------------------------------------|--|---------|---------|----------------------------------|--|--|--|----------|---------------|--|
|           |               |   |                                  | TYPE    | NUMBER | RECOVERY (mm) or TCR % | N-VALUE or RQD % |  | 50 kPa                             | 100 kPa  | 150 kPa | 200 kPa | WATER CONTENT & ATTERBERG LIMITS |  |  |  |          |               |  |
|           |               |   |                                  |         |        |                        |                  |  |                                    | ▲ LABORATORY TEST      ◆ FIELD VANE TEST<br>★ POCKET PENETROMETER    □ POCKET SHEAR VANE<br>✖ SPT (N-value) BLOWS/0.3m |         |         |                                  |  |  |  |          |               |  |
|           |               |   |                                  |         |        |                        |                  |  |                                    | Water Content (%) and Blow Count<br>10   20   30   40   50   60   70   80  |         |         |                                  |  |  |  |          |               |  |
| 0         |               | ASPHALT<br>CONCRETE<br>FILL: granular base, 19 mm<br>Firm brown <b>FAT CLAY (CH)</b><br>some silt, trace sand<br>Soft tan <b>LEAN CLAY (CL)</b>   |                                  |         |        |                        |                  |  |                                    |  |         |         |                                  |  |  |  |          |               |  |
| 1         |               |   | BS<br>AS<br>AS<br>AS<br>AS<br>AS |         |        |                        |                  | Sieve/Hydro at 0.8 m<br>G   S   M   C<br>0% 4% 59% 37% |                                    |  |         |         |                                  |  |  |  |          |               |  |
| 2         |               | Firm black to grey <b>FAT CLAY (CH)</b><br>- trace silt   | AS<br>AS                         |         |        |                        |                  |  |                                    |  |         |         |                                  |  |  |  |          |               |  |
| 3         |               | <b>End of Borehole</b><br>• Borehole terminated at a depth of 2.2 m.<br>• No groundwater seepage or soil sloughing was observed during or upon completion of drilling.<br>• Borehole backfilled in accordance with the City of Winnipeg Street Cuts Manual. |                                  |         |        |                        |                  |  |                                    |  |         |         |                                  |  |  |  |          |               |  |

BACKFILL SYMBOL: ASPHALT    GROUT    CONCRETE  
 BENTONITE    DRILL CUTTINGS    SAND    SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.      Logged By: RB  
 Drilling Method: 125 mm SSA      Reviewed By: GB  
 Completion Depth: 2.2 m      Page 1 of 1




CLIENT: City of Winnipeg  
 PROJECT: 2025 Local Street Renewal Program (Contract 4)  
 LOCATION: Simpson Ave  
 DATE BORED: January 09 2025

PROJECT NO.: 123317463-4  
 BH ELEVATION: N/A  
 DATUM: N/A  
 WATER LEVEL: N/A

| DEPTH (m) | ELEVATION (m) | SOIL DESCRIPTION (USCS)   | STRATA PLOT | SAMPLES |        |                        |                  | OTHER TESTS / REMARKS | UNDRAINED SHEAR STRENGTH, Cu (kPa) |         |         |         | BACKFILL | ELEVATION (m) |
|-----------|---------------|---|-------------|---------|--------|------------------------|------------------|-----------------------|------------------------------------|---------|---------|---------|----------|---------------|
|           |               |   |             | TYPE    | NUMBER | RECOVERY (mm) or TCR % | N-VALUE or RQD % |                       | 50 kPa                             | 100 kPa | 150 kPa | 200 kPa |          |               |
| 0         |               | ASPHALT<br>CONCRETE   |             |         |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               | FILL: granular base, 19 mm<br>Firm grey FAT CLAY (CH)<br>- some silt  |             |         |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               | Soft tan LEAN CLAY (CL)   |             | BS      |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               |   |             | AS      |        |                        |                  |                       |                                    |         |         |         |          |               |
|           |               | Firm grey FAT CLAY (CH)<br>- trace silt   |             | AS      |        |                        |                  |                       |                                    |         |         |         |          |               |
| 2.2       |               | <b>End of Borehole</b><br><ul style="list-style-type: none"> <li>Borehole terminated at a depth of 2.2 m.</li> <li>No groundwater seepage or soil sloughing was observed during or upon completion of drilling.</li> <li>Borehole backfilled in accordance with the City of Winnipeg Street Cuts Manual.</li> </ul> |             |         |        |                        |                  |                       |                                    |         |         |         |          |               |

Sieve/Hydro at 0.8 m  
 G S M C  
 0% 1% 18% 81%

UNDRAINED SHEAR STRENGTH, Cu (kPa)  
 ▲ LABORATORY TEST    ◆ FIELD VANE TEST  
 ★ POCKET PENETROMETER    □ POCKET SHEAR VANE  
 50 kPa    100 kPa    150 kPa    200 kPa  
 WATER CONTENT & ATTERBERG LIMITS    W<sub>P</sub>    W    W<sub>L</sub>  
 ✕ SPT (N-value) BLOWS/0.3m



Printed Feb 24 2025 09:19:03 SOIL\_123317463-4.GPJ\_2/24/25

BACKFILL SYMBOL: ASPHALT    GROUT    CONCRETE  
 BENTONITE    DRILL CUTTINGS    SAND    SLOUGH

Drilling Contractor: Maple Leaf Drilling Ltd.    Logged By: RB  
 Drilling Method: 125 mm SSA    Reviewed By: GB  
 Completion Depth: 2.2 m    Page 1 of 1

## **Appendix E**

### Laboratory Testing Reports

- Atterberg Limits
- Particle-Size Analysis
- Standard Proctor
- California Bearing Ratio
- Concrete Compressive Strength

## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 1

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Feb.03

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-234, 0.6 m, Riverton Ave.

STANTEC SAMPLE NO. 5625

|        | LIQUID LIMIT |    |
|--------|--------------|----|
| TRIAL  | 1            | 2  |
| BLOWS  | 26           | 25 |
| MC (%) | 81           | 82 |

|        | PLASTIC LIMIT |    |
|--------|---------------|----|
| TRIAL  | 1             | 2  |
| MC (%) | 33            | 33 |

|                      |      |
|----------------------|------|
| LIQUID LIMIT, LL     | 82   |
| PLASTIC LIMIT, PL    | 33   |
| PLASTICITY INDEX, PI | 49   |
| AS REC'D MC (%)      | 38.7 |



COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 2

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Feb.03

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-235, 0.7 m, Riverton Ave.

STANTEC SAMPLE NO. 5626

| TRIAL  | LIQUID LIMIT |    |
|--------|--------------|----|
|        | 1            | 2  |
| BLOWS  | 28           | 29 |
| MC (%) | 73           | 73 |

| TRIAL  | PLASTIC LIMIT |    |
|--------|---------------|----|
|        | 1             | 2  |
| MC (%) | 28            | 28 |

|                      |      |
|----------------------|------|
| LIQUID LIMIT, LL     | 74   |
| PLASTIC LIMIT, PL    | 28   |
| PLASTICITY INDEX, PI | 47   |
| AS REC'D MC (%)      | 38.8 |



COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

# ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 3

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Feb.04

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-236, 0.6 m, Riverton Ave.

STANTEC SAMPLE NO. 5627

| TRIAL  | LIQUID LIMIT |    |
|--------|--------------|----|
|        | 1            | 2  |
| BLOWS  | 25           | 24 |
| MC (%) | 75           | 76 |

| TRIAL  | PLASTIC LIMIT |    |
|--------|---------------|----|
|        | 1             | 2  |
| MC (%) | 32            | 31 |

|                      |      |
|----------------------|------|
| LIQUID LIMIT, LL     | 75   |
| PLASTIC LIMIT, PL    | 31   |
| PLASTICITY INDEX, PI | 44   |
| AS REC'D MC (%)      | 29.1 |



COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 4

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Feb.04

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-237, 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5628

|        | LIQUID LIMIT |    |
|--------|--------------|----|
| TRIAL  | 1            | 2  |
| BLOWS  | 28           | 26 |
| MC (%) | 77           | 77 |

|        | PLASTIC LIMIT |    |
|--------|---------------|----|
| TRIAL  | 1             | 2  |
| MC (%) | 29            | 29 |

|                      |      |
|----------------------|------|
| LIQUID LIMIT, LL     | 78   |
| PLASTIC LIMIT, PL    | 29   |
| PLASTICITY INDEX, PI | 48   |
| AS REC'D MC (%)      | 30.5 |



COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 5

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Feb.05

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-238, 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5629

| TRIAL  | LIQUID LIMIT |    |
|--------|--------------|----|
|        | 1            | 2  |
| BLOWS  | 24           | 25 |
| MC (%) | 38           | 38 |

| TRIAL  | PLASTIC LIMIT |    |
|--------|---------------|----|
|        | 1             | 2  |
| MC (%) | 18            | 18 |

|                      |      |
|----------------------|------|
| LIQUID LIMIT, LL     | 38   |
| PLASTIC LIMIT, PL    | 18   |
| PLASTICITY INDEX, PI | 20   |
| AS REC'D MC (%)      | 21.8 |



COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 6

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Feb.05

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-239, 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5630

|        | LIQUID LIMIT |    |
|--------|--------------|----|
| TRIAL  | 1            | 2  |
| BLOWS  | 22           | 23 |
| MC (%) | 30           | 29 |

|        | PLASTIC LIMIT |    |
|--------|---------------|----|
| TRIAL  | 1             | 2  |
| MC (%) | 18            | 18 |

|                      |      |
|----------------------|------|
| LIQUID LIMIT, LL     | 29   |
| PLASTIC LIMIT, PL    | 18   |
| PLASTICITY INDEX, PI | 11   |
| AS REC'D MC (%)      | 20.2 |



COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services



# ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 7

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Feb.04

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Kailash Vaghjyani

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-240, 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5631

|        | LIQUID LIMIT |    |
|--------|--------------|----|
| TRIAL  | 1            | 2  |
| BLOWS  | 27           | 26 |
| MC (%) | 44           | 43 |

|        | PLASTIC LIMIT |    |
|--------|---------------|----|
| TRIAL  | 1             | 2  |
| MC (%) | 16            | 16 |

|                      |      |
|----------------------|------|
| LIQUID LIMIT, LL     | 44   |
| PLASTIC LIMIT, PL    | 16   |
| PLASTICITY INDEX, PI | 28   |
| AS REC'D MC (%)      | 21.0 |



COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D4318 - LIQUID LIMIT, PLASTIC LIMIT AND PLASTICITY INDEX OF SOILS (LL METHOD B - ONE-POINT)

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 8

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Feb.04

SAMPLED BY: Stantec Consulting Ltd.

SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Kailash Vaghjiyani

**MATERIAL IDENTIFICATION**


CLIENT FIELD ID BH-241, 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5632

| TRIAL  | LIQUID LIMIT |    |
|--------|--------------|----|
|        | 1            | 2  |
| BLOWS  | 26           | 25 |
| MC (%) | 86           | 86 |

| TRIAL  | PLASTIC LIMIT |    |
|--------|---------------|----|
|        | 1             | 2  |
| MC (%) | 28            | 28 |

|                      |      |
|----------------------|------|
| LIQUID LIMIT, LL     | 86   |
| PLASTIC LIMIT, PL    | 28   |
| PLASTICITY INDEX, PI | 58   |
| AS REC'D MC (%)      | 29.7 |



COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 1

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Jan.27

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-234. 0.6 m, Riverton Ave.

STANTEC SAMPLE NO. 5625



| Sieve Size (mm) | % Passing |
|-----------------|-----------|
| 50.0            | 100.0     |
| 40.0            | 100.0     |
| 25.0            | 100.0     |
| 20.0            | 100.0     |
| 16.0            | 100.0     |
| 12.5            | 100.0     |
| 9.5             | 100.0     |
| 4.75            | 100.0     |
| 2.36            | 100.0     |
| 2.00            | 100.0     |
| 1.18            | 100.0     |
| 0.600           | 100.0     |
| 0.300           | 99.8      |
| 0.150           | 99.5      |
| 0.075           | 98.4      |
| 0.005           | 82.5      |
| 0.002           | 81.7      |
| 0.001           | 78.7      |

| Gravel | Sand   |        |      | Silt | Clay | Colloids |
|--------|--------|--------|------|------|------|----------|
|        | Coarse | Medium | Fine |      |      |          |
| 0.0    | 0.0    | 0.1    | 1.5  | 16.7 | 81.7 | 78.7     |

**COMMENTS**

No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 2

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Jan.27

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-235. 0.7 m, Riverton Ave.

STANTEC SAMPLE NO. 5626



| Sieve Size (mm) | % Passing |
|-----------------|-----------|
| 50.0            | 100.0     |
| 40.0            | 100.0     |
| 25.0            | 100.0     |
| 20.0            | 100.0     |
| 16.0            | 100.0     |
| 12.5            | 100.0     |
| 9.5             | 100.0     |
| 4.75            | 100.0     |
| 2.36            | 100.0     |
| 2.00            | 100.0     |
| 1.18            | 100.0     |
| 0.600           | 100.0     |
| 0.300           | 99.9      |
| 0.150           | 99.6      |
| 0.075           | 98.7      |
| 0.005           | 67.0      |
| 0.002           | 63.3      |
| 0.001           | 63.2      |

| Gravel | Sand   |        |      | Silt | Clay | Colloids |
|--------|--------|--------|------|------|------|----------|
|        | Coarse | Medium | Fine |      |      |          |
| 0.0    | 0.0    | 0.1    | 1.2  | 35.4 | 63.3 | 63.2     |

COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Dept.  
104 - 1155 Pacific Avenue  
Winnipeg, Manitoba  
R3E 2P1

PROJECT 2025 Local Street Renewal Program  
Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 3

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Jan.24

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-236. 0.6 m, Riverton Ave.

STANTEC SAMPLE NO. 5627



| Sieve Size (mm) | % Passing |
|-----------------|-----------|
| 50.0            | 100.0     |
| 40.0            | 100.0     |
| 25.0            | 100.0     |
| 20.0            | 100.0     |
| 16.0            | 100.0     |
| 12.5            | 100.0     |
| 9.5             | 100.0     |
| 4.75            | 100.0     |
| 2.36            | 100.0     |
| 2.00            | 99.9      |
| 1.18            | 99.9      |
| 0.600           | 99.7      |
| 0.300           | 99.4      |
| 0.150           | 99.1      |
| 0.075           | 98.1      |
| 0.005           | 71.6      |
| 0.002           | 63.3      |
| 0.001           | 55.7      |

| Gravel | Sand   |        |      | Silt | Clay | Colloids |
|--------|--------|--------|------|------|------|----------|
|        | Coarse | Medium | Fine |      |      |          |
| 0.0    | 0.1    | 0.4    | 1.4  | 34.8 | 63.3 | 55.7     |

**COMMENTS**

No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 4

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Jan.27

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-237. 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5628



| Sieve Size (mm) | % Passing |
|-----------------|-----------|
| 50.0            | 100.0     |
| 40.0            | 100.0     |
| 25.0            | 100.0     |
| 20.0            | 100.0     |
| 16.0            | 100.0     |
| 12.5            | 100.0     |
| 9.5             | 100.0     |
| 4.75            | 100.0     |
| 2.36            | 100.0     |
| 2.00            | 100.0     |
| 1.18            | 100.0     |
| 0.600           | 99.9      |
| 0.300           | 99.8      |
| 0.150           | 99.7      |
| 0.075           | 99.6      |
| 0.005           | 74.5      |
| 0.002           | 72.5      |
| 0.001           | 72.5      |

| Gravel | Sand   |        |      | Silt | Clay | Colloids |
|--------|--------|--------|------|------|------|----------|
|        | Coarse | Medium | Fine |      |      |          |
| 0.0    | 0.0    | 0.2    | 0.2  | 27.1 | 72.5 | 72.5     |

COMMENTS  
 No comments.

REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 5

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Jan.27

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-238. 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5629



| Sieve Size (mm) | % Passing |
|-----------------|-----------|
| 50.0            | 100.0     |
| 40.0            | 100.0     |
| 25.0            | 100.0     |
| 20.0            | 100.0     |
| 16.0            | 100.0     |
| 12.5            | 100.0     |
| 9.5             | 100.0     |
| 4.75            | 100.0     |
| 2.36            | 100.0     |
| 2.00            | 99.9      |
| 1.18            | 99.7      |
| 0.600           | 99.3      |
| 0.300           | 98.9      |
| 0.150           | 98.6      |
| 0.075           | 98.0      |
| 0.005           | 40.1      |
| 0.002           | 29.5      |
| 0.001           | 23.9      |

| Gravel | Sand   |        |      | Silt | Clay | Colloids |
|--------|--------|--------|------|------|------|----------|
|        | Coarse | Medium | Fine |      |      |          |
| 0.0    | 0.1    | 0.8    | 1.1  | 68.5 | 29.5 | 23.9     |

COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 6

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Jan.24

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-239. 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5630



| Sieve Size (mm) | % Passing |
|-----------------|-----------|
| 50.0            | 100.0     |
| 40.0            | 100.0     |
| 25.0            | 100.0     |
| 20.0            | 100.0     |
| 16.0            | 100.0     |
| 12.5            | 100.0     |
| 9.5             | 100.0     |
| 4.75            | 100.0     |
| 2.36            | 100.0     |
| 2.00            | 100.0     |
| 1.18            | 99.9      |
| 0.600           | 99.7      |
| 0.300           | 99.3      |
| 0.150           | 98.7      |
| 0.075           | 94.1      |
| 0.005           | 21.1      |
| 0.002           | 15.6      |
| 0.001           | 12.8      |

| Gravel | Sand   |        |      | Silt | Clay | Colloids |
|--------|--------|--------|------|------|------|----------|
|        | Coarse | Medium | Fine |      |      |          |
| 0.0    | 0.0    | 0.5    | 5.4  | 78.5 | 15.6 | 12.8     |

**COMMENTS**

No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services



## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 7

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Jan.27

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-240. 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5631



| Sieve Size (mm) | % Passing |
|-----------------|-----------|
| 50.0            | 100.0     |
| 40.0            | 100.0     |
| 25.0            | 100.0     |
| 20.0            | 100.0     |
| 16.0            | 100.0     |
| 12.5            | 100.0     |
| 9.5             | 100.0     |
| 4.75            | 100.0     |
| 2.36            | 99.8      |
| 2.00            | 99.7      |
| 1.18            | 99.6      |
| 0.600           | 99.5      |
| 0.300           | 99.3      |
| 0.150           | 98.9      |
| 0.075           | 96.1      |
| 0.005           | 42.9      |
| 0.002           | 37.3      |
| 0.001           | 33.0      |

| Gravel | Sand   |        |      | Silt | Clay | Colloids |
|--------|--------|--------|------|------|------|----------|
|        | Coarse | Medium | Fine |      |      |          |
| 0.0    | 0.3    | 0.3    | 3.3  | 58.8 | 37.3 | 33.0     |

COMMENTS  
 No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D7928 - PARTICLE-SIZE DISTRIBUTION OF FINE-GRAINED SOILS USING THE SEDIMENTATION ANALYSIS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 2P1

PROJECT 2025 Local Street Renewal Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 8

DATE SAMPLED: 2025.Jan.09

DATE RECEIVED: 2025.Jan.09

DATE TESTED: 2025.Jan.27

SAMPLED BY: Stantec Consulting Ltd.


SUBMITTED BY: Stantec Consulting Ltd.

TESTED BY: Rimanshi Gorasiya

**MATERIAL IDENTIFICATION**

CLIENT FIELD ID BH-241. 0.8 m, Simpson Ave.

STANTEC SAMPLE NO. 5632



| Sieve Size (mm) | % Passing |
|-----------------|-----------|
| 50.0            | 100.0     |
| 40.0            | 100.0     |
| 25.0            | 100.0     |
| 20.0            | 100.0     |
| 16.0            | 100.0     |
| 12.5            | 100.0     |
| 9.5             | 100.0     |
| 4.75            | 100.0     |
| 2.36            | 100.0     |
| 2.00            | 100.0     |
| 1.18            | 100.0     |
| 0.600           | 100.0     |
| 0.300           | 99.8      |
| 0.150           | 99.6      |
| 0.075           | 99.2      |
| 0.005           | 81.3      |
| 0.002           | 81.2      |
| 0.001           | 81.2      |

| Gravel | Sand   |        |      | Silt | Clay | Colloids |
|--------|--------|--------|------|------|------|----------|
|        | Coarse | Medium | Fine |      |      |          |
| 0.0    | 0.0    | 0.1    | 0.7  | 18.0 | 81.2 | 81.2     |

**COMMENTS**

No comments.



REPORT DATE 2025.Feb.06

REVIEWED BY Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

# PROCTOR TEST REPORT

TO City of Winnipeg  
 104 - 1155 Pacific Ave.  
 Winnipeg, MB  
 R3E 2P1


CLIENT City of Winnipeg  
 C.C.

ATTN: Geoff Kerr

PROJECT 2025 Local Street Renewal Program

PROJECT NO. 123317463-4 - Contract 4  
 PROCTOR NO. 1 DATE SAMPLED 2025.Jan.07 DATE RECEIVED 2025.Jan.07 DATE TESTED 2025.Jan.31

|                         |                              |                            |                                    |
|-------------------------|------------------------------|----------------------------|------------------------------------|
| INSITU MOISTURE         | 17.9 %                       | COMPACTION STANDARD        | Standard Proctor, ASTM             |
| TESTED BY               | Donald Eliazar               |                            | D698                               |
| MATERIAL IDENTIFICATION |                              | COMPACTION PROCEDURE       | A: 101.6mm Mold,<br>Passing 4.75mm |
| MAJOR COMPONENT         | Subgrade                     | RAMMER TYPE                | Manual                             |
| SIZE                    | Fat Clay (CH)                | PREPARATION                | Moist                              |
| DESCRIPTION             |                              | OVERSIZE CORRECTION METHOD | None                               |
| SUPPLIER                | Existing Materials           | RETAINED 4.75mm SCREEN     | N/A %                              |
| SOURCE                  | BH-234, 0.6 m (Riverton Ave) |                            |                                    |



| TRIAL NUMBER | WET DENSITY (kg/m³) | DRY DENSITY (kg/m³) | MOISTURE CONTENT (%) |
|--------------|---------------------|---------------------|----------------------|
| 1            | 1808                | 1585                | 14.1                 |
| 2            | 1886                | 1609                | 17.2                 |
| 3            | 1943                | 1619                | 20.0                 |
| 4            | 1903                | 1547                | 23.0                 |

|                    | MAXIMUM DRY DENSITY (kg/m³) | OPTIMUM MOISTURE CONTENT (%) |
|--------------------|-----------------------------|------------------------------|
| CALCULATED         | 1620                        | 19.5                         |
| OVERSIZE CORRECTED |                             |                              |

**COMMENTS**

Stantec Sample No. 5625

# PROCTOR TEST REPORT

TO City of Winnipeg  
 104 - 1155 Pacific Ave.  
 Winnipeg, MB  
 R3E 2P1


CLIENT City of Winnipeg  
 C.C.

ATTN: Geoff Kerr

PROJECT 2025 Local Street Renewal Program

PROJECT NO. 123317463-4 - Contract 4  
 PROCTOR NO. 2 DATE SAMPLED 2025.Jan.07 DATE RECEIVED 2025.Jan.07 DATE TESTED 2025.Jan.31

|                         |                              |                            |                                    |
|-------------------------|------------------------------|----------------------------|------------------------------------|
| INSITU MOISTURE         | 16.9 %                       | COMPACTION STANDARD        | Standard Proctor, ASTM             |
| TESTED BY               | Donald Eliazar               |                            | D698                               |
| MATERIAL IDENTIFICATION |                              | COMPACTION PROCEDURE       | A: 101.6mm Mold,<br>Passing 4.75mm |
| MAJOR COMPONENT         | Subgrade                     | RAMMER TYPE                | Manual                             |
| SIZE                    | Fat Clay (CH)                | PREPARATION                | Moist                              |
| DESCRIPTION             |                              | OVERSIZE CORRECTION METHOD | None                               |
| SUPPLIER                | Existing Materials           | RETAINED 4.75mm SCREEN     | N/A %                              |
| SOURCE                  | BH-235, 0.7 m (Riverton Ave) |                            |                                    |



| TRIAL NUMBER | WET DENSITY (kg/m³) | DRY DENSITY (kg/m³) | MOISTURE CONTENT (%) |
|--------------|---------------------|---------------------|----------------------|
| 1            | 1787                | 1573                | 13.6                 |
| 2            | 1896                | 1633                | 16.1                 |
| 3            | 1982                | 1657                | 19.6                 |
| 4            | 1977                | 1613                | 22.6                 |

|                    | MAXIMUM DRY DENSITY (kg/m³) | OPTIMUM MOISTURE CONTENT (%) |
|--------------------|-----------------------------|------------------------------|
| CALCULATED         | 1660                        | 19.0                         |
| OVERSIZE CORRECTED |                             |                              |

**COMMENTS**

Stantec Sample No. 5626.

# PROCTOR TEST REPORT

TO City of Winnipeg  
 104 - 1155 Pacific Ave.  
 Winnipeg, MB  
 R3E 2P1


CLIENT City of Winnipeg  
 C.C.

ATTN: Geoff Kerr

PROJECT 2025 Local Street Renewal Program

PROJECT NO. 123317463-4 - Contract 4  
 PROCTOR NO. 3 DATE SAMPLED 2025.Jan.07 DATE RECEIVED 2025.Jan.07 DATE TESTED 2025.Jan.31

|                         |                              |                            |                                    |
|-------------------------|------------------------------|----------------------------|------------------------------------|
| INSITU MOISTURE         | 15.0 %                       | COMPACTION STANDARD        | Standard Proctor, ASTM             |
| TESTED BY               | Donald Eliazar               |                            | D698                               |
| MATERIAL IDENTIFICATION |                              | COMPACTION PROCEDURE       | A: 101.6mm Mold,<br>Passing 4.75mm |
| MAJOR COMPONENT         | Subgrade                     | RAMMER TYPE                | Manual                             |
| SIZE                    | Fat Clay (CH)                | PREPARATION                | Moist                              |
| DESCRIPTION             |                              | OVERSIZE CORRECTION METHOD | None                               |
| SUPPLIER                | Existing Materials           | RETAINED 4.75mm SCREEN     | N/A %                              |
| SOURCE                  | BH-236, 0.6 m (Riverton Ave) |                            |                                    |



| TRIAL NUMBER | WET DENSITY (kg/m³) | DRY DENSITY (kg/m³) | MOISTURE CONTENT (%) |
|--------------|---------------------|---------------------|----------------------|
| 1            | 1700                | 1502                | 13.2                 |
| 2            | 1810                | 1543                | 17.3                 |
| 3            | 1913                | 1573                | 21.6                 |
| 4            | 1919                | 1529                | 25.5                 |

|                    | MAXIMUM DRY DENSITY (kg/m³) | OPTIMUM MOISTURE CONTENT (%) |
|--------------------|-----------------------------|------------------------------|
| CALCULATED         | 1570                        | 21.5                         |
| OVERSIZE CORRECTED |                             |                              |

**COMMENTS**

Stantec Sample No. 5627.

# PROCTOR TEST REPORT

TO City of Winnipeg  
 104 - 1155 Pacific Ave.  
 Winnipeg, MB  
 R3E 2P1


CLIENT City of Winnipeg  
 C.C.

ATTN: Geoff Kerr

PROJECT 2025 Local Street Renewal Program

PROJECT NO. 123317463-4 - Contract 4  
 PROCTOR NO. 4 DATE SAMPLED 2025.Jan.07 DATE RECEIVED 2025.Jan.07 DATE TESTED 2025.Jan.31

|                         |                             |                            |                                    |
|-------------------------|-----------------------------|----------------------------|------------------------------------|
| INSITU MOISTURE         | 20.5 %                      | COMPACTION STANDARD        | Standard Proctor, ASTM             |
| TESTED BY               | Doanld Eliazar              |                            | D698                               |
| MATERIAL IDENTIFICATION |                             | COMPACTION PROCEDURE       | A: 101.6mm Mold,<br>Passing 4.75mm |
| MAJOR COMPONENT         | Subgrade                    | RAMMER TYPE                | Manual                             |
| SIZE                    | Fat Clay (CH)               | PREPARATION                | Moist                              |
| DESCRIPTION             |                             | OVERSIZE CORRECTION METHOD | None                               |
| SUPPLIER                | Existing Materials          | RETAINED 4.75mm SCREEN     | N/A %                              |
| SOURCE                  | BH-237, 0.8 m (Simpson Ave) |                            |                                    |



| TRIAL NUMBER | WET DENSITY (kg/m³) | DRY DENSITY (kg/m³) | MOISTURE CONTENT (%) |
|--------------|---------------------|---------------------|----------------------|
| 1            | 1702                | 1570                | 8.4                  |
| 2            | 1798                | 1597                | 12.6                 |
| 3            | 1930                | 1657                | 16.5                 |
| 4            | 1970                | 1632                | 20.7                 |

|                    | MAXIMUM DRY DENSITY (kg/m³) | OPTIMUM MOISTURE CONTENT (%) |
|--------------------|-----------------------------|------------------------------|
| CALCULATED         | 1660                        | 18.0                         |
| OVERSIZE CORRECTED |                             |                              |

**COMMENTS**

Stantec Sample No. 5628.

# PROCTOR TEST REPORT

TO City of Winnipeg  
 104 - 1155 Pacific Ave.  
 Winnipeg, MB  
 R3E 2P1


CLIENT City of Winnipeg  
 C.C.

ATTN: Geoff Kerr

PROJECT 2025 Local Street Renewal Program

PROJECT NO. 123317463-4 - Contract 4  
 PROCTOR NO. 5 DATE SAMPLED 2024.Jan.09 DATE RECEIVED 2024.Jan.09 DATE TESTED 2024.Feb.05

|                         |                             |                            |                                    |
|-------------------------|-----------------------------|----------------------------|------------------------------------|
| INSITU MOISTURE         | 23.7 %                      | COMPACTION STANDARD        | Standard Proctor, ASTM             |
| TESTED BY               | Donald Eliazar              |                            | D698                               |
| MATERIAL IDENTIFICATION |                             | COMPACTION PROCEDURE       | A: 101.6mm Mold,<br>Passing 4.75mm |
| MAJOR COMPONENT         | Subgrade                    | RAMMER TYPE                | Manual                             |
| SIZE                    | Lean Clay (CL)              | PREPARATION                | Moist                              |
| DESCRIPTION             |                             | OVERSIZE CORRECTION METHOD | None                               |
| SUPPLIER                | Existing Materials          | RETAINED 4.75mm SCREEN     | N/A %                              |
| SOURCE                  | BH-238, 0.8 m (Simpson Ave) |                            |                                    |



| TRIAL NUMBER | WET DENSITY (kg/m³) | DRY DENSITY (kg/m³) | MOISTURE CONTENT (%) |
|--------------|---------------------|---------------------|----------------------|
| 1            | 1765                | 1555                | 13.5                 |
| 2            | 1845                | 1572                | 17.4                 |
| 3            | 1913                | 1571                | 21.8                 |
| 4            | 1934                | 1540                | 25.6                 |

|                    | MAXIMUM DRY DENSITY (kg/m³) | OPTIMUM MOISTURE CONTENT (%) |
|--------------------|-----------------------------|------------------------------|
| CALCULATED         | 1580                        | 19.5                         |
| OVERSIZE CORRECTED |                             |                              |

COMMENTS  
 Stantec Sample No. 5629.

# PROCTOR TEST REPORT

TO City of Winnipeg  
 104 - 1155 Pacific Ave.  
 Winnipeg, MB  
 R3E 2P1


CLIENT City of Winnipeg  
 C.C.

ATTN: Geoff Kerr

PROJECT 2025 Local Street Renewal Program

PROJECT NO. 123317463-4 - Contract 4  
 PROCTOR NO. 6 DATE SAMPLED 2025.Jan.09 DATE RECEIVED 2025.Jan.09 DATE TESTED 2025.Feb.05

|                         |                             |                            |                                    |
|-------------------------|-----------------------------|----------------------------|------------------------------------|
| INSITU MOISTURE         | 20.4 %                      | COMPACTION STANDARD        | Standard Proctor, ASTM             |
| TESTED BY               | Donald Eliazar              |                            | D698                               |
| MATERIAL IDENTIFICATION |                             | COMPACTION PROCEDURE       | A: 101.6mm Mold,<br>Passing 4.75mm |
| MAJOR COMPONENT         | Subgrade                    | RAMMER TYPE                | Manual                             |
| SIZE                    | Lean Clay (CL)              | PREPARATION                | Moist                              |
| DESCRIPTION             |                             | OVERSIZE CORRECTION METHOD | None                               |
| SUPPLIER                | Existing Materials          | RETAINED 4.75mm SCREEN     | N/A %                              |
| SOURCE                  | BH-239, 0.8 m (Simpson Ave) |                            |                                    |



| TRIAL NUMBER | WET DENSITY (kg/m³) | DRY DENSITY (kg/m³) | MOISTURE CONTENT (%) |
|--------------|---------------------|---------------------|----------------------|
| 1            | 1648                | 1462                | 12.7                 |
| 2            | 1747                | 1493                | 17.0                 |
| 3            | 1838                | 1514                | 21.4                 |
| 4            | 1880                | 1498                | 25.5                 |

|                    | MAXIMUM DRY DENSITY (kg/m³) | OPTIMUM MOISTURE CONTENT (%) |
|--------------------|-----------------------------|------------------------------|
| CALCULATED         | 1510                        | 22.0                         |
| OVERSIZE CORRECTED |                             |                              |

**COMMENTS**

Stantec Sample No. 5630.



# PROCTOR TEST REPORT

TO City of Winnipeg  
 104 - 1155 Pacific Ave.  
 Winnipeg, MB  
 R3E 2P1


CLIENT City of Winnipeg  
 C.C.

ATTN: Geoff Kerr

PROJECT 2025 Local Street Renewal Program

PROJECT NO. 123317463-4 - Contract 4  
 PROCTOR NO. 7 DATE SAMPLED 2025.Jan.09 DATE RECEIVED 2025.Jan.09 DATE TESTED 2025.Feb.05

|                         |                             |                            |                                    |
|-------------------------|-----------------------------|----------------------------|------------------------------------|
| INSITU MOISTURE         | 18.6 %                      | COMPACTION STANDARD        | Standard Proctor, ASTM             |
| TESTED BY               | Donald Eliazar              |                            | D698                               |
| MATERIAL IDENTIFICATION |                             | COMPACTION PROCEDURE       | A: 101.6mm Mold,<br>Passing 4.75mm |
| MAJOR COMPONENT         | Subgrade                    | RAMMER TYPE                | Manual                             |
| SIZE                    | Lean Clay (CL)              | PREPARATION                | Moist                              |
| DESCRIPTION             |                             | OVERSIZE CORRECTION METHOD | None                               |
| SUPPLIER                | Existing Materials          | RETAINED 4.75mm SCREEN     | N/A %                              |
| SOURCE                  | BH-240, 0.8 m (Simpson Ave) |                            |                                    |



| TRIAL NUMBER | WET DENSITY (kg/m³) | DRY DENSITY (kg/m³) | MOISTURE CONTENT (%) |
|--------------|---------------------|---------------------|----------------------|
| 1            | 1810                | 1637                | 10.6                 |
| 2            | 1924                | 1694                | 13.6                 |
| 3            | 2021                | 1733                | 16.6                 |
| 4            | 2041                | 1708                | 19.5                 |

|                    | MAXIMUM DRY DENSITY (kg/m³) | OPTIMUM MOISTURE CONTENT (%) |
|--------------------|-----------------------------|------------------------------|
| CALCULATED         | 1730                        | 17.0                         |
| OVERSIZE CORRECTED |                             |                              |

**COMMENTS**

Stantec Sample No. 5631.

# PROCTOR TEST REPORT

TO City of Winnipeg  
 104 - 1155 Pacific Ave.  
 Winnipeg, MB  
 R3E 2P1


CLIENT City of Winnipeg  
 C.C.

ATTN: Geoff Kerr

PROJECT 2025 Local Street Renewal Program

PROJECT NO. 123317463-4 - Contract 4  
 PROCTOR NO. 8 DATE SAMPLED 2025.Jan.09 DATE RECEIVED 2025.Jan.09 DATE TESTED 2025.Feb.07

|                         |                             |                            |                                    |
|-------------------------|-----------------------------|----------------------------|------------------------------------|
| INSITU MOISTURE         | 14.7 %                      | COMPACTION STANDARD        | Standard Proctor, ASTM             |
| TESTED BY               | Donald Eliazar              |                            | D698                               |
| MATERIAL IDENTIFICATION |                             | COMPACTION PROCEDURE       | A: 101.6mm Mold,<br>Passing 4.75mm |
| MAJOR COMPONENT         | Subgrade                    | RAMMER TYPE                | Manual                             |
| SIZE                    | Fat Clay (CH)               | PREPARATION                | Moist                              |
| DESCRIPTION             |                             | OVERSIZE CORRECTION METHOD | None                               |
| SUPPLIER                | Existing Materials          | RETAINED 4.75mm SCREEN     | N/A %                              |
| SOURCE                  | BH-241, 0.8 m (Simpson Ave) |                            |                                    |



| TRIAL NUMBER | WET DENSITY (kg/m³) | DRY DENSITY (kg/m³) | MOISTURE CONTENT (%) |
|--------------|---------------------|---------------------|----------------------|
| 1            | 1816                | 1610                | 12.8                 |
| 2            | 1920                | 1645                | 16.7                 |
| 3            | 1988                | 1648                | 20.6                 |
| 4            | 1967                | 1572                | 25.1                 |

|                    | MAXIMUM DRY DENSITY (kg/m³) | OPTIMUM MOISTURE CONTENT (%) |
|--------------------|-----------------------------|------------------------------|
| CALCULATED         | 1650                        | 19.0                         |
| OVERSIZE CORRECTED |                             |                              |

**COMMENTS**

Stantec Sample No. 5632.

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2025 Local Street Renewals Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 1

DATE SAMPLED: 2025.Jan.09  
 SAMPLED BY: Larry Presado


DATE RECEIVED: 2025.Jan.09  
 SUBMITTED BY: Larry Presado

DATE TESTED: 2025.Feb.04  
 TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

|                   |                |                    |                               |
|-------------------|----------------|--------------------|-------------------------------|
| MATERIAL USE      | Subgrade       | SUPPLIER           | Existing Material             |
| MAX. NOMINAL SIZE | < 4.75 mm      | SOURCE             | In Situ                       |
| MATERIAL TYPE     | Fat Clay (CH)  | SAMPLE LOCATION    | BH-234, 0.6 m - Riverton Ave. |
| SPECIFICATION ID  | Not Applicable | STANTEC SAMPLE NO. | 5625                          |

|                     |           |                           |                        |
|---------------------|-----------|---------------------------|------------------------|
| IMMERSION PERIOD    | 96 ± 2 hr | TARGET MAX. DRY DENSITY   | 1620 kg/m <sup>3</sup> |
| CONDITION OF SAMPLE | Soaked    | TARGET OPTIMUM MOISTURE   | 19.5 %                 |
| SURCHARGE MASS      | 4.54 kg   |                           |                        |
| +19 mm OVERSIZE     | 0 %       | AS-COMPACTED DRY DENSITY  | 1541 kg/m <sup>3</sup> |
| SWELL OF SAMPLE     | 3.87 %    | AS-COMPACTED MOISTURE     | 19.4 %                 |
| POST-TEST MOISTURE  | 28.9 %    | AS-COMPACTED % COMPACTION | 95 %                   |




**CBR VALUE AT 2.54 mm PENETRATION**  
2.2

**CBR VALUE AT 5.08 mm PENETRATION**  
2.3

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.  
 As per ASTM D1883 10.2, the sample should be re-run to confirm the higher CBR value at 5.08 mm.

REPORT DATE 2025.Feb.10

REVIEWED BY   
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2025 Local Street Renewals Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 2

DATE SAMPLED: 2025.Jan.09  
 SAMPLED BY: Larry Presado


DATE RECEIVED: 2025.Jan.09  
 SUBMITTED BY: Larry Presado

DATE TESTED: 2025.Feb.04  
 TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

|                   |                |                    |                               |
|-------------------|----------------|--------------------|-------------------------------|
| MATERIAL USE      | Subgrade       | SUPPLIER           | Existing Material             |
| MAX. NOMINAL SIZE | < 4.75 mm      | SOURCE             | In Situ                       |
| MATERIAL TYPE     | Fat Clay (CH)  | SAMPLE LOCATION    | BH-235, 0.7 m - Riverton Ave. |
| SPECIFICATION ID  | Not Applicable | STANTEC SAMPLE NO. | 5626                          |

|                     |           |                           |                        |
|---------------------|-----------|---------------------------|------------------------|
| IMMERSION PERIOD    | 96 ± 2 hr | TARGET MAX. DRY DENSITY   | 1660 kg/m <sup>3</sup> |
| CONDITION OF SAMPLE | Soaked    | TARGET OPTIMUM MOISTURE   | 19.0 %                 |
| SURCHARGE MASS      | 4.54 kg   |                           |                        |
| +19 mm OVERSIZE     | 0 %       | AS-COMPACTED DRY DENSITY  | 1577 kg/m <sup>3</sup> |
| SWELL OF SAMPLE     | 2.86 %    | AS-COMPACTED MOISTURE     | 19.0 %                 |
| POST-TEST MOISTURE  | 24.1 %    | AS-COMPACTED % COMPACTION | 95 %                   |




**CBR VALUE AT 2.54 mm  
PENETRATION**  
3.8

**CBR VALUE AT 5.08 mm  
PENETRATION**  
3.4

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2025.Feb.10

REVIEWED BY   
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2025 Local Street Renewals Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 3

DATE SAMPLED: 2025.Jan.09  
 SAMPLED BY: Larry Presado


DATE RECEIVED: 2025.Jan.09  
 SUBMITTED BY: Larry Presado

DATE TESTED: 2025.Feb.04  
 TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

|                   |                |                    |                               |
|-------------------|----------------|--------------------|-------------------------------|
| MATERIAL USE      | Subgrade       | SUPPLIER           | Existing Material             |
| MAX. NOMINAL SIZE | < 4.75 mm      | SOURCE             | In Situ                       |
| MATERIAL TYPE     | Fat Clay (CH)  | SAMPLE LOCATION    | BH-236, 0.6 m - Riverton Ave. |
| SPECIFICATION ID  | Not Applicable | STANTEC SAMPLE NO. | 5627                          |

|                     |           |                           |                        |
|---------------------|-----------|---------------------------|------------------------|
| IMMERSION PERIOD    | 96 ± 2 hr | TARGET MAX. DRY DENSITY   | 1570 kg/m <sup>3</sup> |
| CONDITION OF SAMPLE | Soaked    | TARGET OPTIMUM MOISTURE   | 21.5 %                 |
| SURCHARGE MASS      | 4.54 kg   |                           |                        |
| +19 mm OVERSIZE     | 0 %       | AS-COMPACTED DRY DENSITY  | 1490 kg/m <sup>3</sup> |
| SWELL OF SAMPLE     | 4.40 %    | AS-COMPACTED MOISTURE     | 21.6 %                 |
| POST-TEST MOISTURE  | 30.8 %    | AS-COMPACTED % COMPACTION | 95 %                   |




**CBR VALUE AT 2.54 mm  
PENETRATION**  
2.3

**CBR VALUE AT 5.08 mm  
PENETRATION**  
2.1

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2025.Feb.10

REVIEWED BY   
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2025 Local Street Renewals Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 4


DATE SAMPLED: 2025.Jan.09  
 SAMPLED BY: Larry Presado

DATE RECEIVED: 2025.Jan.09  
 SUBMITTED BY: Larry Presado

DATE TESTED: 2025.Feb.11  
 TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

|                     |                |                           |                              |
|---------------------|----------------|---------------------------|------------------------------|
| MATERIAL USE        | Subgrade       | SUPPLIER                  | Existing Material            |
| MAX. NOMINAL SIZE   | < 4.75 mm      | SOURCE                    | In Situ                      |
| MATERIAL TYPE       | Fat Clay (CH)  | SAMPLE LOCATION           | BH-237, 0.8 m - Simpson Ave. |
| SPECIFICATION ID    | Not Applicable | STANTEC SAMPLE NO.        | 5628                         |
| IMMERSION PERIOD    | 96 ± 2 hr      | TARGET MAX. DRY DENSITY   | 1660 kg/m <sup>3</sup>       |
| CONDITION OF SAMPLE | Soaked         | TARGET OPTIMUM MOISTURE   | 18.0 %                       |
| SURCHARGE MASS      | 4.54 kg        |                           |                              |
| +19 mm OVERSIZE     | 0 %            | AS-COMPACTED DRY DENSITY  | 1575 kg/m <sup>3</sup>       |
| SWELL OF SAMPLE     | 3.83 %         | AS-COMPACTED MOISTURE     | 18.1 %                       |
| POST-TEST MOISTURE  | 25.1 %         | AS-COMPACTED % COMPACTION | 95 %                         |




**CBR VALUE AT 2.54 mm  
PENETRATION**  
1.8

**CBR VALUE AT 5.08 mm  
PENETRATION**  
1.7

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2025.Feb.18

REVIEWED BY   
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2025 Local Street Renewals Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 5


DATE SAMPLED: 2025.Jan.09  
 SAMPLED BY: Larry Presado

DATE RECEIVED: 2025.Jan.09  
 SUBMITTED BY: Larry Presado

DATE TESTED: 2025.Feb.11  
 TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

|                     |                |                           |                              |
|---------------------|----------------|---------------------------|------------------------------|
| MATERIAL USE        | Subgrade       | SUPPLIER                  | Existing Material            |
| MAX. NOMINAL SIZE   | < 4.75 mm      | SOURCE                    | In Situ                      |
| MATERIAL TYPE       | Lean Clay (CL) | SAMPLE LOCATION           | BH-238, 0.8 m - Simpson Ave. |
| SPECIFICATION ID    | Not Applicable | STANTEC SAMPLE NO.        | 5629                         |
| IMMERSION PERIOD    | 96 ± 2 hr      | TARGET MAX. DRY DENSITY   | 1580 kg/m <sup>3</sup>       |
| CONDITION OF SAMPLE | Soaked         | TARGET OPTIMUM MOISTURE   | 19.5 %                       |
| SURCHARGE MASS      | 4.54 kg        |                           |                              |
| +19 mm OVERSIZE     | 0 %            | AS-COMPACTED DRY DENSITY  | 1502 kg/m <sup>3</sup>       |
| SWELL OF SAMPLE     | 7.09 %         | AS-COMPACTED MOISTURE     | 19.4 %                       |
| POST-TEST MOISTURE  | 34.4 %         | AS-COMPACTED % COMPACTION | 95 %                         |




**CBR VALUE AT 2.54 mm  
PENETRATION**  
1.4

**CBR VALUE AT 5.08 mm  
PENETRATION**  
1.3

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2025.Feb.18

REVIEWED BY   
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2025 Local Street Renewals Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 6


DATE SAMPLED: 2025.Jan.09  
 SAMPLED BY: Larry Presado

DATE RECEIVED: 2025.Jan.09  
 SUBMITTED BY: Larry Presado

DATE TESTED: 2025.Feb.11  
 TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

|                     |                |                           |                              |
|---------------------|----------------|---------------------------|------------------------------|
| MATERIAL USE        | Subgrade       | SUPPLIER                  | Existing Material            |
| MAX. NOMINAL SIZE   | < 4.75 mm      | SOURCE                    | In Situ                      |
| MATERIAL TYPE       | Lean Clay (CL) | SAMPLE LOCATION           | BH-239, 0.8 m - Simpson Ave. |
| SPECIFICATION ID    | Not Applicable | STANTEC SAMPLE NO.        | 5630                         |
| IMMERSION PERIOD    | 96 ± 2 hr      | TARGET MAX. DRY DENSITY   | 1510 kg/m <sup>3</sup>       |
| CONDITION OF SAMPLE | Soaked         | TARGET OPTIMUM MOISTURE   | 22.0 %                       |
| SURCHARGE MASS      | 4.54 kg        |                           |                              |
| +19 mm OVERSIZE     | 0 %            | AS-COMPACTED DRY DENSITY  | 1434 kg/m <sup>3</sup>       |
| SWELL OF SAMPLE     | 6.40 %         | AS-COMPACTED MOISTURE     | 22.1 %                       |
| POST-TEST MOISTURE  | 37.2 %         | AS-COMPACTED % COMPACTION | 95 %                         |




**CBR VALUE AT 2.54 mm  
PENETRATION**  
1.5

**CBR VALUE AT 5.08 mm  
PENETRATION**  
1.3

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2025.Feb.18

REVIEWED BY   
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services



## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2025 Local Street Renewals Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 7


DATE SAMPLED: 2025.Jan.09  
 SAMPLED BY: Larry Presado

DATE RECEIVED: 2025.Jan.09  
 SUBMITTED BY: Larry Presado

DATE TESTED: 2025.Feb.11  
 TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

|                     |                |                           |                              |
|---------------------|----------------|---------------------------|------------------------------|
| MATERIAL USE        | Subgrade       | SUPPLIER                  | Existing Material            |
| MAX. NOMINAL SIZE   | < 4.75 mm      | SOURCE                    | In Situ                      |
| MATERIAL TYPE       | Lean Clay (CL) | SAMPLE LOCATION           | BH-240, 0.8 m - Simpson Ave. |
| SPECIFICATION ID    | Not Applicable | STANTEC SAMPLE NO.        | 5631                         |
| IMMERSION PERIOD    | 96 ± 2 hr      | TARGET MAX. DRY DENSITY   | 1730 kg/m <sup>3</sup>       |
| CONDITION OF SAMPLE | Soaked         | TARGET OPTIMUM MOISTURE   | 17.0 %                       |
| SURCHARGE MASS      | 4.54 kg        |                           |                              |
| +19 mm OVERSIZE     | 0 %            | AS-COMPACTED DRY DENSITY  | 1645 kg/m <sup>3</sup>       |
| SWELL OF SAMPLE     | 2.32 %         | AS-COMPACTED MOISTURE     | 16.9 %                       |
| POST-TEST MOISTURE  | 23.4 %         | AS-COMPACTED % COMPACTION | 95 %                         |




**CBR VALUE AT 2.54 mm PENETRATION**  
3.6

**CBR VALUE AT 5.08 mm PENETRATION**  
3.4

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2025.Feb.18

REVIEWED BY   
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

## ASTM D1883 - CALIFORNIA BEARING RATIO (CBR) OF LABORATORY-COMPACTED SOILS

TO City of Winnipeg, Public Works Dept.  
 104 - 1155 Pacific Avenue  
 Winnipeg, Manitoba  
 R3E 3P1

PROJECT 2025 Local Street Renewals Program  
 Contract 4

PROJECT NO. 123317463-4

ATTN Geoff Kerr

REPORT NO. 8

DATE SAMPLED: 2025.Jan.09  
 SAMPLED BY: Larry Presado


DATE RECEIVED: 2025.Jan.09  
 SUBMITTED BY: Larry Presado

DATE TESTED: 2025.Feb.11  
 TESTED BY: Donald Eliazar

**MATERIAL IDENTIFICATION**

|                   |                |                    |                              |
|-------------------|----------------|--------------------|------------------------------|
| MATERIAL USE      | Subgrade       | SUPPLIER           | Existing Material            |
| MAX. NOMINAL SIZE | < 4.75 mm      | SOURCE             | In Situ                      |
| MATERIAL TYPE     | Fat Clay (CH)  | SAMPLE LOCATION    | BH-241, 0.8 m - Simpson Ave. |
| SPECIFICATION ID  | Not Applicable | STANTEC SAMPLE NO. | 5632                         |

|                     |           |                           |                        |
|---------------------|-----------|---------------------------|------------------------|
| IMMERSION PERIOD    | 96 ± 2 hr | TARGET MAX. DRY DENSITY   | 1650 kg/m <sup>3</sup> |
| CONDITION OF SAMPLE | Soaked    | TARGET OPTIMUM MOISTURE   | 19.0 %                 |
| SURCHARGE MASS      | 4.54 kg   |                           |                        |
| +19 mm OVERSIZE     | 0 %       | AS-COMPACTED DRY DENSITY  | 1565 kg/m <sup>3</sup> |
| SWELL OF SAMPLE     | 1.31 %    | AS-COMPACTED MOISTURE     | 19.2 %                 |
| POST-TEST MOISTURE  | 25.2 %    | AS-COMPACTED % COMPACTION | 95 %                   |




**CBR VALUE AT 2.54 mm  
PENETRATION**  
2.8

**CBR VALUE AT 5.08 mm  
PENETRATION**  
2.1

**COMMENTS**

Sample prepared to 95% of the maximum dry density at the optimum moisture content as determined from ASTM D698.

REPORT DATE 2025.Feb.18

REVIEWED BY   
 Guillaume Beauce, P.Eng.  
 Geotechnical Engineer - Materials Testing Services

| Core No. | Street       | Diameter (mm)                                 | Length (mm) | L/D Ratio | Correction Factor | Peak Load (kN) | Compressive Strength (MPa) |           |
|----------|--------------|---|-------------|-----------|-------------------|----------------|----------------------------|-----------|
|          |              |   |             |           |                   |                | Measured                   | Corrected |
| 242      | Allan St     | 75.75   | 175.34      | 2.315     | 1.0000            | 150.56         | 33.41                      | 33.41     |
| 243      | Allan St     | 75.76   | 117.76      | 1.554     | 0.9643            | 287.47         | 63.77                      | 61.49     |
| 244      | Allan St     | 75.75   | 174.83      | 2.308     | 1.0000            | 204.03         | 45.27                      | 45.27     |
| 245      | Allan St     | 75.80   | 150.48      | 1.985     | 0.9988            | 222.13         | 49.22                      | 49.17     |
| 246      | Dunrobin Ave | 75.75   | 151.97      | 2.006     | 1.0000            | 238.37         | 52.89                      | 52.89     |
| 247      | Dunrobin Ave | 75.73   | 146.12      | 1.929     | 0.9943            | 146.38         | 32.50                      | 32.31     |
| 248      | Dunrobin Ave | <i>Crumbly/fractured core; test cancelled</i> |             |           |                   |                |                            |           |
| 249      | Dunrobin Ave | 75.73   | 148.47      | 1.961     | 0.9969            | 183.26         | 40.69                      | 40.56     |
| 250      | Hershey St   | 75.71   | 131.83      | 1.741     | 0.9793            | 266.97         | 59.30                      | 58.07     |
| 251      | Hershey St   | 75.77   | 89.11       | 1.176     | 0.9122            | 219.95         | 48.78                      | 44.50     |