



1138-2025 ADDENDUM 5

2025 SEWER RENEWALS BY CIPP LINING – CONTRACT 5

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: June 5, 2026
BY: N. Kehler
TELEPHONE NO. 431-388-5986

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Addendum 2026-03-10

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 1138-2025 Form B: Prices with 1138-2025 Addendum 5 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R3): Add Item No. 13(a).

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, June 11, 2026.

PART D – SUPPLEMENTAL CONDITIONS

Revise: D13.4 to read: The City intends to award this contract by July 10, 2026.

Revise: D17.1 to read: The Contractor shall achieve Substantial Performance within eighty-five (85) Working consecutive Working Days of the commencement of the Work as specified in D13, or by November 30, 2026, whichever comes first.

Revise: D18.1 to read: The Contractor shall achieve Total Performance within ninety-five (95) Working consecutive Working Days of the commencement of the Work as specified in D13, or by June 25, 2027.

PART E – SPECIFICATIONS

Add: E11.2(c) Pipeline Access Plan - Portage Avenue Siphon

- i. A work plan shall be provided for pipeline access and chamber modifications, if required, to facilitate liner installation at the Portage Avenue Siphon site.
- ii. Further to E11.2(a) and E11.2(b), where structural modifications to the existing siphon chamber structure are proposed, beyond removal and replacement of existing precast manhole risers, the plan shall include the following:
 - a. Drawings illustrating the proposed pipeline access Work to be completed, including excavation and shoring plans, temporary chamber modifications, demolitions, and chamber reconstruction details required to facilitate the Work.

- b. Structural design report demonstrating that the proposed chamber modifications account for both temporary construction loading and long-term loading applied to the chamber. Structural design shall include review of the existing chamber structural components to remain or to be modified by the Work, and shall consider all current applicable codes and standards.
- c. Detailed construction sequencing, methods of construction, proposed equipment to be used, temporary measures, and any other information required to fully describe the Work.
- d. The complete submission shall be prepared, signed, and sealed by a Professional Engineer experienced in structural chamber design and licensed to practice in the province of Manitoba.

Delete: 1138-2025 Addendum 4: E14.8.1(b)(xxii) Bullet

DRAWINGS

Replace: 1138-2025 _Drawing_13911-R1 with 1138-2025 _Addendum_5 Drawing 13911-R2