

116-2025 ADDENDUM 3

NEWPCC LAND DRAINAGE SYSTEM

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

ISSUED: October 20, 2025 BY: Nicholas Drabchuk TELEPHONE NO. (204) 928-8436

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 116-2025 Addendum 1 - Form B: Prices with 116-2025 Addendum 3 - Form B: Prices. The following is a summary of changes incorporated in the replacement Form B: Prices:

Form B(R2): C.1.a) Description "900 mm C76-IV RCP (Pond Outlet to MH9)"

Form B(R2): C.1.b) Description "900 mm C76-IV RCP or SDR-35 PVC (MH9 to CP-MH2, MH8 to MH5)"

Form B(R2): C.1.c) Description "900 mm C76-IV RCP or SDR-35 PVC (MH5 to MH3)"

Form B(R2): C.1.d) Description "900 mm C76-IV RCP or SDR-35 PVC (CP-MH1 to MH8)"

Form B(R2): C.1.d) i) revised Description "Open cut or Trenchless installation, Class B sand bedding,

Class 4 backfill (Open Cut installation) or Class 5 backfill (Trenchless installation), 6-8 m

depth (Before removal of CPT ROW Stockpiles)"

Form B(R2): C.1.e) Description "900 mm C76-V RCP or SDR-35 PVC (MH3 to MH2, MH1 to JB

Connection)"

Form B(R2): C.1.f) i) revised Approximate Quantity 81.5

Form B(R2): D.3.a) i) revised Approximate Quantity 916.0

Form B(R2): D.3.a) ii) Description "1050 mm (PROVISIONAL)"

Form B(R2): D.3.a) ii) revised Approximate Quantity 55.0

Form B(R2): D.3.a) iii) revised Approximate Quantity 306.0

Form B(R2): D.3.a) iv) revised Approximate Quantity 81.5

Form B(R2): D.4.a) Description "1050 mm C76-V RCP (PROVISIONAL)"

PART D - SUPPLEMENTAL CONDITIONS

Revise: D21.3 to read: The Contractor shall not commence the Work on the Site before **December 15, 2025**.

Revise: D21.4 to read: The City intends to award this Contract by **December 4, 2025**.

PART E - SPECIFICATIONS

Add: E26.9 (c) Any temporary or permanent relocation of existing utilities, and or temporary support of

existing utilities required for excavations will be considered incidental to the utility being

installed. No separate payment will be made.

Revise: E30.4.2 (e): Supply and installation of 1050 mm land drainage sewer pipe, including the 1050

connection to MH-11;

DRAWINGS

Replace: 116-2025 Drawing C201-R0 with 116-2025 Addendum 3 Drawing C201-R1

QUESTIONS AND ANSWERS

Q1: What is quantity of the "Existing Topsoil Stockpile"?

A1: Approximately 5160 m³ based on a July 2025 survey, note this is an estimate provided for the Contractors information only, no warranties or guarantees are made on the available quantity at the time of the Work.

Q2: MH-11 has a 1050 connection. Does this get installed regardless of the provisional "1050 CPKC Rail Crossing" getting awarded?

A2: The 1050 connection to MH-11 is provisional based on CPKC approval of the crossing application. If MH-11 is in production or installed prior to CPKC approval of the 1050 Rail Crossing then MH-11 shall not have a 1050 rough opening.