



# 152-2025 ADDENDUM 02

## CIVIC TREE NURSERY SITE DRAINAGE IMPROVEMENTS

### URGENT

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL**

ISSUED: February 19, 2025  
BY: Jori Pincock  
TELEPHONE NO. 431-371-1747

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

### MERX POSTING CLARIFICATION

This bid opportunity was erroneously numbered 152-2024 on MERX. The bid opportunity documents have the correct number as 152-2025.

### PART B – BIDDING PROCEDURES

- Revise: B2.1 to read: The Submission Deadline is 4:00 p.m. Winnipeg time, February **26**, 2025.
- Add: B3.1.1: A second optional Site meeting will be held at 10:00 am on February 24, 2025 to provide Bidders access to the Site.

### PART D – SUPPLEMENTAL CONDITIONS

- Delete: D28.3

### PART E – SPECIFICATIONS

- Add: E12.2 (b) Refer to drawing L-001 for existing culvert diameter. The existing culvert length is approximately 9m. The required length for the replacement culvert shall be verified on site by the Contractor.
- Revise: E13.1(a)(i) to read: Installation of Granular C limestone base course material on the gravel roadway.
- Add: E13.2 (b) The Contractor is responsible to legally dispose of any removed material off site.

Revise E13.3 to read:

Limestone Surfacing

- (a) Add Granular C limestone base course material from a City of Winnipeg approved supplier to the areas and to the proposed grades noted on Drawing L-003 R1 Development and Grading Plan.
- (b) Granular C limestone base course material shall be sourced from a City of Winnipeg Approved Aggregate Supplier. The list of supplier can be found at [https://legacy.winnipeg.ca/finance/findata/matmgt/std\\_const\\_spec/current/Docs/Approved\\_Aggregate\\_Suppliers.pdf](https://legacy.winnipeg.ca/finance/findata/matmgt/std_const_spec/current/Docs/Approved_Aggregate_Suppliers.pdf)

## **DRAWINGS**

Replace: 152-2025 \_Drawing\_L-003 with 152-2025 Drawing L003 R1

## **QUESTIONS AND ANSWERS**

- Q1: Do you have a gauge for the amount of contaminated granular that might be removed from the roadway?
- A1: Previous road renewal work was undertaken in Spring 2024. Organic material on the granular road surface is limited to that which was tracked by equipment and movement of trees throughout one season of operations.
- Q2: Is the Cash Allowance included in the Total Bid Price?
- A2: Yes, the Total Bid Price is inclusive of the Cash Allowance as indicated in Form B Prices.
- Q3: Do you have drawings or detailed locations and depths for the existing irrigation lines?
- A3: The stand pipe locations are noted on the drawings and marked on site. The existing irrigation lines do not have a tracer for locates and the depth of the lines varies. Underground irrigation line locations in the work area are generally known to location staff and they will be able to assist with marking them prior to construction. Repairs to unmarked or incorrectly marked lines may be considered under the Cash Allowance.
- Q4: Will paid quantities be determined by survey upon completion or by the tender estimates?
- A4: Existing and proposed grades are provided for Proponents to confirm the scope of work required and the Approximate Quantities listed in Form B Prices. The Approximate Quantities (tender estimates) will determine the paid quantities. Exceptions may be made for quantities of Granular C limestone base course and mulch mound removals based on volume or metric tonnage required as confirmed by supplier receipts and tipping receipts. Any exceptions will be at the discretion of the Contract Administrator and reviewed prior to the completion of associated scope of work.