

1.01 INSTALLATION AND REMOVAL

- .1 Provide temporary utilities in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.02 WATER SUPPLY

- .1 A limited amount of water from the existing building supply will be made available for construction use.
- .2 Provide, install and maintain temporary lines and connections at own expense.
- .3 The City will pay utility charges.

1.03 TEMPORARY HEATING AND VENTILATION

- .1 Maintain temperatures of minimum 10°C in areas in which construction is in progress.
- .2 During dust generating procedures within bus lift hoarding, ventilate air particulates directly to exterior.
 - .1 Continue ventilation continuously for a minimum 24-hour period after concrete slab demolition work has stopped.
 - .2 Only stop ventilation when hoarding is confirmed free of demolition dust particulates.
 - .3 Contractor to engage and pay for an independent testing agency to ensure hoarding area is free of demolition dust particulates prior to stopping ventilation.
 - .4 Provide to Contract Administrator written report confirming zero level of demolition dust particulates attained prior to stopping ventilation.
 - .5 Obtain written approval from Construction Manager to terminate ventilation procedures.
- .3 Remove hoarding in a careful manner so as not to recharge the interior environment with demolition dust particulates.

1.04 TEMPORARY POWER AND LIGHT

- .1 A construction panel can be tied into PNL-RD or PNL-BB. Other panels may be available. COW to coordinate on site.
- .2 Provide and maintain temporary lighting throughout project. Ensure level of illumination in the work area is not less than 162 lx.

1.05 TEMPORARY COMMUNICATIONS FACILITIES

- .1 Provide and pay for temporary telephone fax and internet hook up, lines and equipment necessary for own use and use of Contract Administrator.

1.06 FIRE PROTECTION

- .1 Provide and maintain adequate temporary fire protection equipment during performance of Work, as required by insurance companies having jurisdiction and governing Codes, regulations and By-Laws.
- .2 Burning rubbish and construction waste materials is not permitted on site.

END OF SECTION