





PARTIAL FLOOR PLAN - POWER AND SYSTEMS - DEMOLITION

GENERAL NOTES:

1. DISCONNECT AND REMOVE EXISTING RECEPTACLE. REMOVE WIRE AND CONDUIT BACK TO SOURCE.

KEY NOTES:

- CEILING FAN TO BE REMOVED BY MECHANICAL. ELECTRICAL CONTRACTOR TO REMOVE POWER, WIRE, CONDUIT, ETC. BACK TO SOURCE.
- 2 EXISTING EXHAUST FAN TO BE REMOVED BY MECHANICAL. ELECTRICAL CONTRACTOR TO REMOVE POWER, WIRE, CONDUIT, ETC. BACK TO SOURCE.
- 3 EXISTING EXHAUST HOOD TO BE REMOVED BY MECHANICAL. ELECTRICAL CONTRACTOR TO REMOVE POWER, WIRE, CONDUIT, ETC. BACK TO SOURCE.
- 4 EXISTING HOT WATER TANK TO BE REMOVED BY MECHANICAL. ELECTRICAL CONTRACTOR TO REMOVE POWER, WIRE, CONDUIT, ETC. BACK TO SOURCE.
- (5) EXISTING PANEL TO REMAIN.
- (6) EXISTING CONTROL PANELS, PUSH BUTTONS AND EXHAUST SWITCHES SERVING PAINT BOOTHS TO REMAIN.
- 7 DISCONNECT AND REMOVE EXISTING SPEAKER. REMOVE ALL ASSOCIATED WIRING.
- (8) EXISTING DEVICES LOCATED ON WALL TO REMAIN.



Stantec Consulting Ltd.
Suite 500, 311 Portage Avenue
Winnipeg MB Canada R3B 2B9
Tel. 204.489.5900 Fax. 204.453.9012
www.stantec.com

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.

The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorized by Stantec is forbidden.

Consultants

Legend

Revision	Ву	Appd.	YY.MM.DD
ISSUED FOR CONSTRUCTION ISSUED	 СВ Ву	AA Appd.	25.06.04 YY.MM.DD
File Name:	 	 	YY.MM.DD

Permit-Seal



ENGINEERS
GEOSCIENTISTS
MANITOBA

Certificate of Authorization Stantec Consulting Ltd. No. 1301

Client/Project

WINNIPEG TRANSIT MAINTENANCE FACILITY OFFICE REDEVELOPMENT

421 OSBORNE ST. SOUTH, WINNIPEG, MB

Title

PARTIAL FLOOR PLAN - POWER AND SYSTEMS - DEMOLITION

115421006	1/8"=1'-0"	
Drawing No.	Sheet	Revision
E-103	5 of 18	0