

- 2. CONSTRUCT NEW (+/- 50mm) MS1 ASPHALT OVERLAY (E16) 3. REMOVE EXISTING CONCRETE PAVEMENT AND CONSTRUCT NEW 150mm
- REINFORCED CONCRETE PAVEMENT
- 4. INSTALL TYPE B PAVEMENT REPAIR FABRIC (CW3140, E18)
- 5. CONSTRUCT NEW 100mm CONCRETE SIDEWALK (SD-228A) 6. RENEW EXISTING 100mm CONCRETE SIDEWALK (SD-228A)
- 7. CONSTRUCT NEW CURB RAMP (SD-229D)
- 8. CONSTRUCT NEW MODIFIED BARRIER CURB (SD-203B)
- 9. INSTALL NEW DETECTABLE WARNING SURFACE TILE (SD-229E)
- 10. INSTALL NEW CATCH PIT WITH BARRIER CURB AND GUTTER INLET FRAME (SD-023, AP-011, AP-012), AND CONNECT TO EXISTING CATCH BASIN WITH 250mm Ø PVC PIPE AS PER CW 2130
- 11. ABANDON EXISTING DRAINAGE INLET AS PER CW2130
- 12. RENEW EXISTING CURB RAMP (SD-229D)
- 13. RENEW EXISTING BARRIER CURB (SD-205) 14. RENEW EXISTING BARRIER CURB AND GUTTER (SD-200)
- 15. RENEW EXISTING CURB RAMP AND GUTTER (SD-200, SD-229C)
- 16. REMOVE EXISTING ASPHALT OVERLAY 17. ADJUST FRAME TO GRADE
- 18. LIMIT OF ASPHALT OVERLAY
- 19. PLANE 40mm OF EXISTING CONCRETE PAVEMENT FOR CONCRETE HEADER
- 20. PRUNE TREES/SHRUBS AS DIRECTED BY CONTRACT ADMINISTRATOR (E12)
- 21. RENEW EXISTING 150mm REINFORCED CONCRETE SIDEWALK (SD-235)

GENERAL NOTES

- A. PAVEMENT DIMENSIONS ARE TO BACK OF CURB
- B. ALL CURB RADII UNDER 15.0m SHALL BE MODIFIED
- C. CURB REPLACEMENT AS DIRECTED BY CONTRACT ADMINISTRATOR D. CONTRACTOR TO CONFIRM THE LOCATION OF ALL UTILITIES/SERVICES IN THE
- FIELD PRIOR TO CONSTRUCTION
- E. ADJUST WATER VALVES AND CURB STOPS AS DIRECTED BY CONTRACT ADMINISTRATOR
- F. PAVEMENT REPAIRS SHOWN ARE A REPRESENTATIVE SAMPLE OF THE
- TENDER QUANTITIES G. ASPHALT TIE-INS ARE TO BE DETERMINED IN THE FIELD BY CONTRACT ADMINISTRATOR

METRIC

ISSUED FOR TENDER

TENDER NO. 2-2025

WHOLE NUMBERS INDICATE MILLIMETERS DECIMALIZED NUMBERS INDICATE METERS

Winnipeg

ENGINEER'S SEAL

SHUMKA

2025-02-25

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

McK	FN7	IF S	TR	FF

MICHENZIE STREET FROM CHURCH AVENUE TO POLSON AVENUE

FROM STA. 1+00 TO STA. 2+15

CONCRETE PAVEMENT REHABILITATION, NEW CONCRETE SIDEWALK AND ASSOCIATED WORKS

SHEET	25	OF	29

CITY DRAWING NUMBER SE-25-124

ф	HYDRANT	+		LDS/WWS	 		CONCRETE		LOCATION APPROVED
8	VALVE	•		WATERMAIN			CONCRETE SIDEWALK		UNDERGROUND STRUCTURES
Q	CURB STOP	•		GAS	— ···-		ASPHALT		SINDLINGING ON STREET ON LEG
0	MANHOLE	•		TRAFFIC SIGNALS			PAVEMENT REPAIR FABRIC		SUPR. U/G STRUCTURES DATE
	CATCH BASIN			HYDRO/STREET LIGHT			WOOD FENCE		COMMITTEE
Δ	CATCH PIT/CURB INLET	A		MTS/SHAW		EXISTING	LEGEND - PLAN	PROPOSED	NOTE:
<u>О</u> -О	HYDRO POLE	••		CURB RENEWAL					LOCATION OF UNDERGROUND STRUCTURES AS
	LIGHT STANDARD	••		PROPERTY LINE			NORTH GUTTER		SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN
\hookrightarrow	TRAFFIC SIGNAL POLE	•		RAMP CURB			CENTER LINE		THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT.
+	SURVEY BAR	+	231.000	ELEVATIONS	(231.000)		SOUTH GUTTER		CONFIRMATION OF EXISTENCE AND EXACT
	GEODETIC BENCH MARK		@	TREE					LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES
EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PROFILE	PROPOSED	BEFORE PROCEEDING WITH CONSTRUCTION.

_[ELEV	/,			ENGINEERING DIVISION TECHNOLOGY SERVICES BRANCH 106 - 1155 PACIFIC AVE			
					DESIGNED D.P. BY	CHECKED G.K., R.W., J.T.S.		
-					DRAWN D.P.	APPROVED J.T.S.		
-	2.	ISSUED FOR TENDER	2025/02/25	D.P.	HOR. SCALE: 1 : 250			
ı	1.	SUBMIT FOR PLAN APPROVAL	2025/02/05	D.P.	VERTICAL: 1:10			
	NO.	REVISIONS	DATE	BY	DATE 2025/02/25			