




1. EXISTING GIRDER ENDS HAS PREVIOUSLY BEEN TREATED WITH ACTIVATED ARC SPRAY ZINC
2. ROUGHEN EXISTING CONCRETE GIRDER ENDS AS PER ICRI GUIDELINE No. 310.2R (MEDIUM SCARIFICATION) TO 6mm AMPLITUDE WITHIN ABUTMENT AND PIER END DIAPHRAGMS.
3. ENSURE EXISTING CONCRETE IS CLEAN AND FREE OF LAITANCE PRIOR TO PLACING CONCRETE.



 THE CITY OF WINNIPEG PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION	
LAGIMODIERE TWIN OVERPASSES OVER CPKC KEEWATIN REHABILITATION AND RELATED WORKS	CITY DRAWING NUMBER B123-25-2120
	SHEET 20 OF 47
SOUTHBOUND STRUCTURE GIRDER DIAPHRAGM CONCRETE DETAILS	2120