



## 415-2025 ADDENDUM 2

### CHLORINE VENTILATION UPGRADES AT REGIONAL PUMPING STATIONS

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: June 16<sup>th</sup>, 2025  
BY: Drew Murray  
TELEPHONE NO. 204 986-2492

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

#### **PART B – BIDDING PROCEDURES**

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg Time, July 9<sup>th</sup>, 2025

Add: B3.9.1 Photos from the Site investigation can be made available upon request to the Contract Administrator identified in D6.1.

#### **PART D – SUPPLEMENTAL CONDITIONS**

Revise: D20.4 to read: The City intends to award this Contract by August 11<sup>th</sup>, 2025

Revise: D23.1(a) to read: Shop drawing review of all equipment: Prior to October 3<sup>rd</sup>, 2025.

#### **NMS SPECIFICATIONS**

Section 23 74 00 Packaged Outdoor HVAC Equipment (Toxic Chemical Scrubber Specification).

Revise: 2.8.2 to read: The chlorine absorption media must be non-hazardous both before and after chlorine absorption. The media must be non reactive to the outdoor site conditions listed in Section 02 22 10.01. The reaction heat from absorption must be below the maximum temperature the toxic chemical scrubber can operate within. Media shall be capable of removing chemical throughout the entire media bed, shall be totally non-flammable, and shall be UL Classified, Class 1.

Section 23 74 00 Packaged Outdoor HVAC Equipment (Toxic Chemical Scrubber Specification)

Add: 2.9.1.5 The toxic chemical scrubber must be capable of media sampling from each separated bed and supplied with appropriate equipment for media sampling.

#### **QUESTIONS AND ANSWERS**

Q1: Is the Work at each station going to be done in sequentially or done concurrently?

A1: The preference is for the Work at each station to be done sequentially. By doing it this way any lesson learned from the first station can be avoided in the subsequent stations and we avoid having to potentially do

re-work at all three stations. The substantial and total completion dates are reflective of the Work being done sequentially. It is understood with material lead time issues this may not be possible.

Q2: Are there going to be any nighttime shutdown work?

A2: Yes, during the daytime hours (5am to 11:30pm) all three pumping stations have to be in operation (Pumps running), no exceptions. During nighttime hours (11:30pm-5:00am), one station can be shutdown. Essential panels and UPS panels that have to be shutdown to facilitate installation will have to be done during a nighttime shutdown. Non-essential panel shutdown may be able to be done during normal business hours.

Q3: Will construction trailers be allowed on site? Can they be powered from station power?

A3: Yes, each station has a preferred spot where contractors and potentially subcontractors may install a trailer. Power for the trailers may come from the station. Source panel shall be determined during construction.

Q4: Will the existing chlorine detection system need to remain operational during construction?

A4: Yes, the existing chlorine detection system needs to remain operational up until the new system is installed. Location of the new chlorine detection equipment will have to be located such that this can be accommodated.

Q5: Does the existing fire alarm system at Hurst need to remain operational during construction?

A5: Yes, the existing fire alarm system needs to remain operational up until the new fire alarm system is installed.

Q6: Is the Contractor responsible for removing and abating all Asbestos Containing Materials if it is not disturbed by the Work?

A6: The contractor shall be responsible for the abatement and replacement of confirmed and presumed Asbestos Containing Materials as indicated in the asbestos reports in Appendix F. Where Work may affect a limited area of confirmed or presumed asbestos and said material has not been identified as requiring abatement in the reports, the Contractor's abatement and replacement requirements shall be limited to the area disturbed by the Work only.