

ASSET_NUM	STREET	LOCATION DESCRIPTION	FLOW TYPE	WORK NAME TYPE	EST_COST	COMMENTS	DIAMETER	LENGTH
S-MA00015145	ABERDEEN AV\J	1ST MH W OF SALTER ST TO MH AT SALTER ST	CS	FULL SEGMENT LINER	\$57,375.00	FL, FC, SSL, D ~ PWD STREET RENEWAL AT DOWNSTREAM END OF SEWER IN 2020-21	300	94.9
S-MA20016393	AGNES ST	1ST MH S OF SARGENT AV TO 2ND MH S OF SARGENT AV	CS	AUGMENTED FS LINER	\$82,500.00	epr 6.4-9m and 90-93.2	375	99.1
S-MA00015355	ANDERSON AV\J	1ST MH W OF SALTER TO MH AT SALTER ST	CS	FULL SEGMENT LINER	\$56,850.00	FL, CL, CL, B ~ MAY REQUIRE AN EPR AS (TYPE 2A) AT 13.0-13.6 METRES ~ EPR NOT IN LIMITS OF ROAD WORK	300	93.5
S-MA00009119	ATLANTIC AV	1ST MH E POWERS ST TO 2ND MH E POWERS ST	CS	FULL SEGMENT LINER	\$50,250.00	PWD STREET RENEWAL IN 2021 - NEED TO LINE SEWER BEFORE DEFECTS WORSEN AND REQUIRE EPRs	300	94.6
S-MA00009144	ATLANTIC AV	2ND MH E POWERS ST TO MH @ SALTER ST	CS	FULL SEGMENT LINER	\$57,375.00	PWD STREET RENEWAL IN 2021 - NEED TO LINE SEWER BEFORE DEFECTS WORSEN AND REQUIRE EPRs	300	94.5
S-MA20014818	BALMORAL ST	5TH MH S OF ST MARYS AV TO MH AT BROADWAY AV\N.PL\	CS	AUGMENTED FS LINER	\$72,375.00	epr 15.7-18.10	300	70.7
S-MA20014851	BALMORAL ST	1ST MH S OF PORTAGE AV TO 2ND MH S OF PORTAGE AV	CS	FULL SEGMENT LINER	\$44,250.00		300	69.9
S-MA20014790	BALMORAL ST	1ST MH S OF BROADWAY TO MH AT BROADWAY	CS	FULL SEGMENT LINER	\$67,875.00	FL,CL,CX,CC,FC,BJ; Bx5, FM, CM, CC, CL, SSS	375	114.4
S-MA20016667	BALMORAL ST	MH AT QU'APPELLE AV TO 1ST MH S OF QU'APPELLE AV	CS	FULL SEGMENT LINER	\$65,775.00	FL,B,CL, IMAGES AVAIL. (Verified by A4 Reinspection Tape # 42036)	375	110.8
S-MA00012469	BANNERMAN AV	1ST MH W OF SINCLAIR ST TO MH AT SINCLAIR ST	CS	FULL SEGMENT LINER	\$20,100.00		300	27.4
S-MA00017684	BEACONSFIELD ST	1ST MH N OF LUSTED AV TO 2ND MH N OF LUSTED AV	CS	FULL SEGMENT LINER	\$24,150.00	PWD street renewal in 2021 - Need to line before defects worsen and a dig is required under new pavement	250	36.7
S-MA70054886	BORROWMAN PL	1ST MH S OF PORTAGE AV TO PLUG S OF MH70024566	CS	FULL SEGMENT LINER	\$10,125.00	SAP, SAM, HSV, FM, FL	300	4.5
S-MA00012482	CATHEDRAL AV\J	MH AT SINCLAIR ST TO 1ST MH E OF SINCLAIR ST	CS	FULL SEGMENT LINER	\$58,200.00	STREETS REHABBED IN 2020 AND 2021 NEED TO LINE BEFORE DEFECTS WOSREN AND AN EPR IS NEEDED.	300	103.8
S-MA20014873	COOPER AV	MH AT OSBOURNE ST(W.PL) TO MH AT COLONY ST	CS	FULL SEGMENT LINER	\$57,862.50	Continuous FM, SSS	450	78.6
S-MA00013061	DUFFERIN AV\J	MH AT SALTER ST(WPL) TO 1ST MH E OF SALTER ST	CS	FULL SEGMENT LINER	\$63,150.00	FL, FM, B ~ PWD ROAD RENEWAL IN 2020 SHOULD LINE BEFORE DEFECTS WORSEN AND A DIG IS REQUIRED TO REPAIR	375	105.8
S-MA20014637	FURBY ST	1ST MH S OF PORTAGE AV TO 2ND MH S OF PORTAGE AV	CS	FULL SEGMENT LINER	\$62,100.00	HSV, BSV, FM, CM, SSS; PIPE IN POOR CONDITION BUT STILL HAS SHAPE	300	103.5
S-MA20016547	FURBY ST	3RD MH N OF FURBY PL TO MH AT ELLICE AV	CS	FULL SEGMENT LINER	\$52,650.00	B @ service - image available	300	85.5
S-MA20014848	GOOD ST	2ND MH S OF PORTAGE AV TO MH AT ST MARYS AV\NPL\	CS	AUGMENTED FS LINER	\$59,085.00	URGENT EPRS at 2-4m and 41.1-43.1m	300	42.8
S-MA20014805	GOOD ST	2ND MH S OF ST MARY AV TO 3RD MH S OF ST MARY AV	CS	AUGMENTED FS LINER	\$123,967.50	HSV, B, FM, OBI at 47.0m	375	131.5
S-MA00013790	LISGAR AV	2ND MH E OF AUSTIN ST TO 1ST MH E OF AUSTIN ST	CS	AUGMENTED FS LINER	\$62,100.00	EPR 34.5 - 36.9 m DS with 1 service reconnect	300	81.5
S-MA00013172	MANITOBA AV	1ST MH W OF SALTER ST TO 2ND MH W OF SALTER ST	CS	FULL SEGMENT LINER	\$51,075.00	B, H, SWS	300	82.3
S-MA20007193	MCDERMOT AVE W	1ST MH E OF KING EDWARD ST- 2ND MH E OF KING EDWARD ST	WWS	FULL SEGMENT LINER	\$58,425.00		200	96.1
S-MA20016714	MCGEE ST	3RD MH S OF WELLINGTON AV TO 4TH MH S OF WELLINGTON AV	CS	AUGMENTED FS LINER	\$77,025.00	EPR at 9-15.4m and 91.8-94.8m	300	94.9
S-MA20014439	MCGEE ST,(W.LEG)	1ST MH S.OF ST.MATTHEWS AV. TO MH AT ST.MATTHEWS AV.	CS	AUGMENTED FS LINER	\$65,385.00	epr from 65.5-67.5	300	78.4
S-MA20016557	MCMICKEN ST	1ST MH S OF ELLICE AV TO MH AT ELLICE AV	CS	FULL SEGMENT LINER	\$55,800.00	FC, B @ service - images available; HSV, BSV, JSM, FM, FC, FL, CM, CL, SSS	225	92.0
S-MA20016794	MCMICKEN ST	1ST MH S OF SARGENT AV TO MH AT SARGENT AV	CS	AUGMENTED FS LINER	\$80,130.00	epr 0-4m	225	103.6
S-MA20014908	MEMORIAL BV\W.OF CL\	1ST MH N OF YORK AV TO MH AT YORK AV\N.PL\	CS	FULL SEGMENT LINER	\$40,050.00	Bx2, FM, FL, CM, CC, SSS	375	61.2
S-MA00007450	PARK LANE AV ELEG	1ST MH N PARK LANE AV SLEG TO 2ND MH N PARK LANE	WWS	FULL SEGMENT LINER	\$66,975.00	SCP throughout pipe. SMW @ 26.5-27.5m Upstream.	250	121.5
S-MA20014617	PORTAGE AV	MH AT FURBY ST(EPL) TO 1ST MH W OF FURBY ST	CS	FULL SEGMENT LINER	\$51,075.00	BJ, CC, CL - IMAGES AVAIL. FC, FL, FM, JOM	300	82.4
S-MA20016471	PORTAGE AV\CL TO S.OF CL\	MH AT BALMORAL ST(S.LEG) TO MH AT GOOD ST	CS	AUGMENTED FS LINER	\$86,625.00	HSVx4, H, BSV, FM, FL, CC, JOMx3, SSS. More than 3 EPRs required.	300	108.7
S-MA20016754	QU'APPELLE AV	MH AT DEACON ST TO 1ST MH W OF DEACON ST	CS	AUGMENTED FS LINER	\$57,300.00	URGENT EPR 0-0.5m	300	65.5
S-MA20012155	ROSS AV	2ND MH E OF ODDY ST TO 1ST MH E OF ODDY ST	WWS	AUGMENTED FS LINER	\$57,900.00	Spalling BAD THROUGHOUT - PIPE MISSING COMPLETELY AT UPSTREAM END	200	67.6
S-MA00015339	SALTER AV	MH AT CHURCH AV TO MH AT ANDERSON AV	CS	FULL SEGMENT LINER	\$60,000.00	SAND (BACKFILL) INFILTRATING AT JOINT AT 57.7 M. ROAD RECONSTRUCTED IN 2020-21	300	99.8
S-MA20016837	SARGENT AV	MH AT FURBY ST TO MH AT MCMICKEN ST	CS	AUGMENTED FS LINER	\$63,225.00	URGENT EPR at 11.7-13.7m	300	54.9
S-MA00010935	SEKIRK AV\J	1ST E OF BATTERY ST TO MH AT BATTERY ST(WPL)	CS	FULL SEGMENT LINER	\$63,150.00	CL, CLJ, BJ, CC, w/ EPR 6.5-7.5 (H ABOVE CN) is part of the 2020 PWD contract	300	105.6
S-MA00010838	SELKIRK AV\J	1ST MH E OF SGT TOMMY PRINCE ST TO 1ST MH E OF M	CS	FULL SEGMENT LINER	\$67,350.00	B@CN, CL, FCJ, FL, H@CN, EPR 105.2-106.2 JDL ~ CHANGED TO A TYPE 2 DISCUSSIONS DETERMINED WE COULD LINE THROUGH THE	300	113.5
S-MA20017658	SHERBROOK ST	2ND MH AT PORTAGE AV TO 3RD MH N OF PORTAGE AV	CS	FULL SEGMENT LINER	\$39,000.00	HSVx2 (small), FM, FL, CC, SSS	300	59.9
S-MA20018247	SHERBROOK ST	1ST MH S OF NOTRE DAME AV TO 2ND MH S OF NOTRE DAME AV	CS	FULL SEGMENT LINER	\$42,150.00	B, FM, FC, JOM, CM, CC, CL, SSC, SSS	300	65.4
S-MA20013651	SHERBROOK ST.	1ST MH N.OF CORNISH AV. TO MH AT CORNISH AV.	CS	FULL SEGMENT LINER	\$34,800.00		300	51.8
S-MA20017152	TORONTO ST	MH AT ST MATTHEWS AV(NPL) TO 1ST MH N OF ST MATTHEWS AV	CS	FULL SEGMENT LINER	\$64,537.50	EPR @ 11.8 METRES FOR DEFECTIVE SERVICE; HSV, FL, FM, FC, FH3, JOL	300	116.9
S-MA20017441	TORONTO ST	2ND MH N OF ST MATTHEWS AV TO 3RD MH N OF ST MATTHEWS AV	CS	FULL SEGMENT LINER	\$57,900.00	HSV, B, FH4, FL, FM, FC, JSM	375	111.2
S-MA20014913	VAUGHAN ST	1ST MH N OF ST MARY AV TO 2ND MH N OF ST MARY AV	CS	FULL SEGMENT LINER	\$47,925.00	FM, CC, CL, SRI, SSS	300	76.3
S-MA20016468	VAUGHAN ST	1ST MH S OF GRAHAM AV TO MH AT GRAHAM AV	CS	FULL SEGMENT LINER	\$52,650.00	FM	375	85.4
S-MA20014369	WESTMINSTER AV	MH AT MARYLAND ST(E.PL) TO MH AT SHERBROOK ST	CS	AUGMENTED FS LINER	\$75,300.00	epr 30.2-31.2m and 88-90m	300	89.6
S-MA20011840	WILLIAM AV W	MH @ KEEWATIN ST TO 1ST MH W OF KEEWATIN ST	WWS	FULL SEGMENT LINER	\$29,550.00		200	41.4
S-MA20013677	WOLSELEY AV\N.OF CL\	2ND MH E OF MARYLAND ST TO MH AT SHERBROOK ST	CS	FULL SEGMENT LINER	\$15,900.00	0-8m FL, 12m FCJ, IMAGES AVAILABLE; JAM (H), FM, CC, SAV, SSS	300	15.5
S-MA20016559	YOUNG ST	MH AT ELLICE AV TO 4TH MH N OF PORTAGE AV	CS	AUGMENTED FS LINER	\$91,875.00	EPR 78.1-80 - urgent repair	300	122.5
S-MA70054642	YOUNG ST	4TH MH S OF CUMBERLAND AV TO MH AT SARGENT AV	CS	AUGMENTED FS LINER	\$67,020.00	EPR from 5.5-8m and 30.4-32.9m	300	65.1
S-MA70104335	YOUNG ST	3RD MH N OF PORTAGE AV TO 4TH MH N OF PORTAGE AV	CS	AUGMENTED FS LINER	\$78,930.00	FM, FC, FL, CM, CC, CL, SSS. EPR @ 49.9-52.4m and EPR @ 55.5-57.9m	300	121.7
					\$2,847,142.50			