



ABBREVIATIONS	
R	RELOCATED DEVICE
D	EXISTING DEVICE TO BE DEMOLISHED
ER	EXISTING DEVICE TO BE RELOCATED
E	EXISTING DEVICE TO REMAIN

- 1 CONFIRM THE NEW MCC (400A,600V/3PHASE/4W) IS INSTALLED ON-SITE PRIOR TO THE COMMENCEMENT OF THIS PROJECT.
- 2 CONFIRM THE NEW PANEL (225A,120/208V/3PHASE/4W) IS INSTALLED ON-SITE PRIOR TO THE COMMENCEMENT OF THIS PROJECT.
- 3 DISCONNECT AND REMOVE EXISTING WIRING AND CONDUIT ALL THE WAY BACK TO SOURCE MCC. DEMOLISH EXISTING ELECTRIC HEATING COIL
- 4 DEMOLISH EXISTING DISCONNECT SWITCH. DISCONNECT AND REMOVE EXISTING WIRING AND CONDUIT ALL THE WAY BACK TO SOURCE MCC. DEMOLISH EXISTING ELECTRIC UNIT HEATER.
- 5 DEMOLISH THE EXISTING BREAKERS OF ELECTRIC HEATER HE3. RETAIN EXISTING BREAKERS OF ELECTRIC HEATER HE1.
- 6 DEMOLISH THE EXISTING THERMOSTAT SERVING UNIT HEATER C/W ALL CABLING


THE CITY OF WINNIPEG
 WATER AND WASTE DEPARTMENT
 ENGINEERING SERVICES DIVISION

MACLEAN RESERVOIR VALVE HOUSE
VENTILATION UPGRADE
EXISTING POWER PLAN - GROUND FLOOR

CITY FILE NUMBER
W-938

SHEET **1** OF **7**

CITY DRAWING NUMBER
1-0630R-E0007-001

ENGINEER'S SEAL

CONSULTANT DRAWING NUMBER
E1.0

BID OPP: ###-20##
CONTRACT NUMBER: #

FILE PATH:
FILE NAME: