## Diamond Schmitt Architects

### INTERIOR FINISHES- CEILINGS

PROJECT NAME: South Winnipeg Recreation Campus Phase 1
PROJECT NUMBER: 220007
ISSUE DATE: 02/05/2026
REVISION DATE: Construction Documents

| ITEM | | ITEM DESCRIPTION & LOCATION | PRODUCT | SPEC SPECTION | COMMENTS |
|---|---|---|---|---|---|
| CEILING | | | | | |
| ACP1 | | ACOUSTICAL PANEL CEILING SYSTEM - SUSPENDED<br><br>Recreation: Movement Studio | MANUFACTURER: USG/USC CEILINGS<br>PRODUCT: HALTON LOOK ACOUSTICAL PANELS<br>DESCRIPTION: Mineral fiber acoustical panel, Fine textured, Impact and scratch resistant, washable and scrubbable. Grid Profile Option C, 9/ Round Edge<br>TYPICAL PANEL SIZE: 24" x 23" / 2' TIM 2112Sloot X 24Sloot X 25mm<br>SECONDARY PANEL SIZES: 24" x 48" x 2' / 2' x 48" x 2'<br>COLOUR:FLAT WHITE 050<br>SUSPENSION SYSTEM: Main and Cross Tee Suspension Grid and USG Cage Utility Channel<br>UTILITY CHANNEL: USG LOOK INTEGRATED SYSTEM<br>EDGE TRIM: USG Donn® Brand SL DXT, FLAT WHITE<br>ACOUSTICS: NRC 0.95<br>NOTE: Stabilizer Bars to be used as per manufacturer's recommendations. | 09 51 13 | USE WITH USG LOOK INTEGRATED SYSTEM UTILITY CHANNEL FOR INTEGRATED LINEAR LIGHTS. |
| ACP2 | | SPECIALTY WOOD SLAT CEILING PANEL SYSTEM<br><br>Recreation: Corridor R200;<br>Upper Lobby/Gathering R101 | MANUFACTURER: GEOMETRIX<br>PRODUCT: GEOPANEL LINEAR<br>BLADE THICKNESS: 3/4" (20mm) THK<br>BLADE WIDTH: 3" (76mm)<br>BLADES PER PNL: 2 Blades per 12" ( panel<br>PANEL SIZE: 11 1/2" X 7' 11/2"<br>WOOD SPECIES: White Oak<br>WOOD STAIN: CUSTOM STAIN PER CONTROL SAMPLE<br>FINISH: Matte Polyurethane Finish<br>BACKING: Factory attached black acoustic felt backer<br>SUSPENSION SYSTEM: Standard heavy duty 1 3/8" T-bar x 1/2" wood backer + wood blade 3/8"<br>- 2" depth. Fully accessible panels using Dennerlok Wood Tongue Clips<br>ACOUSTICS: NRC 0.65<br>FIRE TREATMENT: CLASS A<br>4<br>APPROVED EQUAL: LINEA LINEAR PLANK CEILING, WHITE OAK R6T | 09 54 26 | T-BAR AND HARDWARE SUPPLIED BY INSTALLER |
| ACP3 | | **ACOUSTIC CEILING PANEL WITH TORSION SPRING CEILING SYSTEM**<br><br>Recreation: Rec Gathering Entrance R100;<br>Lobby/Gathering R101; Reception/Control Desk R102; Family Space R113; East-West Corridor Elevator Alcove R170; | MANUFACTURER: ARMSTRONG<br>PRODUCT: METALWORKS IMAGE LINEAR<br>PANEL SIZE: 24" x 96" with 2 plants per panel<br>PLANK SIZE: 12" x 96"<br>FINISH: PAINTED ALUMINUM COAT TO MATCH EXTERIOR CLADDING<br>PERFORATION: M01 Perforation Pattern<br>JOINT STYLE: Closed joint, butt panels, 1/8" spacing between planks<br>SUSPENSION SYSTEM: Black Pinnacle<br>BACKING: Acoustic Option: Black Plenaflex<br>SUSPENSION SYSTEM: Black Prelude XL<br>ACOUSTICS: 0.70 NRC Minimum required.<br>FIRE TREATMENT: CLASS A | 09 54 23 | |
| ACP4 | | **ACOUSTIC CEILING PANEL - PERFORATED WOOD PANELLING**<br><br>Child Care Entry C100 | MANUFACTURER: GEOMETRIX<br>PRODUCT: QUESTONE 34MM<br>PANEL SIZE: 2' X 8'<br>FINISH: WOOD VENEER WITH LACQUER COATING (WOOD SPECIES - WHITE OAK)<br>JOINT STYLE: TONGUE & GROOVE, ONE OF PLANKS TO BE BUTT JOINTED<br>WOOD SPECIES: White Oak<br>BACKING: ACOUSTICALLY RATED BLACK NON-WOVEN FABRIC<br>SUSPENSION SYSTEM: HEAVY DUTY 15/16" METALLIC T-BAR GRID SYSTEM WITH #12 GAUGE HANGING WIRE, PROVIDE TONGUE & GROOVE CLIPS (ECOSCREEN)<br>ACOUSTICS: 0.70 NRC Minimum required.<br>FIRE TREATMENT: CLASS A<br>4<br>APPROVED EQUAL: LINEA R3T-TBG WHITE OAK R4T | 09 54 26 | |
| ACT1 | | **ACOUSTIC CEILING TILE IN SUSPENSION SYSTEM**<br><br>Recreation: Administrative Offices, Staff Rooms, Level 2 MPR, Wellness Room<br><br>Child Care Centre: Infant Rooms, Pre-School Rooms, Administrative Offices, Corridors | **PRODUCT OPTION A:**<br>MANUFACTURER: CertainTeed Saint-Gobain<br>PRODUCT: SYMPHONY 5 Square edge trim<br>DESCRIPTION: Mineral fiber material with acoustically transparent membrane with factory-applied latex paint.<br>SIZE: 24" x 48" x 5/8" THK (610mm X 1220mm X 15mm)<br>COLOUR: WHITE<br>SUSPENSION SYSTEM: Reveal Trim Grid, WHITE, SmartFit System for linear lights and diffusers<br>ACOUSTICS: NRC 0.55<br><br>**PRODUCT OPTION B:**<br>MANUFACTURER: Armstrong<br>PRODUCT: Public Square Up-to-edge profile<br>DESCRIPTION: Mineral fiber with Durable Washable/Antimicrobial resistance<br>SIZE: 24" x 48" x 5/8" THK (610mm X 1220mm X 15mm)<br>COLOUR: WHITE<br>SUSPENSION SYSTEM: Prelude, adjusted to suit linear lights and diffusers per pattern drawn on Reflected Ceiling Plans<br>ACOUSTICS: NRC 0.90 | 09 51 23 | |
| ACT2 | | **ACOUSTIC CEILING TILE IN SUSPENSION SYSTEM - MOISTURE RESISTANT**<br><br>Recreation: Changerooms, LTRs, Public Washrooms | MANUFACTURER: Armstrong<br>PRODUCT: Ceramaguard Fine Fissured Perforated, Square lay-in Edge Profile<br>DESCRIPTION: Mineral Fiber with Durable Washable Mineral Fiber panel with integrated linear lights<br>SIZE: 24" x 48" x 5/8" THK (610mm X 1220mm X 15mm)<br>COLOUR: WHITE<br>SUSPENSION SYSTEM: Prelude Plus XL Aluminum system(TL, adjusted to suit linear lights and diffusers<br>ACOUSTICS: NRC 0.55 | 09 51 23 | |
| ACT3 |  | **ACOUSTIC CEILING TILE IN SUSPENSION SYSTEM - HIGH CAC**<br><br>Recreation: Large MPR 1 & MPR 2 | **PRODUCT OPTION A:**<br>MANUFACTURER: CertainTeed Saint-Gobain<br>PRODUCT: CLEAR LIFE 15 SYMPHONY 5 Reveal edge trim, CAC Foil Backing<br>DESCRIPTION: Mineral fiber material with acoustically transparent membrane with factoy-applied latex paint.<br>SIZE: 24" x 48" x 7 TIM (610mm x 1220mm x 25mm), 4" x 25' x 1' TIM (102mm x 610mm x 25mm)<br>COLOUR: WHITE<br>SUSPENSION SYSTEM: Reveal Trim Grid, WHITE, SmartFit System for linear lights and diffusers<br>ACOUSTICS: NRC 0.95, TCRC range of 35-37 achieved with CAC foil backing (ordered and sold separately)<br><br>**PRODUCT OPTION B:**<br>MANUFACTURER: Armstrong<br>PRODUCT: Ultima High NRC, Regular edge profile<br>DESCRIPTION: Mineral fiber material with mold, mildew, humidity resistance<br>SIZE: 24" x 48" x 7 TIM (610mm x 1220mm x 25mm), 4" x 25' x 1' TIM (102mm x 610mm x 25mm)<br>COLOUR: WHITE<br>SUSPENSION SYSTEM: Prelude adjusted to suit linear lights and diffusers per pattern drawn on RCP;<br>ACOUSTICS: NRC 0.85, CAC 35 | 09 51 23 | |

## Diamond Schmitt Architects

### INTERIOR FINISHES- WALLS & MILLWORK

PROJECT NAME: South Winnipeg Recreation Campus Phase 1
PROJECT NUMBER: 220007
ISSUE DATE: 02/05/2026
REVISION: Construction Documents

| ITEM | | ITEM DESCRIPTION & LOCATION | PRODUCT | SPEC SPECTION | COMMENTS |
|---|---|---|---|---|---|
| WALL FINISHES + ACOUSTIC WALL PANELS | | | | | |
| ACMU1 | | ARCHITECTURAL CONCRETE MASONRY UNITS (INTERIOR)<br><br>SEE DWGS FOR LOCATION | MANUFACTURER: DAY & CAMPBELL<br>PRODUCT: MODERN MASONRY ARCHITECTURAL LINE<br>SIZE: 200mm x 200mm x 400mm (8"x8"x16")<br>SUSTAINEDBS: 90mm x 90mm x 190mm, RUNNING BOND | 04 22 23 | |
| CMU | | CONCRETE MASONRY UNITS (INTERIOR)<br>Service Rooms, Refer to Plans for Locations | | 04 22 00 | |
| TL3 |  | **PORCELAIN WALL TILE**<br><br>Recreation: Changeroom showers, Public Washrooms<br><br>Child Care Staff Washroom, LTR, Infant and Pre-School Rooms | MANUFACTURER: Centura Tile<br>PRODUCT: Rainbow Series<br>COLOUR: White Gloss<br>SIZE/THICKNESS: 100mm x 400mm, Stack Bond | 09 31 00 | |
| TL4 | | **PORCELAIN WALL TILE**<br><br>Recreation: Women's Changeroom (accent walls) | MANUFACTURER: Centura Tile<br>PRODUCT: Rainbow Series<br>COLOUR: Surya Glossy-RR<br>SIZE/THICKNESS: 100mm x 400mm, Stack Bond | 09 31 00 | |
| TL5 | | **PORCELAIN WALL TILE**<br><br>Recreation: Family Changeroom (accent walls) | MANUFACTURER: Centura Tile<br>PRODUCT: Rainbow Series<br>COLOUR: Tuscany Glossy<br>SIZE/THICKNESS: 100mm x 400mm, Stack Bond | 09 31 00 | |
| TL6 | | **PORCELAIN WALL TILE**<br><br>Recreation: Men's Changeroom (accent walls) | MANUFACTURER: Centura Tile<br>PRODUCT: Rainbow Series<br>COLOUR: Turquoise Gloss<br>SIZE/THICKNESS: 100mm x 400mm, Stack Bond | 09 31 00 | |
| TL7 | | **PORCELAIN WALL TILE**<br><br>Recreation: Accent walls: Recreation Room, MPR Living Room, Craft Room back splashes | MANUFACTURER: Stone Tile<br>PRODUCT: Marble Series<br>COLOUR: Thassos<br>SIZE/THICKNESS: 305mm x 610mm, Vertical Stack Bond | 09 31 00 | |
| TL8 |  | **PORCELAIN WALL TILE**<br><br>Alcove Wall @ Corridor R170, MPR Island Front | MANUFACTURER: Stone Tile<br>PRODUCT: CEO Dinaki Marble Finish<br>COLOUR: Bianco<br>SIZE/THICKNESS: 305mm x 610mm, Vertical Stack Bond | 09 31 00 | |
| TL9 | | **PORCELAIN WALL TILE (MIXED COLOURS)**<br>Child Care Washrooms | MANUFACTURER: Centura Tile<br>PRODUCT: Rainbow Series<br>COLOUR: Tuscany Glossy, Sage Glossy #95; Turquoise Gloss<br>SIZE/THICKNESS: 100mm x 400mm, Stack Bond Vertical | 09 31 00 | Refer to Drawings A601, A602, A603, A604 for Tile Colour Pattern |
| AWP1 | | ACOUSTIC WALL PANEL - Felt<br><br>Movement Studio | 4<br>MANUFACTURER: MASKIT GROUP<br>PRODUCT: FELT-WALL FELT<br>COLOUR: 0100, 0101<br>FINISH: Matte<br>NOTES:<br>APPROVED EQUAL: LINEA ECOFELT WITH 50MM AIR CAVITY TO MEET NRC REQUIREMENTS. COLOUR TO BE SELECTED FROM FULL COLOUR RANGE BY CONTRACT ADMINISTRATOR | 09 77 13 | |
| AWP2 | | ACOUSTIC WALL PANEL - Perforated Metal<br><br>Gymnasium Running Track | 4<br>MANUFACTURER: Performance Contracting, Inc.<br>DESCRIPTION: Perforated aluminum, 18 gauge, panel<br>FINISH: Alpha-Flex tool alternative finish "Metro Sound Black Acoustic Blanket"<br>Manufacturer: Dawn Corning & Kinetex<br>NRC: 0.80 | 09 78 13 | |
| AWP4 | | ACOUSTIC WALL PANEL - **Perforated Wood Paneling**<br><br>L MPR 1 & L Corridor R 100, Child Care Entry | MANUFACTURER: GEOMETRIX<br>PRODUCT: QUESTONE 34MM(1 3/4")<br>PANEL SIZE: 2' X 8' / 2' X 10' / 4' x 96" / 4' x 8'<br>FINISH: WOOD VENEER WITH LACQUER COATING (WOOD SPECIES - WHITE OAK)<br>JOINT STYLE: T & G, ONE OF PLANKS TO BE BUTT JOINTED<br>BACKING: ACOUSTICALLY RATED BLACK NON-WOVEN FABRIC<br>4<br>APPROVED EQUAL: LINEA R3T-TBG WHITE OAK R6T | 09 77 13 | |
| PT1 | | INTERIOR PAINT<br><br>Typical Walls, Ceilings throughout | 4<br>MANUFACTURER: BENJAMIN MOORE<br>PRODUCT: ULTRA SPEC SCUFF-X INTERIOR PAINT<br>PRODUCT CODE: KAE<br>COLOUR: TBD<br>FINISH: TBD<br>NOTES: | 09 91 00 | SURFACE MARKING RESISTANT |
| PT2 | | **INTERIOR PAINT**<br><br>Admin Areas Accent Walls (Locations TBD) | MANUFACTURER: BENJAMIN MOORE<br>PRODUCT: ULTRA SPEC SCUFF-X INTERIOR PAINT<br>PRODUCT CODE: KAE<br>COLOUR: TBD<br>FINISH: TBD<br>NOTES: | 09 91 00 | |
| PT3 | | **INTERIOR PAINT - ENAMEL SEMI-GLOSS**<br><br>Shop Applied paint for Misc metals | MANUFACTURER: TBD<br>COLOUR: TBD<br>FINISH: ENAMEL SEMI-GLOSS<br>NOTES: | 09 91 00 | All paint colours for Misc metals to be confirmed by Contract Administrator. Allow for 4 additional colours (P1-5, 6, 7, 8) |
| PT4 | | **INTERIOR PAINT**<br><br>Door Frames and Doors | MANUFACTURER: TBD<br>PRODUCT: TBD<br>PRODUCT CODE: TBD<br>COLOUR: TBD<br>FINISH: ENAMEL<br>NOTES: SHOP FINISHED DOORS AND FRAMES | 09 91 00 | |
| FLM1 | | SPECIALTY FINISH: APPLIED WINDOW FILM<br><br>Movement Studio Glazing<br>Universal Changeroom Glazing | MANUFACTURER: 3M<br>PRODUCT: CRYSTAL GLASS FRAMED<br>COLOUR: DUATED CRYSTAL FT250 150<br>SIZE/THICKNESS: 1524mm X 61.7m<br>NOTES: | 08 87 00 | |
| MIR1 |  | MIRROR<br><br>Recreation: Movement Studio; Public Washrooms, Changerooms Vanities<br><br>Child Care Staff Washroom | MANUFACTURER: FOR CONTRACTOR<br>PRODUCT: FRAMELESS GLASS<br>COLOUR: TBD<br>SIZE/THICKNESS: 6mm THK<br><br>NOTES: Exposed edges, ground and polished | 08 80 00 | |
| MIR2 | | **SANITIS/LUXURY MIRROR**<br>Child Care Staff Washroom, Infant and Pre-School Room C100<br>4 | MANUFACTURER: REFER TO SPECIFICATIONS<br>PRODUCT: FULL VERAPHANEAC DOME | 10 86 00 | |
| SS1 | | **SOLID SURFACING**<br><br>Reception Desk, Kitchen Counters, Benches, Alcove Bar Storage | MANUFACTURER: CORIAN<br>PRODUCT: SOLID SURFACE<br>COLOUR: Corian Glacier White<br>SIZE/THICKNESS: 19mm THK | 06 40 00 | |
| SS2 | | **SOLID SURFACING**<br><br>Reception Desk Accent Colour | MANUFACTURER: CORIAN<br>PRODUCT: SOLID SURFACE<br>COLOUR: TBD<br>SIZE/THICKNESS: 19mm THK | 06 40 00 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| WP1 | | **WALL PROTECTION - CHILD CARE**<br>**4 COLOURS TO BE LATER SELECTED BY CONTRACT ADMINISTRATOR**<br><br>Corridor C101, Infant and Pre-School Care Rooms | MANUFACTURER: CONSTRUCTION SPECIALTIES<br>PRODUCT: INPRO PALLADIUM RIGID SHEET<br>COLOUR: TBD<br>SIZE/THICKNESS: 1.22mm (0.047)<br>NOTES: | 10 26 13 | FINAL SUPPLIMENTARY COLOUR SELECTIONS TO BE TAKEN WPS, WP5, WP9, WP6, WP7 |
| PLAM 1 | | **PLASTIC LAMINATE**<br><br>Staff Room Kitchen, MPR Living Room and Craft Room Kitchenettes, Staff Room Storage | MANUFACTURER: WILSONART, FORMICA<br>PRODUCT:<br>COLOUR: TBD<br>FINISH: SD<br>THICKNESS: 0.8mm | 06 60 00 | |
| PLAM 2 | | **PLASTIC LAMINATE**<br><br>MPR Servery Kitchen and Island | MANUFACTURER: WILSONART, FORMICA<br>PRODUCT:<br>COLOUR: TBD<br>FINISH: SD<br>THICKNESS: 0.8mm | 06 40 00 | |
| PLAM 3 | | **PLASTIC LAMINATE**<br><br>MPR Servery Kitchen Recessed Uppers | MANUFACTURER: WILSONART, FORMICA<br>PRODUCT:<br>COLOUR: TBD<br>FINISH: SD<br>THICKNESS: 0.8mm | 06 40 00 | |
| PLAM 4 | | **PLASTIC LAMINATE**<br><br>2nd Floor Corridor Lockers | MANUFACTURER: WILSONART, FORMICA<br>PRODUCT: TBD<br>COLOUR: TBD<br>FINISH: SD<br>THICKNESS: 0.8mm | 06 40 00 | |
| PLAM 5 | | **PLASTIC LAMINATE**<br><br>Child Care Millwork | MANUFACTURER: WILSONART, FORMICA<br>PRODUCT:<br>COLOUR: TBD<br>FINISH: SD<br>THICKNESS: 0.8mm | 06 40 00 | |
| PLAM 6 | | **PLASTIC LAMINATE**<br><br>Child Care Millwork | MANUFACTURER: WILSONART, FORMICA<br>PRODUCT:<br>COLOUR: TBD<br>FINISH: SD<br>THICKNESS: 0.8mm | 06 40 00 | |

## Diamond Schmitt Architects

### INTERIOR FINISHES- FLOORS & BASE

PROJECT NAME: South Winnipeg Recreation Campus Phase 1
PROJECT NUMBER: 220007
ISSUE DATE: 02/05/2026
REVISION DATE: Construction Documents

| ITEM | | ITEM DESCRIPTION & LOCATION | PRODUCT | SPEC SPECTION | COMMENTS |
|---|---|---|---|---|---|
| FLOOR + BASE | | | | | |
| WDFL1 | | ATHLETIC HARDWOOD FLOORING SYSTEM<br><br>TRIPLE GYM | MANUFACTURER: ROBBINS<br>PRODUCT: BIO-CHANNEL STAR<br>SYSTEM TYPE: ANCHORED SPINE WITH METAL CHANNEL<br>FLOOR ASSEMBLY THICKNESS: 2-1/8" 54mm<br>SUBFLOOR CONSTRUCTION: CONTINUOUS STRIP, FACTORY PREPARED ANCHOR SLOTS<br>RESILIENCE LAYER: SCSF PROFILED ZERGUS SHOCK PAD<br>SURFACE FINISH: 25/32" 20mm CONTINUOUS STRIP, BI-MAPLE FLOORING (MPMA-F3)<br>PERIMETER BASE: Rubber vent cove 2" 150mm TYPE - BLACK<br>4<br>AcoustiCork® SCF-41 with 60 ECCoat<br>4<br>AcoustiCork® SCF-41 with 60 ECCoat<br>Connor Sports REGULARX XP-222 | 09-64-66 | 4<br>SEE09-64 Compliance Required per 09-64-66.1.2.1 |
| WDFL2 | | ATHLETIC HARDWOOD FLOORING SYSTEM<br><br>MOVEMENT STUDIO | MANUFACTURER: ROBBINS<br>PRODUCT: UNIMAX100<br>SYSTEM TYPE: ANCHORED SCREWED<br>FLOOR ASSEMBLY THICKNESS: 2-1/8" 53mm<br>SUBFLOOR CONSTRUCTION: CONTINUOUS PANEL SUBFLOOR<br>RESILIENCE LAYER: VIBRATION DAMPENING ZERGUS SHOCK PAD<br>SURFACE FINISH: 25/32" 20mm CONTINUOUS STRIP, BI-MAPLE FLOORING (MPMA-F3)<br>PERIMETER BASE: Rubber vent cove 2" 150mm TYPE - BLACK<br>4<br>ACCEPTABLE EQUALS:<br>4<br>ACCEPTABLE EQUALS:<br>AcoustiTex® F-22 P-31 | 09-64-66 | 4<br>SEE09-64 Compliance Required per 09-64-66.1.2.1 |
| RSF1 | | RESILIENT ATHLETIC FLOORING<br><br>FITNESS CENTRE | MANUFACTURER: ADVANTAGE SPORT<br>PRODUCT: SHOCK TILE<br>DESCRIPTION: ALL-IN-ONE FITNESS FLOOR MADE FROM RECYCLED RUBBER TILES<br>TOPCOAT COLOUR: CONCRETE<br>SIZE/THICKNESS: 1000mm (3 1/3') x 1000mm (3 1/3') x 50mm (2") THK<br>4<br>ACCEPTABLE EQUALS PROVIDED: 25 CONTRACT ADMINISTRATOR TO SELECT FROM FULL COLOUR AND FINISH RANGE.<br>ACCEPTABLE EQUAL (LOW PERFORMANCE): ULTRA TILE 2 | 09-65-66 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| RSF2 | | RESILIENT ATHLETIC FLOORING<br>WITH INTEGRATED LINES<br><br>3-LANE RUNNING TRACK: 2 TONE COLOUR TRACK | MANUFACTURER: ROBBINS<br>PRODUCT: PLEASTIC 19" LAV<br>DESCRIPTION: SEAMLESS, NON-POROUS SMOOTH MULTI-PURPOSE SPORTS FLOOR.<br>TOPCOAT COLOUR: BLUE LINE<br>UNIFORMITY COLOUR: WHITE<br>SIZE/THICKNESS: 10mm THK<br>4<br>ACCEPTABLE EQUAL: CONNOR SPORTS FLEXPLAY WITH AN EMPHASIS COLOUR RANGE<br>ACCEPTABLE EQUAL: FLEXTOUR PLUS WEL AND FLEXR 12-5 CONTRACT ADMINISTRATOR TO SELECT FROM FULL COLOUR<br>ACCEPTABLE EQUAL: | 09-65-66 | REFER TO FLOOR FINISH PLAN FOR TOP COAT COLOUR LOCATION AND UNIFORMY LAYOUT<br>FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| RSF3 | | RESILIENT ATHLETIC FLOORING<br><br>FITNESS CENTRE<br>(HEAVY WEIGHTS AREA) | MANUFACTURER: PUTGO<br>PRODUCT: GENIE MAT OT 70<br>DESCRIPTION: RUBBER FLOORING TILE<br>COLOUR: CRA GRANITE<br>SIZE/THICKNESS: 607mm (23 7/8") x 607mm (23 7/8") x 70mm (2 3/4") THICK | 09-65-66 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| CPT1 | | MODULAR CARPET TILE<br><br>STAFF OFFICES<br>WELLNESS ROOM | MANUFACTURER: INTERFACE<br>COLLECTION: ON LINE<br>PATTERN: 4041451<br>COLOUR: 10370 PEWTER<br>SIZE: TILE 250mm X 1000mm X 3mm THK<br>BACKING: TEC 2000 BIO BACKING<br>FIBER TYPE: 100% RECYCLED CONTENT NYLON<br><br>ALTERNATE - WELLNESS FLOOR COVERING Mex Reconcile Vinx Design DR204 180 Stone | 09-68-00 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| EF1 |  | EPOXY FLOOR COATING<br><br>LOADING/WASTE MANAGEMENT<br>STAFF ENTRY/BICYCLE STORAGE<br>MECHANICAL/ELECTRICAL ROOMS<br>SPRINKLER ROOM<br>RUNNING TRACK STORAGE | MANUFACTURER: MAPEI<br>PRODUCT: MAPEFLOOR SYSTEM 32<br>DESCRIPTION: Solvent-free, multi-layer epoxy system<br>COLOUR: STANDARD COLOR - TBD<br>FINISH: TBD<br>4<br>APPROVED EQUAL: SHERWIN WILLIAMS CONTRACT ADMINISTRATOR TO PICK COLOUR FROM FULL COLOUR AND FINISH RANGE.<br>APPROVED EQUAL: Sherwin Williams MONITED BROADCAST SYSTEM EQUAL PRODUCTS TO MEET SPREAD RATING OF MINIMUM 25 CONTRACT ADMINISTRATOR TO PICK FROM FULL COLOUR AND FINISH RANGE. | 09-67-00 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| EF2 |  | EPOXY FLOOR COATING<br><br>EXIT STAIRS LEVEL 1 | MANUFACTURER: MAPEI<br>PRODUCT: MAPEFLOOR SYSTEM 32<br>DESCRIPTION: Solvent-free, multi-layer epoxy system<br>COLOUR: STANDARD COLOR - TBD<br>FINISH: SEMI<br>4<br>APPROVED EQUAL: SHERWIN WILLIAMS CONTRACT ADMINISTRATOR TO PICK COLOUR FROM FULL COLOUR AND FINISH RANGE.<br>APPROVED EQUAL: Sherwin Williams MONITED BROADCAST SYSTEM EQUAL PRODUCTS TO MEET SPREAD RATING OF MINIMUM 25 CONTRACT ADMINISTRATOR TO PICK FROM FULL COLOUR AND FINISH RANGE. | 09-67-00 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| FLC1 | | FLOOR COATING<br><br>GYM STORAGE, EXIT STAIRS LEVEL 2 AND INTERMEDIATE LANDINGS AND TREADS | MANUFACTURER: TREMCO<br>PRODUCT: TREMCO ROOFGRIP<br>DESCRIPTION: Pedestrian Traffic Coating<br>COLOUR: STANDARD COLOR - TBD<br>FINISH: SEMI<br>4<br>APPROVED EQUAL: SHERWIN WILLIAMS DECK COTE | 09-67-00 | |
| FLGR1 | | FLOOR GRILLMAT<br><br>REC CENTRE ENTRY VESTIBULE | MANUFACTURER: CONSTRUCTION SPECIALTIES<br>PRODUCT: STAINLESS STEEL GRID<br>MODEL: GRIDLINE 06<br>MOUNTING: RECESSED MOUNTED<br>GRID DEPTH: 28.6MM (1 1/8")<br>AXIS/FRAME FINISH: TYPE 316 STAINLESS STEEL WITH SATIN #4 FINISH | 12 48 16 | 1,000 LBS/WHEEL ROLLING LOAD CAPACITY |
| RFL1 | | RESILIENT SHEET FLOORING - RUBBER<br><br>RECEPTION/CONTROL DESK, 2-BAY OFFICE, ESCAPEVER ROOM, START ROOM, 1 MPRP, L MPR STORAGE, MPR TEAM ROOM, MPR'S, MPR STORAGE MOVEMENT STUDIO STORAGE | MANUFACTURER: INTERFACE<br>PRODUCT: ENTWINE 2.0<br>COLOUR: 6522 SUNDAY PAPER<br>BACKING: RUBBER<br>SIZE/THICKNESS: 1.22m x 37m / 2.5mm THK | 09-65-15 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| RFL2 | | RESILIENT SHEET FLOORING - VINYL<br><br>+ 5 COLOURS TO BE SELECTED BY CONTRACT ADMINISTRATOR<br><br>CHILD CARE CENTRE, RECREATION FOOD CONCESSION | MANUFACTURER: FORBO<br>PRODUCT: ETERNAL WOOD<br>COLOUR: 11862 BLOND OAK, PLUS ALLOW FOR 5 ADDITIONAL COLOURS FROM ETERNAL COLOUR LINE TO BE LATER SELECTED BY CONTRACT ADMINISTRATOR<br>SIZE/THICKNESS: 2m x 12m / 2.0mm THK WITH 0.70mm WEAR LAYER<br>ACOUSTICS: 16dL IMPACT SOUND REDUCTION | 09-65-17 | FINAL SUPPLIMENTARY COLOUR SELECTIONS TO BE TAKEN RFL3, RFL4, RFL5, RFL6, RFL7 |
| RFL8 | | FALL SAFE FLOORING<br><br>FAMILY SPACE | MANUFACTURER: SOFSURFACES<br>PRODUCT: SUNSHARE RUBBER PLAYGROUND TILES<br>COLOUR: PREMIUM 95 SERIES, TUSCAN RED<br>SIZE/THICKNESS: 24" x 24" x 2" THK<br>NOTES: 2 in THK suitable for 3 feet fall height | 09-66-66 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| RFL9 | | FALL SAFE FLOORING<br><br>FAMILY SPACE | MANUFACTURER: SOFSURFACES<br>PRODUCT: SUNSHARE RUBBER PLAYGROUND TILES<br>COLOUR: PREMIUM 95 SERIES, SEDONA<br>SIZE/THICKNESS: 24" x 24" x 2" THK<br>NOTES: 2 in THK suitable for 3 feet fall height | 09-65-66 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| TL1 | | FLOOR TILE<br><br>LOBBY/GATHERING, CORRIDORS, MPR SERVERY, CHILD CARE CENTRE CORRECTION, CHILD CARE ENTRY, CHILD CARE SOUTH VESTIBULE, PRE-SCHOOL EAST VESTIBULE | MANUFACTURER: STONE TILE<br>PRODUCT: ST-PETTA SABBIOSA<br>COLOUR: GRIGIO<br>SIZE/THICKNESS: 600mm X 1200mm X 10mm THK<br>FINISH: TEXTURED<br>GROUT: TBD<br>NOTES: | 09-31-00 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| TL2 | | FLOOR TILE<br><br>CHANGE ROOMS, WASHROOMS, STAFF WC, WCC, LTR (1 & 2), CUSTODIAL CLOSET, SHOWERS AT | MANUFACTURER: DALTILE<br>PRODUCT: KEYSTONE<br>COLOUR: DESERT GRAY D614<br>FINISH: MATTE<br>SIZE/THICKNESS: 50mm x 50mm X 6mm THK<br>NOTES: | 09-31-00 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| TLB1 | | TILE BASE<br><br>TILE BASE FOR PUBLIC AREAS AT TL1 LARGE FORMAT TILE | MANUFACTURER: STONE TILE<br>PRODUCT: ST-PETTA SABBIOSA<br>COLOUR: GRIGIO<br>SIZE/THICKNESS: 100mm X 10mm THK<br>FINISH: TEXTURED<br>GROUT: TBD<br>NOTES: LENGTH OF TILES BASES TO CORRESPOND TO 600mm OR 1200mm TILE JOINTS | 09-31-00 | FINAL COLOUR SELECTION PENDING CONTRACT ADMINISTRATOR APPROVAL |
| TLB2 | | COVE WALL BASE - TILE<br><br>TYPICAL AT SHOWERS AND CHANGE AREAS | MANUFACTURER: DALTILE<br>P