



 Ø250mm PERFORATED PIPE
 (LEACHATE DRAINS CUT INTO
 EXISTING WASTE BODIES FOR
 LEACHATE DRAINAGE CONTROL)

 LEACHATE TRENCH WITH
 250mm PERFORATED
 PIPE

1. RETRO-REFLECTIVE POSTS IN ACCORDANCE WITH MANITOBA TRANSPORTATION AND INFRASTRUCTURE (MTI) POLICY STANDARDS NO 600-A-H AS APPROVED BY THE CONTRACT ADMINISTRATOR. 4 REQUIRED AROUND EACH MANHOLE AND 1 REQUIRED BY EACH CLEAN-OUT. POSTS TO BE 100mm x 100mm ORANGE POLY POST AND 4m HIGH.
2. GRANULAR BLANKET SHALL BE PLACED BY WORKING UP SLOPE FROM TOE TO MAINTAIN STABILITY AS APPROVED BY THE CONTRACT ADMINISTRATOR.
3. VOLUME BETWEEN PROPOSED GARBAGE TOP AND GRADED GROUND SURFACE TO BE CONSTRUCTED BY THE CITY OF WINNIPEG IN FUTURE, AND IS INCLUDED HERE FOR REGULATORY PURPOSES.
4. GRANULAR MATERIAL SPECIFICATIONS PROVIDED IN SECTION 31 23 23 UNDER DRAINAGE MATERIAL.



LD-13813

FILE PATH: \\kgs-file\l-r-data\Projects\2025\25-0107-011\Dwg\Env\
FILE NAME: 25-0107-011_G04.dwg