



8-2025 ADDENDUM 2

2025 LOCAL STREET RENEWAL PROGRAM – RAQUETTE STREET AND VARIOUS OTHER LOCATIONS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: April 3, 2025
BY: Blair Cockrell
TELEPHONE NO. 204-928-8431

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 8-2025 Form B: Prices with 8-2025 Addendum 2- Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R1): Revise description of Items F.5 i), G.5 i) and I.5 i).

Revise descriptions and approximate quantity of Items A.3 i), E.3 i), J.3 i) and K.3 i).

PART E – SPECIFICATIONS

Revise: E10.4 to read: Acceptable insulation is:

Extruded Polystyrene rigid foam insulation – Type 4, 100 mm (4”) in thickness.

DOW - Roofmate or Highload 40

Owen’s Corning - Foamular 350 or Foamular 400.

EcoCarbon-Foam-Eco40

2” X 48” X 96”, 2” X 24” X 96”, 4” X 24” X 96”

Add: E23: E23. HAULING AND PLACEMENT OF 50 MM GRANULAR B RECYCLED CONCRETE AGGREGATE

DESCRIPTION

E23.1 General

E23.1.1 This specification covers the hauling from a designated supplier and installation of 50 mm Granular B Recycled Concrete Aggregate.

E23.1.2 Referenced Standard Construction Specifications

(a) CW 3110 – Sub-Grade, Sub-Base and Base Course Construction.

MATERIALS

E23.2 Materials will be provided to the Contractor by the supplier awarded the contract in accordance with Tender No. 103-2025.

HAULING OF MATERIAL

E23.3 The Contractor shall obtain the 50 mm Granular B Recycled Concrete Aggregate by the supplier awarded the contract in accordance with Tender No. 103-2025.

E23.4 The Contractor shall place orders for material by calling the supplier awarded the contract in accordance with Tender No. 103-2025.

E23.5 The material will be available for pick up between the following hours:

(a) 0700 to 1800 from Monday to Friday

(b) 0700 to 1400 on Saturday

E23.6 Material will not be available for pick up on general holidays in Manitoba.

E23.7 Requests for pick-up outside of these hours must be made a minimum of four days in advance to the Contract Administrator.

E23.8 The Contractor will be provided use of the scale at the pick-up site to facilitate tare and gross vehicles weights. A printed ticket will be provided for each load.

E23.9 The supplier shall load the material into the Contractor's truck/truck trailer and shall facilitate unloading when a truck has been overloaded.

CONSTRUCTION METHODS

E23.10 Construction methods will be in accordance with CW 3110.

QUALITY ASSURANCE TESTING

E23.11 Quality Assurance Testing for physical properties as per CW 3110 will not be required. Field Density Testing will be required as per CW 3110.

MEASUREMENT AND PAYMENT

E23.12 The hauling, placing and compaction of sub-base material will be measured on a weight basis and paid for at the Contract Unit Price per tonne for the "Hauling and Placing Sub-Base Material" listed here below. The weight to be paid for will be the total number of tonnes of sub-base material supplied and placed in accordance with this specification, accepted and measured by the Contract Administrator.

E23.13 Items of Work:

(a) 50 mm Granular B Recycled Concrete Aggregate.

E23.14 The weight to be paid for will be the total number of tonnes of sub-base material as measured on a certified weight scale.

E23.15 Only material placed within the limits of excavation will be included in the payment for the "Items of Work listed for sub-base material".

E23.16 No measurement or payment will be made for materials rejected by the Contract Administrator.

DRAWINGS

Replace: 8-2025 _Drawing_CT-08-R0 with 8-2025 _Addendum_2-Drawing_CT-08-R1

Replace: 8-2025 _Drawing_CT-14-R0 with 8-2025 _Addendum_2-Drawing_CT-14-R1

Replace: 8-2025 _Drawing_CT-15-R0 with 8-2025 _Addendum_2-Drawing_CT-15-R1

Replace: 8-2025 _Drawing_CT-16-R0 with 8-2025 _Addendum_2-Drawing_CT-16-R1

Replace: 8-2025 _Drawing_CT-21-R0 with 8-2025 _Addendum_2-Drawing_CT-21-R1

Replace: 8-2025 _Drawing_CT-22-R0 with 8-2025 _Addendum_2-Drawing_CT-22-R1

Replace: 8-2025 _Drawing_CT-29-R0 with 8-2025 _Addendum_2-Drawing_CT-29-R1