

1. PROVIDE WALL MOUNT DIGITAL GENSET CONTROLLER AT WATCH DESK 109, 60" AFF OF EXISTING 5-GANG LIGHT SWITCH, WITH 3/4" EMT (INSIDE BUILDING/ABOVE GRADE) & PVC CONDUITS (BELOW GRADE) TO GENERATOR. ALSO REFER TO DRAWING E3 RENOVATION NOTE 2. GENERATOR.
2. REWORK PANEL "NP-A" FEEDER PATHWAY TO "MD-1" TO MEET CODE.
3. PROVIDE GFCI DUPLEX RECEPTACLE 42" AFF.
4. REMOVE MOBILE GENSET CEILING-HUNG RECEPTACLE & COMPONENTS BACK TO PANEL.
5. ALL CEILING RECEPTACLES SHALL BE CONNECTED TO EMERGENCY POWER PANELS. RE-CIRCUIT MAYBE REQUIRED.
6. RE-CIRCUIT EQUIPMENT.

A circular professional engineer seal for the Province of Manitoba. The outer ring contains the text "PROVINCE OF MANITOBA" at the top and "REGISTERED PROFESSIONAL ENGINEER" at the bottom. Inside the ring, the name "X. WU" is printed above "Member 31088". A handwritten signature in blue ink is written across the seal. A date stamp "2025-09-11" is also visible.


Winnipeg
THE CITY OF WINNIPEG
SETS & PROJECT MANAGEMENT DEPT.
MUNICIPAL ACCOMMODATIONS DIV.
3-65 GARRY STREET, R3C 4K4

SHEET TITLE
MAIN FLOOR PLAN
ELECTRICAL
POWER AND SYSTEMS

SCALE AS SHOWN	PROJECT No: 2024-070	SHEET No: E4-R1
-------------------	-------------------------	---------------------------