



82-2025 ADDENDUM 2

SHOAL LAKE AQUEDUCT MANHOLE REPAIRS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: 2025-05-30
BY: A. Braun
TELEPHONE NO. 204 955-1210

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2024-02-01

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 82-2025 Form B: Prices with 82-2025 Addendum 2 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Add: 2.(c): Supply of Granular Material for Pad Upgrades

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

- Add: E16.2(d) Granular pad materials shall be a hard, durable crushed granite aggregate, clean and free from organic material, meeting the gradation requirements of CW3110, 50 mm, Granular B or MTI CR-MM50 (MTI 901).
- Add: E16.3(e) Granular materials shall be stockpiled at the GWWD East Braintree Railway Yard or at a mutually agreed upon location a minimum of two (2) months in advance of the pad upgrade work at the SLA site.
- Add: E16.3(f) GWWD Railway staff will transport granular materials to the site via the GWWD Railway. The Contractor shall provide equipment for the following portions of the operations:
- (i) Loading railcars at the East Braintree GWWD Railway Yard.
 - (ii) Stockpiling materials at each manhole site.
- Add: E16.4.2 Supply of Granular Material for Pad Upgrades
- Add: E16.4.2(a) Supply of granular material for pad upgrades will be measured and paid on a per tonne basis at the Contract Unit Price as identified in Form B. Payment shall include all materials and labour to complete the work.