



### 839-2025 ADDENDUM 3

## ARMSTRONG SEWER RELIEF WORKS (CONTRACT 1)

### URGENT

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: April 16, 2026  
BY: John Minkevich  
TELEPHONE NO. (204) 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Addendum 2026-03-10

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

### FORM B: PRICES

Replace: 839-2025 Form B: Prices with 839-2025 Addendum 3 Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B (R2):

- Revise: B.5 (a) to read: "600 mm PVC (SDR35) within 900mm Steel Casing Pipe, Class B bedding, Class 1 backfill"
- Revise: Approximate Quantity for B.7 (a) (i) to read: **298.0**
- Revise: Approximate Quantity for B.7 (a) (ii) to read: **173.0**
- Revise: Approximate Quantity for B.9 (a) to read: **298.0**
- Revise: Approximate Quantity for B.9 (b) to read: **173.0**
- Revise: B.10 (a) (i) to read: "1200 mm Dia x 1.22 m high base (MH 2,3, 5, 7, 9, 12, 13, 15,16, 17, 19, 20, 22, **22A**, 23, 24, 25, 28, 29, 36, 37, 40, 41, 46, 47, 52, 53, 54, 57, 58, 26, 30)"
- Revise: Approximate Quantity for B.10 (a) (i) to read: **181.5**

### PART D – SUPPLEMENTAL CONDITIONS

- Revise: D2.7 (d) to read: "The chamber construction Work must take place during the dry weather flow (DWF) period from December 1 to Feb 28<sup>th</sup>, **unless authorized by the Contract Administrator. The Contract Administrator will work with the Contractor to determine the exact limits of Dry Weather Flow based on site conditions approaching the defined DWF period of December 1 to February 28.**"
- Revise: D.17 (b) to read: "Any Work associated with the construction of the Chamber to facilitate the connection of the new sanitary trunk sewer to the interceptor sewer at Main Street must be undertaken during the dry weather flow (DWF) period (between December 1 and February 28th),

**unless authorized by the Contract Administrator. The Contract Administrator will work with the Contractor to determine the exact limits of Dry Weather Flow based on site conditions approaching the defined DWF period of December 1 to February 28.”**

Delete: D19.1 (c)

Delete: D23.1 (c)

Revise: D35.5 (a) to read: “The Fuel Factor rate shall be set at 2.7% of the monetary value of all Work based on unit prices.”

Delete: D35.5 (b)

Delete: D35.5 (c)

## **PART E – SPECIFICATIONS**

Add: E10.4.4 (a)(i) to read: “The center southbound lane may be temporarily closed to accommodate the work around the Main Street interceptor connection chamber. This temporary lane closure must be limited to as short a period of time as possible to complete the Work and may include a contraflow lane in the median northbound lane.”

Add: E11.1 (f) to read: “For the proposed construction laydown area east of the CKPC Rail in the grassed park enclosed by Leila Avenue, Partridge Avenue and McGregor Street and as identified on drawing 13658, all trees to be protected with temporary fencing a minimum of 3 metres from the base of the trees to protect root zones, except for the dingle spruce tree near the middle of the site. This single spruce tree may be cut down but will need to be replaced in a nearby location, acceptable to the City Urban Forestry Dept, during the final restorations, as per E12.”

Revise: E25.7 (f) (i) to read: “Controlled Low-Strength Material (CLSM) / Cement Stabilized Fill shall be in accordance with CW 2030 and Table CW 2160.1 unless otherwise indicated on the Drawings.

- ◆ The Contractor shall install fill in lifts and provide sufficient supports to resist uplift of piping or structures due to backfilling.”

Add: E25.7 (g) to read: “Excavation under or within one (1) meter of sidewalks, pathways and alleys shall be Class 2 or 3 as per SD-002.”

Add: E28.1.3 (b) to read: “Any depressurization work conducted outside of the Dry Weather Flow period (between December 1 and February 28) will be at Contractor’s cost.”

Revise: E29.1 (a) to read: “Tunnelling methods shall be used for the installation of the new WWS Trunk sewers 900 mm or larger as shown on the drawings beginning east of the CPKC rail crossing and continuing to the connection to **MH-65** (with the exception of the crossings of the existing 2700 mm Trunk sewer that will be installed in accordance with **Error! Reference source not found.**)”

Revise: E37.1 (c) to read: “The Work associated with the construction of the chamber, including the shoring to support the chamber construction and connections to the chamber must occur within the dry weather flow period identified in the Sequence of Work (Section D17), **unless authorized by the Contract Administrator. The Contract Administrator will work with the Contractor to determine the exact limits of Dry Weather Flow based on site conditions approaching the defined DWF period of December 1 to February 28.**

**Note that an exclusion to the limitation of Work only occurring within the DWF period may be allowed for the shoring, 900 mm sewer connection and any excavation up to 5 m radius from the 2250 mm Main Street interceptor sewer. Any**

**excavation within a 5 m radius of the 2250 mm Main Street Interceptor sewer must be reviewed and approved by the Contractor's Structural Engineer, and submitted in writing to the Contract Administrator for approval."**

Add: E37.4 (b) to read: "If the Contractor's proposed installation method requires changes to the Main Street Interceptor Connection Chamber, the Contractor shall be responsible for all additional costs associated with that change."

## **DRAWINGS**

### **Note:**

- 1) A new 1200mm dia. manhole (MH 22A) will be added to the 250mm collector WWS at approx. STA 11+55 on Leila Avenue (drawing 13653) and the approximate quantity was revised in 839-2025 Form B: Prices with 839-2025 Addendum 3 Form B: Prices. A revised drawing with the change will be provided to the successful bidder after Award of Contract.
- 2) All sewer services ranging in sizes between 150mm and 200mm, which cross the 350mm AC WM between STA 7+75 and STA 16+20 on Leila Avenue (drawing 13650, 13651, 13652, 13653, 13654, 13655, 13656 and 13657) will be extended 2.0m in length to the south to allow for proper distance between the installation shafts and the 350mm AC WM. The change in quantities was revised accordingly in 839-2025 Form B: Prices with 839-2025 Addendum 3 Form B: Prices.

## **APPENDICES**

Replace: 839-2025\_Appendix\_E with 839-2025\_Addendum 3\_Appendix\_E

**NOTE TO BIDDERS: QUESTIONS AND ANSWERS BELOW DO NOT FORM PART OF THE CONTRACT**

**QUESTIONS AND ANSWERS**

Q1: Can work be done outside of the DWF exclusion period at the Main Street Interceptor?

A1: Work that does not affect the structural integrity of the 2250 mm Main Street Interceptor, as outlined in E37, may proceed with approval of the Contract Administrator.