



## CHLORINE BUILDING GROUND FLOOR

SCALE: 1 :

## GENERAL NOTES:

1. ALL EQUIPMENT MARKED FOR DEMOLITION INCLUDES THE COMPLETE REMOVAL BACK TO THE SOURCE PANEL OF ANY EXISTING POWER AND CONTROLS SYSTEMS ASSOCIATED WITH THAT EQUIPMENT.

## DEMOLITION NOTES:

- (A) EXHAUST FAN TO BE DEMOLISHED. REMOVE ALL CONDUIT AND CABLING FOR POWER AND CONTROLS BACK TO THE SOURCE PANEL. COMPLETELY REMOVE ANY ASSOCIATED MOTORIZED DAMPERS AND FIELD CONTROL EQUIPMENT.
- (B) REMOVE MOTORIZED INTAKE DAMPER AND ALL ASSOCIATED CONDUIT AND CABLING FOR POWER AND CONTROLS BACK TO THE SOURCE PANEL.
- (C) REMOVE EXISTING CHLORINE GAS DETECTION CONTROLLER PC-920-AIY AND ASSOCIATED CHLORINE GENERATOR AND SENSORS. EXISTING CHLORINE HORNS AND STROBES ARE BEING REUSED AND REWIRED TO NEW CONTROLLERS. CONTRACTOR TO RETAIN EXISTING WIRING/ CONDUIT TO HORNS AND STROBES WHERE POSSIBLE AND MODIFY/ADD ACCORDINGLY. EXISTING GAS DETECTION CONTROLLER SHALL REMAIN IN OPERATION UNTIL NEW SYSTEM IS INSTALLED, COMMISSIONED AND PUT IN SERVICE. CONTRACTOR TO ENSURE CONSTRUCTION SCHEDULE FACILITATES THIS MANDATE

1-0640C-E0005	ELECTRICAL PANEL LAYOUT, MCC-C710/MCC-C720E
DRAWING NUMBER	REFERENCE DRAWINGS



					 <b>AtkinsRéalis</b> 148 Nature Park Way, Winnipeg, Manitoba Canada R3P 0X7 204-786-8080	ENGINEER'S SEAL						
00	ISSUED FOR TENDER AND CONSTRUCTION	2025/04/30	VE	VE	CONSULTANT NO.:							
NO.	REVISIONS	DATE	DESIGN	CHECK								