



# 200-2026 ADDENDUM 1

## 2026 WATER MAIN RENEWALS – CONTRACT 4

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: April 23, 2026  
BY: Rob Sherlock  
TELEPHONE NO. 204 478-8993

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Addendum 2026-03-10

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

### **PART E – SPECIFICATIONS**

- Add: E12.11 Temporary shutdown of the existing 900mm Ingersoll feeder main will be required when installing the proposed 250mm water main that will cross the feeder main on St. Matthews Avenue on drawings D-17522. The Contractor shall provide a schedule for the proposed shutdown to the Contract Administrator a minimum of five (5) Business Days prior to the proposed shutdown date for coordination with the City. Written construction method statement identified in E12.10 shall be submitted and approved prior to submission of proposed feeder main shutdown schedule.
- Add: E12.12 Proposed shutdown timeline for the existing 900mm Ingersoll feeder main is subject to approval of the Superintendent of Water Distributions Operations, and will be dependent on the availability of City personnel to complete shutdown of the feeder main, and that there are no other active shutdowns within the distribution system that will be impacted by the shutdown of the feeder main. No claim for delay will be considered if the City is unable to complete the feeder main shutdown in accordance with the Contractor's proposed construction schedule.
- Add: E12.13 Subject to approval of the written construction method statement identified in E12.10, and approval of the proposed shutdown timeline as per E12.12, should the proposed shutdown timeline for the existing 900mm Ingersoll feeder main be prior to September 7, 2026, any proposed shutdown would be limited to a maximum of three (3) Calendar Days. Should the Contractor require a shutdown longer than three (3) Calendar Days to complete the feeder main crossing at St. Matthews Avenue, this shutdown must be scheduled after September 7, 2026, and is still subject to approval as per E12.12.
- Add: E12.14 Temporary shutdown of the existing 900mm Ingersoll feeder main will not be required for installation of the parallel water main renewal on Ingersoll Street, or for water service renewals that will be crossing the feeder main provided all Work in close proximity to a feeder main, exploratory excavations, and shoring is completed in accordance with E12 to E14.