



## 242-2026 ADDENDUM 1

### 2026 WATER MAIN RENEWALS – CONTRACT 7

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE  
BID/PROPOSAL**

ISSUED: April 29, 2026  
BY: Jeff Fraser  
TELEPHONE NO. 204 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID/PROPOSAL AND SHALL FORM  
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Addendum 2026-03-10

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.**

---

#### **FORM B: PRICES**

Replace: 242-2026 Form B: Prices with 242-2026 Addendum 1 - Form B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R1):

- Revised Pay Item B.1 a) i) to read “trenchless installation, Class B sand bedding, Class 3 backfill”
- Revised Pay Item B.11 Spec. Ref. to read “E8, CW 3335”
- Removed Pay Item C.17 “Supply and Install Detectable Warning Surface Tiles”
- Revised Pay Item C.18 Spec. Ref. to read “E8, CW 3335”
- Removed Pay Item D.12 “Supply and Install Detectable Warning Surface Tiles”
- Revised the quantity of Pay Item E.1 a) i) to read 40 l.m.
- Revised Pay Item E.1 b) i) to read “trenchless installation, Cement-Bentonite Fill backfill”
- Added Pay Item E.1 c) i) “trenchless installation, Cement-Bentonite Fill backfill”
- Revised the quantity of Pay Item E.5 a) i) to read 28 l.m.
- Added Pay Item E.5 b) i) “trenchless installation, Cement-Bentonite Fill backfill”
- Revised the Units of Pay Item E14 from “Lump Sum” to “Allowance” in the amount of \$10,000.
- Revised Pay Item F.16 Spec. Ref. to read “E8, CW 3335”
- Added Pay Item G.6 c) “Curb Stops – Replace Existing”, Size 25 mm, Quantity 1.
- Added Pay Item G.7 c) “Curb Stop Boxes – Replace Existing”, Size 25 mm, Quantity 1.
- Any Reference to E6 on the Form B has been revised to read E7.

## **PART B – BIDDING PROCEDURES**

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, **May 4<sup>th</sup>**, 2026.

## **PART E – SPECIFICATIONS**

- Add: E14.1 c) Cement-Bentonite Fill is to replace the standard Class 3 backfill and sand bedding in all excavations on the “wet” (river) side of the Scotia Street centerline including but not limited to all construction shafts and utility locate excavations.
- Add: E14.6 (a) iii) All piping and appurtenances within excavations where CB fill is to be placed are to be wrapped in a 0.15 millimetre (6 mil) thick polyethylene sheet bond breaker for future maintenance.