



REFERENCE NOTES:

- CONSTRUCTION NOTES:**

1. PLANE EXISTING ASPHALT PAVEMENT IF REQUIRED AND PLACE NEW 80mm TYPE MS1 ASPHALT PAVEMENT
2. REMOVE EXISTING PAVEMENT AND CONSTRUCT NEW 200mm REINFORCED CONCRETE PAVEMENT c/w NEW 80mm TYPE MS1 ASPHALT OVERLAY
3. CONSTRUCT NEW CONCRETE CURB RAMP (10-12mm HT. INTEGRAL)
4. CONSTRUCT NEW CONCRETE BARRIER CURB (100mm HT. SEPARATE)
5. CONSTRUCT NEW CONCRETE MODIFIED BARRIER CURB (150mm HT. INTEGRAL)
6. RENEW EXISTING CONCRETE RAMP CURB (10-12mm HT. MONOLITHIC)
7. RENEW EXISTING CONCRETE BARRIER CURB (100mm HT. DOWELLED)
8. RENEW EXISTING CONCRETE MODIFIED BARRIER CURB (150mm HT. DOWELLED)
9. RENEW EXISTING 100mm CONCRETE SIDEWALK
10. INSTALL EXISTING MANHOLE/ CATCH BASIN TO GRADE
11. ADJUST NEW CAST IRON RISER RING
12. REMOVE EXISTING FRAME AND PLACE NEW FRAME AND SOLID COVER (AP-006/AP-007)
13. INSTALL NEW CURB AND GUTTER INLET c/w 1800mm CATCH BASIN (SD-024) AND CONNECT NEW 250mm LEAD TO EXISTING 300 COMBINED SEWER
14. REMOVE EXISTING CATCH BASIN / CATCH PIT AND ABANDON LEAD
15. INSTALL NEW DETECTABLE WARNING SURFACE TILE
16. ADJUST EXISTING WATER VALVE TO GRADE
17. ADJUST ALL WATER SERVICE SHUT OFF VALVES (CURB STOP) TO GRADE

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE, BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

AECOMENGINEER'S SEAL

CONSULTANT DRAWING NO
CT-06

 THE CITY OF WINNIPEG PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION	
2026 REGIONAL STREET RENEWAL PROGRAM	CITY DRAWING NUMBER P-3603-06
	SHEET OF 13
EDMONTON STREET - ELlice AVENUE TO CUMBERLAND AVENUE PAVEMENT REHABILITATION PLAN/PROFILE - STATION 0+410 TO CUMBERLAND AVENUE	