



319-2026 ADDENDUM 2

WEWPCC FEEDER CABLE REPLACEMENT 2026

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: May 22, 2026
BY: Vivek Elimban /Andre Entz Arajuo
TELEPHONE NO. 204 558-3055

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Addendum 2026-03-10

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

DRAWINGS

Replace: 319-2026_Drawing_1-0103-EDTL-Y001-R0 with 319-2026_Addendum_2_Drawing_1-0103-EDTL-Y001-R1

NOTE TO BIDDERS: QUESTIONS AND ANSWERS BELOW DO NOT FORM PART OF THE CONTRACT

QUESTIONS AND ANSWERS

- Q1: The drawing 1-0103-EDTL-Y001 shows 70 MOV arrestors. Please confirm if this is correct?
- A1: The operating voltage is 12.47kV. Please provide 12.47kV rated arrestors. Updated drawing has been included with the addendum. Fuse interrupting rating has also been updated on the drawing that was missing.
- Q2: Is directional drilling under the roadway and using a 5 inch high density polyethylene (HDPE) pipe acceptable? It will be less destructive and will not block the roadway near the disconnect switches?
- A2: Yes, directional drilling under the roadway and using a 5 inch HDPE pipe is acceptable. Extend pipe 2 meters on each side of the roadway. Trench remaining cable run.