



EXISTING CURB

2.500

3.00%

0.60

0.25 ROUNING

80mm TYPE ASPHALT
100mm BASE COURSE
250mm - 50mm SUB-BASE MATERIAL
SEPARATION GEOTEXTILE FABRIC

REGRADE GRANULAR SHOULDER WHERE REQUIRED AS DIRECTED BY THE CONTRACT ADMINISTRATOR

TOPSOIL WHERE REQUIRED AS DIRECTED BY THE CONTRACT ADMINISTRATOR

VARIES

WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES



300 IDS	LAND DRAINAGE SEWER	300 IDS		POLES	T-MIS H-HYDRO
250 WWS	WASTE WATER SEWER	250 WWS		LIGHT STANDARD	
---	GAS	---	---	BACK OF CURB	
---	HYDRO	---	---	ASPHALT RENEWAL	
---	M.T.S.	---	---	FULL DEPTH REPAIR	
150 WM	WATERMAIN	150 WM	---	SIDEWALK REPAIR	
	HYDRANT		---	DIAMOND GRINDING	
	VALVE			BUS ROUTE	---
	MANHOLE		---	PROPERTY LINE	---
	CATCH BASIN		---	SIDEWALK	---
	CURB INLET			TRAFFIC SIGNAL	---
EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PLAN	PROPOSED

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. . ELEV. .		COORDINATE SYSTEM: COV028		
0	ISSUED FOR TENDER	26.04.28	CR	
NO.	REVISIONS	DATE	BY	



DESIGNED BY	AB.	CHECKED BY	SJP
DRAWN BY	AB.	APPROVED BY	CR
HOR. SCALE: 1:250 VERTICAL:		RELEASED FOR CONSTRUCTION:	
DATE	2026/03/23	DATE	2026/04/24

CONSULTANT NO.



THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

PROJECT TITLE	2026 STREETS MAINTENANCE PRESERVATION PROGRAM LAGIMODIERE BOULEVARD SOUTHBOUND
---------------	--

ASPHALT SHOULDER RECONSTRUCTION
STA 1+550 TO STA 1+890

SHEET OF

15 17

CONSULTANT PROJECT NO.
26-0107-006

CITY DRAWING NUMBER
C-114