

467-2026 ADDENDUM 2

KILCONA PARK ROADWAY CONSTRUCTION AND HARBOURVIEW ROADWAY RECONSTRUCTION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: July 7, 2026
BY: David Wiebe, P.Eng.
TELEPHONE NO. 204 453-2301

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Addendum 2026-03-10

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART E – SPECIFICATIONS

- Add: E24.1 (d) The Contractor shall haul approximately three thousand cubic metres (3,000 m³) of suitable site fill material as confirmed and approved by the Contract Administrator to the Dog Park Stockpile Area identified on Sheet 1 of the Drawings.
- Revise: E24.3 to read: Hauling and disposal of excavated material at the Dog Park Stockpile Area, Cordite Landfill and any other location described in CW 1130-R5 are considered incidental to excavation. No further payment will be made for the hauling and disposal of excavated material at these locations.
- Revise: E29.6.4 to read: Sand: washed sand, medium to coarse textured.
- Delete: E32.7.1 (a)
- Delete: E32.7.2 (a)

DRAWINGS

Replace: 467-2026_Drawing_0001_Sht001-RA with 467-2026_Addendum_2-Drawing_0001_Sht001-R1