

1. ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH LATEST REVISION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
2. LEGAL PLAN AND UNDERGROUND INFORMATION FROM CITY OF WINNIPEG LBIS. CONTRACTOR TO VERIFY ALL UNDERGROUNDS IN THE FIELD.
3. CONTRACTOR TO TAKE PRECAUTIONARY STEPS TO AVOID DAMAGE FROM CONSTRUCTION ACTIVITIES TO TREES WITHIN THE LIMITS OF CONSTRUCTION AS OUTLINED IN THE SPECIFICATIONS.
4. LOCATION OF EXISTING SERVICES TO BE CONFIRMED IN THE FIELD BY THE CONTRACTOR.
5. ALL DIMENSIONS ARE TO BACK OF CURB.
6. INSTALL CB LEADS AT MIN. 1.0% SLOPE OR AS DIRECTED BY THE CONTRACT ADMINISTRATOR.
7. CONTRACTOR TO CONFIRM EXISTING LEAD INVERT ELEVATIONS PRIOR TO INSTALLATION.
8. ADJUST ALL WATER VALVES, MANHOLES, CATCH BASINS, CATCH PITS AND WATER SHUT OFF VALVES TO GRADE.
9. REFER TO TENDER FOR DETAILS REGARDING TRAFFIC MANAGEMENT.

- A - DISTANCE FROM EDGE OF PAINT LINE TO RUMBLE STRIP (25 mm)
- B - WIDTH OF PATTERN (TRAVERSE TO DIRECTION OF TRAVEL (150 mm))
- C - STRIP SHAPE (ROUNDED)
- D - SPACING BETWEEN STRIPS (250 mm)
- E - STRIP DEPTH (6 mm)
- F - STRIP LENGTH (LONGITUDINAL TO DIRECTION OF TRAVEL (60mm))
- G - WIDTH OF PAINT LINE (100 mm) CENTERED ON LANE EDGE



WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

C:\pw working directory\projects 2025\dillon_40tjh\dms58542\252191-CT-CON-KILCONA.dwg