

**NOTES :**

CONSTRUCTION STANDARDS  
 TO BE CONSTRUCTED IN ACCORDANCE WITH MANITOBA HYDRO DISTRIBUTION AND SUBTRANSMISSION STANDARDS, LATEST REVISION.  
 NO MAJOR CHANGE SHALL BE MADE WITHOUT APPROVAL OF THE DESIGN ENGINEER OR DELEGATE.

SURVEYS TO STAKE OUT SURVEY MONUMENTS, IF IN THE VICINITY OF THE NEW CONSTRUCTION TO PREVENT DAMAGE OR LOSS.

INSTALLED			
Quantity	Fixture Type	Wattage	Pole Type
6	LED	40	EXCLUSIVE

SALVAGED			
Quantity	Fixture Type	Wattage	Pole Type
4	LED	45	EXCLUSIVE

LOCATION	LUMINAIRE	TYPE	HEIGHT	AVG. CONC. ADJ. MIN.	AVG. CONC. ADJ. MAX.	SPACING

CONTACT	NAME	PHONE NUMBER	E-MAIL ADDRESS
DESIGN	DALE LAMOUREUX	204-599-1384	DLAMOUREUX@HYDRO.MB.CA
DESIGN ENGINEER	KEVIN VANDERBERGHE	204-334-9770	KVANDERBERG@HYDRO.MB.CA
PROJECT MGMT	DIANA NEWBURY	204-226-8325	DNEWBURY@HYDRO.MB.CA
ESA	RYAN AUBRY	204-325-3097	RAUBRY@HYDRO.MB.CA
U/G CONSTRUCTION	JEFF BREAKAY	204-871-2003	JBREAKAY@HYDRO.MB.CA
OWG CONSTRUCTION	COLIN ROCHON	204-981-4137	CROCHON@HYDRO.MB.CA
BELLMTS			
ROGERS			
CUSTOMER	NAVLED HANDEE	204-471-3132	NHANDEE@WANNPREG.CA
CONSULTANT	RICHARD HAWKINS	204-781-6607	RICHARD.HAWKINS@WSP.COM
ENG TECH	TODD FOUNTAIN	204-792-3662	TFOUNTAIN@HYDRO.MB.CA
ENG TECH			

AUTHORITY	NOTIFIED	NOT REQ'D	OBTAINED
DEPT. OF HIGHWAYS			
MUNICIPAL			
BELLMTS / SHAW			
GAS			
EASEMENTS			
CONTROL CENTER			
RAILWAY			
ENVIRO SCREENING			

REEL NUMBER	MANUFACTURER	MANUFACTURE DATE

**CAUTION:  
SEWER, WATER AND GAS  
IN WORK AREA  
USE SOFT DIG AS REQUIRED**

**U/G SL CABLE TO BE MINIMUM  
1.0m AWAY FROM ALL OTHER  
UTILITIES UNLESS OTHERWISE  
NOTED**

**UPON DISCONNECT BY MB HYDRO  
THE CONTRACTOR SHALL INSTALL  
TEMPORARY #6 OVERHEAD FEED IN  
ORDER TO MAINTAIN LIGHTING DURING  
CONSTRUCTION.  
AT THE END OF CONSTRUCTION TEMPORARY  
OVERHEAD SHALL BE DISCONNECTED BY  
THE CONTRACTOR**

**MB HYDRO SHALL CUT, CAP AND ABANDON  
ORIGINAL FEED TO THE STREET LIGHTS  
PRIOR TO REMOVAL. ALL FINAL  
WILL BE COMPLETED BY MB HYDRO.**

**INSTALL NEW STREET LIGHTS AND CABLE  
ON ALIGNMENTS AS SHOWN.**

**INSTALL NEW GROUND RODS AS  
PER CD 50-5**

**ALL STREET LIGHT CABLE TO BE INSTALLED  
IN 2" CONDUIT. FIELD BEND WHERE  
REQUIRED.**

FOR CLEARANCE OF EXISTING WATER & WASTE DEPARTMENT PLANT CONTACT THE SURVEY & INSPECTION BRANCH 48 HOURS PRIOR TO CONSTRUCTION AT 986-3322

NOTE: INDICATION OF ALL UNDERGROUND UTILITIES IS FOR ILLUSTRATIVE PURPOSES ONLY. CONTACT THE APPLICABLE UTILITIES FOR SPECIFIC PLANT LOCATIONS AND CLEARANCES.

**CONSTRUCTION CONCURRENCE**

I, \_\_\_\_\_  
 OF \_\_\_\_\_  
 CONCUR WITH THIS PLAN FOR CONSTRUCTION. CUSTOMER IS RESPONSIBLE TO PROVIDE FINISHED GRADES, LOCATE AND MARK ANY CUSTOMER OWNED UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION (IE. SEWER LINES, WATER LINES, POWER LINES, ETC).  
 SIGN: \_\_\_\_\_ DATE: \_\_\_\_\_

CONTACT "CLICK BEFORE YOU DIG MANITOBA" AT  
[ClickBeforeYouDigMB.com](http://ClickBeforeYouDigMB.com)  
**THREE FULL WORKING DAYS**  
 PRIOR TO CONSTRUCTION FOR LOCATION OF WATER, WASTEWATER, LAND DRAINAGE UTILITIES AND MANITOBA HYDRO UTILITIES

**PRELIMINARY NOT TO  
BE USED FOR  
CONSTRUCTION**

**THIS IS A PRINT OF A DOCUMENT THAT  
HAS BEEN ELECTRONICALLY AUTHENTICATED  
TECHNOLOGY AUTHORIZED BY THE EGM.  
THE ORIGINAL IS IN ELECTRONIC FORM.**



MB HYDRO TO INSTALL NEW DIP PER CD 315-5  
 CONTRACTOR SHALL INSTALL LOWER 3M  
 OF CABLE GUARD PER CD 315-5 & CD 200-63.  
 COIL NEW CABLE FOR FINAL CONNECTION BY MB HYDRO  
 BUILD POLE TO CD 62-26

INSTALL STANDARD ON  
 BREAKAWAY BASE

SALVAGE SIL DIP AND HARDWARE



NO	DATE	REVISIONS	BY	CHKD	APP	ORIGINAL DRAWING SEALED BY	AREA	MANITOBA HYDRO DISTRIBUTION PLANNING & DESIGN WO# P-42598 NETWORK# 4309377
							5306	
							STATION NUMBER 1030	CSC: ST BONIFACE
							FEEDER NUMBER SD777	CUSTOMER SERVICE PROJECT INSTALLATION OF STREETLIGHT BASES, STANDARDS AND CABLE.
							SYSTEM VOLTAGE 7.2/12.47 KV	LITZ PL BETWEEN HENDERSON HWY & APPLETON ST
							SCALE 1:750	
							DATE 02/13/2026	
								1-04707-DE-50000-0689
								SHT. 01/01 REV. 00