



1. ALL EQUIPMENT, DEVICES, FIXTURES REMOVED UNDER DEMOLITION SHOULD BE FIRST OFFERED TO THE CITY FOR REFUSAL, FOLLOWED BY CONTRACTOR AND FINALLY TO BE LEGALLY DISPOSED OF.
2. 3. FOR ALL EXISTING ELECTRICAL DEVICES, EQUIPMENT, ETC. THAT ARE REMOVED, REMOVE EXISTING CONDUIT, WIRING, ETC. BACK TO SOURCE UNLESS OTHERWISE NOTED.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING EXACT LAYOUT, ROUTING, ETC. VERIFY EXISTING SERVICES ON SITE.
5. 6. VERIFY ALL EXISTING EQUIPMENT BEING RE-USED IS WORKING PRIOR TO INSTALLATION. SUPPLY NEW EQUIPMENT AS NECESSARY.
7. CONTRACTOR TO DETERMINE EXACT CABLE ROUTES ON SITE, WHERE POSSIBLE FOLLOW EXISTING CABLE ROUTES THROUGH BUILDING. RE-USE EXISTING OPENINGS AND PENETRATIONS TO ROUTE CABLES. PROVIDE NEW PENETRATIONS WHERE EXISTING CANNOT BE RE-USED. SEAL ALL PENETRATIONS.
8. 9. SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS WITH FIRE STOP MATERIAL AS REQUIRED TO MAINTAIN ASSEMBLY RATING.
10. 11. COORDINATE FULLY WITH MECHANICAL FOR THE SEQUENCE OF DEMOLITION AND CONSTRUCTION.
12. 13. COORDINATE WITH THE CITY PRIOR TO SHUT DOWN OF EQUIPMENT.
14. CONTRACTOR SHALL ENSURE COORDINATION BETWEEN ALL SUBCONTRACTORS AND CONTRACT ADMINISTRATOR, ON AND OFF SITE, AS REQUIRED FOR INSTALLATION OF ELECTRICAL EQUIPMENT.
15. 16. CONTRACTOR TO VISIT SITE DURING BID AND VERIFY ALL EXISTING SERVICES ON SITE PRIOR TO SUBMITTING BID. REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR DURING BID PERIOD.
17. 18. ARRANGE AND PAY CERTIFIED ROOFING CONTRACTOR TO PROVIDE NEW ROOF PITCH BARRIES, SEAL ROOF OPENINGS EXPOSED FROM REMOVAL OF EXISTING FEEDERS. REFER TO SPECIFICATION FOR ADDITIONAL DETAILS.
19. 20. THIS BUILDING MAY CONTAIN ASBESTOS. REFER TO FRONT END SPECIFICATION FOR FURTHER INFORMATION.

EXISTING FAN TO BE RELOCATED. REFER TO DRAWING E2.2 FOR FURTHER INFORMATION. COORDINATE RELOCATION WITH MECHANICAL CONTRACTOR.

2. EXISTING MECHANICAL EQUIPMENT TO REMAIN.

3. DISCONNECT AND REMOVE EXISTING RECEPTACLE.

4. EXISTING RECEPTACLE TO REMAIN.



FILE NAME AND PATH: G:\Projects\2025\25 330 Transit East High Bay Ventilation Upgrade\3.0 CAD\3.4 Elec\25330\_E1-2\_GAX\_R\_1.dwg  
 AUTHOR: E1-2  
 LAST SAVED BY: mdelaney  
 DATE OF ATTEM: 2025-09-16 10:48 AM